AIR TRAILS

DEC. 40

AVIATION FOR EVERYBODY

NAVY PILOT MILL
AIR CORPS QUESTIONNAIRE

Championship Radio-Control for Gas Models

DECEMBER
1 9 4 0

FIFTEEN CENTS

A STREET & SMITH PUBLICATION

20 CENTS IN CANADA

Buy — Build — Fly Models that Win More Compliments, More Honors, More Prizes than Any Other Line of Models in the World

CLEVELAND

★ Class A Gas Models, $1.00 up
★ Class B Gas Models, $1.50 up
★ Class C Gas Models, $3.95 up
★ Scale Gas Jobs, $7.50 up

"America's FIRST LINE of Flying Models"

★ Cleveland's AIRCAR, $4.50
★ Soaring Gliders, 50c up
★ ¾" Scale Models, 95c up
★ ½" Scale Models, 25c up

The "Fantasy of Flight" Series

These flying Models are the Most Unusual ever designed. (Patents Pending). They always attract loads of attention. Build the complete Series.

25" Dragonfly N-1
25" Swallowtail Butterfly N-2
25" Bluejay N-3
25" Vampire Bat N-4
25" Barn Swallow N-5
25" Flying Fish N-6
(No order for less than two)

Worth 2 to 8 times the price, but each kit only **25c**



"Tribute to Brave Nations" Series

This Series brings you 6 different types of Models. Properly adjusted they fly so well, they have been aptly nicknamed the "Mile-Fliers."

32" Norseman C-1 (Cabin Model Illustrated above)
32" Flemish Defiance C-2 (Stick Model)
32" Czechoslovakia Interceptor C-3 (Low Wing)
32" Polish Valor C-4 (Gas Type)
32" Flying Dutchman C-5 (R.O.W. Stick)
36" Austrian Chivalry C-6 (36" Glider)
(No order for less than two)

Worth 2 to 8 times its price, but each kit only **25c**

Playboy Sr. — Piling Up Record of Wins!

First in Cleveland! First in Akron! Second in Elyria! Second in Toledo! Fifth in New Phila! Sixth in Chicago Nationals! And many, many others! Here's Bill Schwab, and his mechanic, Sonny Wilhelm (at right) with the record-breaking Playboy Sr. that's winning contest after contest—the same model that twice broke the world's record within 7 days. Regular stock model which any modelbuilder can make. Get it, build it—get in "the money." Looks and flies like the champion it is. Class "C." Huge 80" span. Complete Kit GP-5017 (except power unit) only..... **$3.95**

Contest-Winning Gas Model

Nothing Better for Gas Model Beginners

KIT NO. GP-5004 except power unit. **$2.50**

More Contest-Winning Gas Models

CLEVELAND VIKING

Span 48". Kit GP-5020 (complete except power unit)..... **$1.50**

CLEVELAND FLEETSTER

Span 42½". Kit GP-5002 (complete except power unit).. **$2.50**

Unique

"ITSY-BITSY"

New monowheel design. Span 38". Kit GP-5016 (complete except power unit) only..... **$1**

Fast-Flying
PLAYBOY JR.

Span 16". A flying beauty and a consistent winner. Kit GP-5006 (complete except power unit). Only..... **$2.50**

BIG DOLLAR VALUE!

Popular
BABY PLAYBOY

Span 25". Use either rubber, or Mighty Atom. Kit GP-5008 (complete except power unit) only..... **$1**

One of Scores of Cleveland Authentic SCALE MODELS

BOEING P26A. Forerunner of most modern fighter planes. Span 21". Complete Kit SF-60.....$2.25
Span 14". Dry Kit D-60.....85c

Gliders *for Indoors & Outdoors*

CLEVELAND DARTS
Builds 2 Class "A" Indoor Complete Kit E-5009
25c

CLEVELAND ARROW
Class B Indoor. Span 18". Complete Kit E-5010
25c

CLEVELAND JAVELIN (above) Class B Outdoor. Span 20"—Complete Kit E-5011.. **25c**

BIG 7-FT. SPAN

CLEVELAND CONDOR Soaring Glider. Span 84". Class D or E. Complete Kit E-5019..... **$1.00**
CLEVELAND EAGLET Soaring Glider. Span 48". Class C. Complete Kit E-5018..... **50c**

Send 10c for Complete Catalog

- RITE PITCH GAS PROPS
- FLO-TORQUE GAS PROPS
- AUSTIN-TIMERS & SUPPLIES
- SMITH COILS & CONDENSERS
- VOIGHT WHEELS
- PRECISION CUT BALSA
- DOOLING DALLAIRE-SYNCRO - BREMER WHIRLWIND RACE CARS

In addition to all the models, shown on this page, this catalog features scores of others, including Indoor and Outdoor Gliders, "Sticks," Microfilm and Wakefield jobs, 25c to $1.00, also thousands of all needed parts, supplies and tools.

Send 10c for your copy today—NOW!

Sky-Tested Models

CLEVELAND THERMALIER. Class C Stick Span 30". Complete Kit E-5014 (except rubber)
50c

Graceful as a gull

CLEVELAND WAKEFIELD "GULL" Span 45". Complete Kit E-5015 (except rubber)..... **$1.00**

ORDERING INSTRUCTIONS

If your dealer can't supply you, send check or money order—cash at own risk. Minimum order 50c. Include 15c for packing charge and postage on orders under $1.50. Shipments outside U. S. add 10%. (Remittances must be in U. S. Funds.) For P. P. Special Delivery in U. S. add 25c. (Ohio residences only add 3% sales tax.)

DEALERS! This is a record-breaking Cleveland year—get your share of this big, profitable turnover. Phone or write your jobber at once for all new models—most better jobbers carry them.

"Cleveland Models Win More Compliments, More Honors, More Prizes Than Any Other Line of Models in the World"

CLEVELAND MODEL & SUPPLY CO., INC.

4508D119 Lorain Ave. *"America's FIRST LINE of Models — Since 1919"* **Cleveland, Ohio, U.S.A.**

At right—For more than 13 years men trained for leadership in commercial aviation at Parks Air College have entered the industry and advanced to such positions as Chief Engineer, Chief Meteorologist, Chief Pilot, Captain, First Flight Officer, Traffic Manager, Factory Manager, Department Supervisor in manufacturing, Superintendent of Maintenance, and many others.

At left—At Parks Airport No. 2 is based all military flight training. A third field of 100 acres supplements this landing area. This arrangement permits the conduct of military aviation training and commercial aviation training by Parks Air College with the minimum of interference and the maximum of efficiency in both.

For Leadership in COMMERCIAL AVIATION

Select Training of Leadership Calibre

TO YOU who have shown superior merit in preparatory school or college, Parks Air College offers training for positions of trust and responsibility in commercial aviation.

You have four courses from which to select: Professional Flight, Aviation Operations, Aeronautical Engineering and Maintenance Engineering. In each, practical training is emphasized. Each is specialized and at the same time comprehensive in its particular field.

You find that the practical application of all training and the entire atmosphere of the College, which is distinctly aeronautical, stimulate and develop the interest that first prompted you to consider aviation as a career field.

Though development of skill is emphasized, your training should and will go much farther than that. In order that you may have the grounding necessary for advancement, you will become acquainted, in addition, with basic principles relating to your particular field within aviation.

To put it another way, you become familiar with the *Why* as well as the *How* of doing things. This is important for your advancement in aviation will depend upon your *Understanding*, your *Reasoning Ability*, your ability to solve the new problems continually arising in aviation.

Graduates of Parks are providing proof of the value of Parks training. You find them in positions of trust and responsibility through all of aviation, such as Factory Manager, Chief Engineer, Chief Pilot, Captain, First Flight Officer, Traffic Manager, Department Supervisor in manufacturing, Superintendent of Maintenance, Station Agent, and many, many others. In addition, a number have made their own jobs. They are conducting successful aeronautical enterprises of their own.

If you are determined to achieve leadership in commercial aviation, acquaint yourself thoroughly with the training opportunities offered you by Parks Air College.

You are invited to send for the 64-page catalog. It will be mailed you free on receipt of your request.

Pertinent Facts About Parks

Parks Air College was founded August 1, 1927.

Has enjoyed full Federal approval longer than any other aviation school.

Is accredited in its Aeronautical Engineering School by the Illinois Superintendent of Public Instruction.

Is accredited by the United States Office of Education of the Federal Security Agency.

Graduates are qualified educationally for appointment as flying cadets in the U. S. Army Air Corps and for flight training in the U. S. Naval Air Reserve.

Has a capacity enrollment of 300 commercial aviation students, 216 U. S. Army Air Corps flying cadets and 48 enlisted mechanics.

Has its own airport with a school plant of 25 buildings devoted to school purposes entirely, also two fields of 568 acres and 96 acres for military flight training.

Has a faculty of 73, each especially qualified for his particular field of instruction.

PARKS AIR COLLEGE Section AT-12
East St. Louis, Illinois.

Please send me details of four major courses in commercial aviation training.

Name.....Age.....

Address.....

City.....

State.....

PARKS AIR COLLEGE East St. Louis, Illinois

The AVIATION INDUSTRY needs Trained Men

UNLIMITED OPPORTUNITIES are open to trained men in Aviation. Sheet metal workers, aircraft mechanics, layout men, assembly men and many others are urgently needed to build, service and maintain the rapidly increasing number of military, commercial and private aircraft.

At Luscombe you will receive thorough preparation in the field of your choice and be ready to take your place in an aircraft factory, with an airline or service station.

There is a constant demand for Luscombe Trained men throughout the aircraft industry and we will welcome the opportunity to acquaint you with our school.

Make Your Selection Today

LUSCOMBE SCHOOL
OFFERS FOUR PRACTICAL COURSES FROM WHICH TO CHOOSE:

1. ONE YEAR Government Approved MASTER MECHANICS COURSE Leading to an A. & E. License.
2. 8 MONTHS Government Approved ENGINE MECHANICS COURSE Leading to an Engine Mechanics License.
3. 8 MONTHS Government Approved AIRPLANE MECHANICS COURSE Leading to an Airplane Mechanics License.
4. 3 MONTHS SHEET METAL COURSE for Aircraft Production.

"Luscombe Graduates will be found wherever airplanes are built, serviced or repaired—better than 98% placed."

NEXT CLASS STARTS JAN. 6, 1941

LUSCOMBE
SCHOOL OF AERONAUTICS
(Division of Luscombe Airplane Corp.)
DEPT. "R" WEST TRENTON, N. J.

ONE YEAR GOVERNMENT APPROVED COURSE leading to an A.&E. License or to Specialization in Factory Production of Modern Airplanes

AIR TRAILS

A STREET & SMITH PUBLICATION

DECEMBER, 1940 — VOLUME XV NO. 3
15 CENTS PER COPY — $1.50 PER YEAR

FEATURES

NAVY PILOT MILL . . . . . By John R. Hoyt 8
DESTINATION UNKNOWN 10
AIR CORPS QUESTIONNAIRE 12
BREAK FORMATION! . . . . . By James L. H. Peck 14
FINE FEATHERS MAKE FINE BIRDS . . . By Hans Groenhoff 16
ENGINEERING MADE EASY . . . . . By Peter Bowers 18
IT TAKES PULL! . . . . . By Alexis Dawydoff 20
BOMB BOX 21

DEPARTMENTS

WHAT'S YOUR QUESTION? 19
AIR ADVENTURERS . . . . Conducted by Albert J. Carlson 22

MODEL SECTION

MODEL MATTERS 23
THE ARROW . . . . By William Gibson and Howard Becker 26
GOODS' CHAMPIONSHIP RADIO MODEL (2) By Walter and Bill Good 30
FAIRCHILD PT-19 ARMY TRAINER . . . . By Earl Stahl 35
LANZO NATIONALS STICK WINNER . . . By Chester Lanzo 38
FULL-COLOR COVER PHOTO OF GRUMMAN MIDWING BY RUDY ARNOLD

C. B. COLBY . . . . . Editor
WM. WINTER . . . . . Associate Editor
ALEXIS DAWYDOFF Gliding & Soaring Editor
GORDON S. LIGHT . . . . Model Editor
ALEX D. SNIFFEN . . . . . Art Editor

Monthly publication issued by Street & Smith Publications, Incorporated, 79 Seventh Avenue, New York City. Allen L. Grammer, President; Henry W. Ralston, Vice President; Gerald H. Smith, Treasurer and Secretary. Copyright, 1940, in U. S. A. and Great Britain by Street & Smith Publications, Inc. Entered as Second-class Matter, January 11, 1937, at the Post Office at New York, under Act of Congress of March 3, 1879. Subscriptions to Canada, $2.00; Countries in Pan American Union, $1.75 per year; elsewhere, $2.25 per year.

All characters used in fiction and semi-fiction stories in this magazine are fictitious. We cannot accept responsibility for unsolicited manuscripts or artwork. Any material submitted must include return postage.

Printed in the U. S. A.

You can Z-O-O-M into an AVIATION CAREER!



IN THE VERY CENTER AND A VERY IMPORTANT PART OF SOUTHERN CALIFORNIA'S GREAT AIRCRAFT INDUSTRY IS LOCATED CURTISS-WRIGHT TECHNICAL INSTITUTE

Established in 1929, in twelve years this famous school has come to be recognized as the nation's leading institution in the training of Aeronautical Engineers and Master Mechanics. Mr. Donald Douglas, President of the great Douglas Aircraft Company, chose this school for his own son's training which pointedly indicates the high standing this school has attained in the aircraft industry.

You, who plan to invest in a course of career training to prepare yourself for the future, must determine in advance what the returns will be on your investment before you put cash on the line. This is imperative since your choice of a school in which to take your training will determine how much money you will make all the rest of your life. Your whole future in aviation depends on your training.

Curtiss-Wright Tech's career training is carefully designed to do just one thing:—TO MAKE MORE MONEY FOR YOU so upon graduation you can be independent and self-supporting for life. For years our hundreds of successful graduates have proven that Curtiss-Wright Tech training gets results and always pays. It has provided them with a profitable occupation and secure future since it trained them in advance for the highest position they could ever expect to occupy. It can do the same for you.

Aviation needs trained men. They are in demand and at a premium. Advancements for them are rapid, especially here in Southern California where there are over $234,000,000.00 in unfilled aircraft orders on hand and where over fifty per cent of all aircraft manufactured in the United States is made. You can get in on the ground floor by training now. BUT you must choose the right school for your training.

Our graduates are obtaining immediate employment and the demand for them far exceeds the supply. We honestly believe that every student who enrolls here will be able to obtain, with our assistance, immediate employment upon graduation. This school has never guaranteed or promised positions for its graduates, but practically every graduate has obtained immediate employment, and is advancing steadily.

WARNING!—"don't miss the boat." The greatest opportunity of your lifetime exists today! There never was such an opportunity in aviation for you; there may never be another. A position awaits you. Insure for yourself a steady income and independence for life. Send in your enrollment today before you "miss the boat."

CURTISS WRIGHT TECHNICAL INSTITUTE

GRAND CENTRAL AIR TERMINAL, 1228 AIRWAY, GLENDALE (LOS ANGELES) CALIF.

UNDER PERSONAL SUPERVISION OF MAJOR C. C. MOSELY, OWNER, SINCE ITS ESTABLISHMENT IN 1929

Contractor to the U. S. Army Air Corps

Offering specialized and proven training in

AERONAUTICAL ENGINEERING AND MASTER MECHANICS

NO FLYING INVOLVED

THIS TOWER OVERLOOKS AVIATION'S MOST DISTINGUISHED SCHOOL OF AERONAUTICS

Without cost or obligation send me full information and catalog on the course checked below. AT-12

- ☆ **AERONAUTICAL ENGINEERING — MAJOR CAREER COURSE (14 MONTHS)**
  - ☆ Post Graduate Aeronautical Engineering Course (8½ months)
  - ☆ Aeronautical Drafting Course, home study (4 months)
- ☆ **MASTER AVIATION MECHANIC—MAJOR CAREER COURSE (1 YEAR)**
  - ☆ Specialized Aircraft Engine Course (8 months)
  - ☆ Specialized Aircraft Sheet Metal Course (3½ months)
  - ☆ Specialized Airplane Manufacturing & Maintenance Course (8 months)
  - ☆ Aircraft Blue Print Reading Course, home study (4 months)

NAME _____ ADDRESS _____

Use this handy Coupon TODAY!

PHANTOM Motors

PACK THE POWER!

Holds 3 Official World Records

A thousand thrills await you with the new official record holding Phantom Torpedo and Bullet. You won't believe your eyes when you see their streamlined beauty, or your ears when you hear the drone of their power packed engines. You will say it isn't possible to sell such fine engines for so little. But it is. That's because Phantom engines are sold direct from factory to you... No in-between profits, you save the difference.

We challenge anyone to show you finer motors that can be bought anywhere near our new prices.

Order now! Start winning some of those contests you've been dreaming about. Fill out the handy coupon below and we'll have your engine rocketing on it's way to you in less than 24 hours after we receive your order.

BULLET & TORPEDO CLASS "B" ENGINE FEATURES

- New special heavy duty type radial motor mounting (replaceable plus standard beam mounting). • Special float type gas gauge (Torpedo only). • Newly designed larger sturdier gas tank made from Magnesium alloy. • Gas tank can be mounted on either side of the fire wall. • All motors equipped with the new Smith "Fire-Cracker" Coil. • Torpedo produces almost 1/5 horsepower with weight of 4¾ oz. Bullet produces almost 1/6 horsepower with weight of 4¾ oz. • Motors built to be used upright or inverted. Your motor on its way 24 hours after order received • Every motor power block tested in our factory and sold to you under a bonded factory guarantee.

TIME IN AIR

On October 1, 1938, Phantom broke the official world's record for time in air. Time: 2 hours 46 minutes 43 seconds non-stop.

AIR MILES FLOWN

On the same date a Phantom powered ship broke the official world's record for number of airline miles flown. Miles covered: 55 airline miles non-stop.

ALTITUDE

Again on the same date a Phantom powered ship broke the world's altitude record. Altitude: Climbed to an elevation of 11,500 feet.



now! $7.25

now! $10.95

PHANTOM MOTORS

800 East Gage Ave., Los Angeles, California

Prices slightly higher in foreign countries.

PLEASE RUSH THE ITEMS CHECKED BELOW:

☐ Money-order enclosed ☐ Send C. O. D.

☐ New improved 1941 Phantom "Bullet" complete with coil, tank and condenser	$ 7.25
☐ New Super Phantom "Torpedo" engine complete with coil, tank and condenser	10.95
☐ Special 11 inch hardwood propeller	.49
☐ Miss Tiny Kit, Propellor and Phantom Built "Bullet"	11.95

Add 3% if delivery point is in California

NAME_____

ADDRESS_____

CITY_____ STATE_____

A-12

SPECIAL 4 to 24 MONTHS AVIATION TRAINING

Geared to National Defense

California Flyers gives you the opportunity to answer the call of aircraft plants and airlines for more skilled men with a training program *geared to national defense needs.* This training, by concentrating on the practical, thorough and proven instruction specified by the industry itself, prepares you in this short space of time not only for a position, but a career, in aviation. So highly approved is California Flyers training, *we cannot supply the demand for our graduates.*

This intensified instruction places you in Production Mechanics or Aircraft Drafting in 4 months, Master Mechanics in 12 months, Aeronautical Engineering in 14 months and Commercial Piloting in 10 to 24 months. And by thus cutting down the time between enrollment and employment, the student not only is in a position to support himself in a shorter time, but finds that his tuition and living costs are greatly reduced.

Why is there such a demand for our graduates?

It is obvious once you have heard the complete story of this famous school. Its founders believe that aviation should be taught in a school where the student remains an individual — learning aviation as it pertains to his individual ambitions and qualifications, and by so doing preparing *him* for the responsibilities of leadership. This way the graduate is prepared to meet today's aviation problems and to contribute to tomorrow's aviation advancement. This is the way today's leaders learned. Only this way can a training program be built for the industry, on industry's specifications. They believe too, that the entire field of aeronautics — engineering, mechanics and piloting are all closely interwoven and that a student should train in a school that teaches all of these important divisions. Above all, they believe that aviation should be taught in an environment of aviation activity, taught where there is the greatest number of men actively engaged in aviation. This is why California Flyers is located in the heart of the world's aviation capital on the world's busiest test field.

IMMEDIATE ACTION REQUIRED

If this is the kind of school that you would like . . . friendly, modern and thorough; if it is *action* you want, write today for further information about this training, geared to national defense needs. California Flyers' new, 64-page catalog, just off the press, tells today's story of aviation at work, complete details of the training courses and how easily and quickly you can become a *California Flyers man,* doing your share for national defense.

Approved by the Civil Aeronautics Authority of the United States Government for Flight and Ground and Master Mechanics Courses

CALIFORNIA FLYERS, INC.

SCHOOL OF AERONAUTICS

LOS ANGELES MUNICIPAL AIRPORT, INGLEWOOD, CALIFORNIA

LEARN ABOUT THIS COMPLETE RANGE OF PRACTICAL CAREER COURSES

CALIFORNIA FLYERS, INC., School of Aeronautics, Dept. AT-12
Los Angeles Municipal Airport, Inglewood, California

Please send me your catalog and complete information on training, tuition, living conditions and employment opportunities. I am over 16 and interested in the subjects, checked:

Aeronautical Engineering ☐ *Airline Piloting* ☐
Production Mechanics (Aircraft sheet metal) ☐ *Aircraft Drafting* ☐
Instrument and Radio Beam Flying ☐ *Master Mechanics* ☐
Instrument Technician ☐

Name_____ Age_____

Address_____

City_____ State_____

Big moment! The reserve pilot takes off in standard trainer, the reliable N3N-1.

Below—From N3N-1 to SBC-4s is a long jump, but they're goal of all cadets.

Author's home port. Three instructors at the Grosse Ile, Mich., Naval Reserve Aviation Base fly formation for edification of student group.

In the East the U. S. Naval Reserve Base at Floyd Bennett Field is important as a "pilot mill." Below in foreground are Reserve hangars.

NAVY PILOT

Our naval reserve bases will "grind out" 1600 pilots per month. Here's a start-to-finish picture of the training Mr. Civilian will get.

FANTASTIC, absurd—that's how it struck anyone familiar with existing training facilities. "Navy to Train 1,600 Pilots a Month," the headlines screamed when Secretary of the Navy Knox warned that we are confronted with "the most grave crisis we have ever faced in our history." To meet this crisis three new naval reserve aviation bases were planned. The nation had finally awakened to the cruel realization that it needed pilots—thousands of them—not tomorrow, but immediately. Where were those additional pilots to come from?

Few of us knew that during the four years from 1936 to 1939 the navy's aviation cadet program had turned out only 775 pilots. How could the navy hope to turn out 1,600 pilots in one month, when it had gained less than that number in four years? Where were the planes, instructors, fields, mechanics, hangars, overhaul shops and station keepers to be found?

Very fortunately, there had come from the navy in 1919 a number of reserve aviators who had clung grimly to the idea that the naval reserve would be of value in some future emergency. Through the lean and barren years of the depression, they had squeezed small appropriations from Congress to maintain the thirteen naval reserve aviation bases that Congress had set up by the Act of 1925, located near major centers such as Boston, Philadelphia, New York, Washington, Miami, Detroit, Chicago, St. Louis, Kansas City, Minneapolis, Los Angeles, San Francisco and Seattle.

In the last few years, the naval reserve base (NRAB) has become what business men call a "going concern," set up, operating, and actually doing business. That fact alone is what may save the time that is now so precious, the fact that the NRAB is already operating and merely has to be expanded. Where ten students a

Watchful waiting. These U. S. N. R. cadets patiently await their turn at the N3N-1 trainers. Note their deflated rubber life vests.

MILL

BY JOHN R. HOYT

month went through, one hundred will be trained; where four or five instructors toiled, twenty-five will sweat. Where only thirty or forty applicants met the examining doctor to have eyes, heart, lungs and general fitness tested, several hundred each month must apply!

In other words, each NRAB will become a veritable pilot mill, grinding out one hundred fliers or so each month. When the three new NRAB's are built, there will be a total of sixteen bases and at any one of them you may apply for navy training—with something like the following questions to start you off:

"How old are you?" (Between twenty and twenty-seven is acceptable.)

"Are you single?" (The answer must be yes.)

"Do you have a college degree?" (If you have only two years of college, you must have had certain subjects in mathematics.)

"Are you physically fit?" (Your answer doesn't mean much—the doctor will take care of that for you!)

You must furnish a transcript of your college work, a birth certificate and letters of recommendation. If all goes well you'll be interviewed by a board of officers, who will select the applicants on the basis of qualifications, appearance and personality—so carefully that the percentage of students eliminated at NRAB's has been estimated at less than fifteen percent. Let us suppose that you make the grade.

On a day set by the navy department you will report to a NRAB—we will presume that you go to the base at Detroit, located on the tip of a small island called Grosse Ile (pronounced grose eel) just south of the city. This base is an integral unit, independent of all others, operated for and by reserve officers and commanded by an officer from the regular navy.

Here you will train for thirty days. Here you will receive ten hours of primary dual-control instruction. And here, if you meet the requirements, you will be given an appointment as an aviation cadet and sent to Pensacola, Florida, for advanced training. (According to the secretary of the navy, there will be additional advanced training centers, because there are limits beyond which Pensacola cannot be expanded.) *(Turn to page 56)*



Sock to be socked. This long wind sock is really a sleeve target to be towed behind a plane while it is shot at by cadet pilots.

U. S. N. R. on parade. Here we see the Floyd Bennett Field unit lined up for inspection. Ships: SBC-4s, Voughts, Beechcraft and Grumman.

DESTINATION UNKNOWN

Naval air corps cadets learning about lighter-than-air craft receive their preliminary training in these "free" balloons. Up you go—to wherever the wind decides!



Full house. Here in the Lakehurst hangar we see four of these training balloons ready for flight.



Inflation in the navy. Before take-off each balloon is carefully inspected and inflated. Lead weights hold the bag and net to floor.



Last stages of inflation. Sandbags hold bag steady while basket is attached.



Walking it out into the open. Crew, ballast and all instruments are aboard as ship leaves dock.

Take-off. A handful of sand falls and up goes the ship. Note pigeons in their box.

Destination unknown. Up into the sky sails the balloon to drift with wind currents until it lands. Note coiled drag-rope brake.



Well, how're we doing? An officer checks box containing altimeter, thermometer, and variometer. Direction of flight may be changed only by entering air layers flowing in different directions. Radio tells where they are.



Coming events cast their shadows. Gradually losing altitude, the balloon crew plans to land.

Valving helium through top vent as seen through the balloon's appendix.



Coming in for one-point landing. Hanging onto the rigging, crew waits as the basket plows through shrubs toward the landing spot.



Down and out. Open rip panel at top empties bag of helium the moment basket reaches ground.

Grab her, boys! Sailors who have followed flight of balloon via truck arrive to assist in packing and retrieving the basket.

Messages to Lakehurst. Carrying messages of crew and destination, these two carrier pigeons start winging toward the home base.

Now for home. All is packed. Let's get going.

AIR CORPS

Questions on entrance requirements are easy —but form only a fragment of those asked. Come sit beside the information officer in one corps area as he does a day's work.

The goal of every applicant: the back seat of a regular army trainer. Here the instructor in the front seat demonstrates use of Gosport tube.



QUESTION: What is a flying cadet?

Answer: A flying cadet is a student flier who has the unique advantage of being paid to learn while learning. Congress created this grade in the army in 1919. The training he receives cannot be equaled in any school in the land. Successful candidates have jobs waiting for them upon completion of the course. While learning they are paid $75 per month plus $1 a day for food.

Question: What is the difference between a flying cadet and an enlisted man in the regular army air corps?

Answer: A man in the regular army cannot become a commissioned officer under normal circumstances as he is not trained with that goal in view. Flying cadets are trained with the purpose of giving successful candidates a commission as a second lieutenant, air corps reserve. They go on active duty upon being commissioned. Then, too, a flying cadet is paid $75, while the pay of a regular army soldier is only $30 per month.

Question: Is C.A.A. or private flying instruction of much value?

Answer: Yes, but not to the degree that it would pay a candidate to forgo appointment until such time as he has received some training.

Question: What are the age limits?

Answer: Between the ages of 20 and 27. To be eligible for a commission as a second lieutenant, candidates must have reached their 21st birthday at time of appointment. For this reason men under 20 years of age are not acceptable since it is the policy of the war department to appoint successful candidates as second lieutenants upon completion of the eight months' course. Men under 21 years of age must have the written consent of their parents. When an applicant has reached his 27th birthday, his name is taken off the eligible list, and, as it normally takes between two and three months to examine and appoint a flying cadet, men with less than three months to go before their 27th birthday, have very little chance to be appointed.

Question: What are the education requirements?

Answer: Applicants must have two years of college to be accepted without a mental exam. Two years of college means half the credits required for a degree. Nothing short of this

QUESTIONNAIRE

is acceptable. Experience is not considered the equivalent. Those lacking the educational requirements are required to take a mental exam. This exam is given after the applicant has successfully passed the physical exam. The test itself is given four times a year, in February, May, August and November, and in the following subjects: United States history, general history, grammar and composition, geography, arithmetic, higher algebra, geometry, trigonometry and elementary physics. Failure to pass the mental exam does not permanently disqualify flying cadet candidates. They may take the exam again after waiting six months.

Question: You say candidates with half the credits toward a degree are exempt from the mental exam despite the fact that they may have taken a purely academic course with no mathematics or engineering subjects?

Answer: Yes, it is assumed that before entering college they will have had the required mathematics and physics. The very fact that a man has completed half the credits required for a degree demonstrates his ability to study and to learn, which after all is what is wanted.

Question: How is the physical examination?

Answer: The exam is difficult in that it covers just about everything imaginable. It is hard for anyone except a flight surgeon to make a definite statement concerning this exam. A flight surgeon, by the way, is a surgeon who is also a flier. He has a detailed knowledge of the requirements for a flier, both through his own broad experience and through countless examinations of fliers.

About the weight—overweight is a definite cause for rejection, so all you applicants who never made the varsity because of your lack of weight, take heart. As the minimum weight is rather low, the average fellow can pass that requirement. The maximum height and weight are 6 feet 2 inches, not more than 180 pounds. The minimum height and weight are 5 feet 4 inches, not less than 115 pounds.

All men who fail the physical are rejected permanently unless the defect is such that it can be corrected. When the defect is corrected the applicant must apply to the Chief of Air Corps, Washington, D. C., for the authority to be re-examined.

Detailed information about physical requirements will be found in answer to later questions.

Question: Applicants enlist for three years as flying cadets. How soon are they discharged, (a) after the course has been successfully completed, or (b) when they are "washed out"?

Answer: Candidates who successfully complete the course of instruction are discharged immediately upon completion of the eight-month period of training and commissioned second lieutenants in the air corps reserves and placed on active duty for a period of two years. Those (b) who are washed out are discharged immediately. They are not held for further service under present conditions.

Question: What other requirements must be met by prospective applicants?

Answer: Men with people depending upon them for support, either in full or in part, should not apply as their application will not be favorably considered. This may be modified slightly in the near future.

Men without a complete high-school education should not apply as the educational exam is even tougher than it appears. The fact that one failure is disqualifying helps make it so. Finally, a man normally leaves high school through lack of interest rather than necessity.

Applicants who are in the regular army, national guard or reserve officers' training corps are required to forward their applications through channels. This does not hold the application up any appreciable length of time. Men in the services mentioned above are given a preference over applicants from civil life regardless of the qualifications of the civilian applicants. Those civilians having previous military training, but who are no longer connected with the military service, are not given any preference over civilians without this training.

Question: Upon passing everything, and after having been notified of my eligibility, when do I get sworn in and when does my pay begin? Who sends me to the air field?

Answer: When an applicant is notified by the war department as to his eligibility, the letter will state the class for which he is qualified. Sometime before the class starts the applicant is notified to report to the nearest recruiting office at his own expense to be sworn in as a flying cadet. Once he is sworn in his pay starts, and continues to and including the date of his discharge. The army sends him to the training center to which he must report for primary instruction. His uniforms are provided him and every effort is made to see that he is quartered in the best accommodations available. *(Turn to page 62)*



BREAK FORMATION!

Dress parade. Republic P-35s in close formation make three-element flight.

The peel-off. Northrop A-17As break formation for attack bombing.

What happens in aerial combat? How does a squadron leader maintain tactical unity? Just why and when is formation broken?

BY JAMES L. H. PECK

THE above questions are typical of the ones being asked nowadays on air-force fighting, and in the answer to each of them "organization" is the keyword.

Strange though it may seem, employment of air power this troubled world over follows certain fundamental procedures or patterns; although each nation must, necessarily, strive to outwit the other in the hope of gaining command of the air. One of these basic patterns is the three-plane fighter unit, which is being universally employed. This smallest of tactical units is known as the *element* in the air corps and the *section* in the naval air service, and is headed by the element or section leader. The *flight* is composed of two or three elements, and is headed by a flight commander. Second in charge is the deputy flight commander, who may lead the second element or fly in that of his superior, as circumstances dictate. This unit is known as the *division* in the navy. The squadron—which designation is used by both services—consists of three or more flights. In addition to his flight commanders, the squadron commander, is supplied a staff of officers who relieve him of the minor details of administration and tactics.

The *group* is made up of three or more squadrons, and the group commander is usually an older flier of wide experience. A *wing* comprises two or more groups—a whole lot of airplanes. So many, in fact, that the wing commander is rarely less a personage than a brigadier general who, as such, is directly responsible to the chief of the air corps. The pursuit group is the largest formation of craft that is usually dispatched on a mission—unless the whole enemy air force is running amuck—because it is the biggest tactical unit which normally operates under the control of one individual. The squadron is capable of acting as an independent command and is, therefore, the most commonly employed.

How is it employed? When?

In offensive strategy, against hostile combat patrols of all sorts, against reconnaissance, and even troop concentrations. In defensive strategy, missions attendant on the protection of a city or other vital area, protection of airdromes, lines of communication, and friendly reconnaissance, and in direct "support" of other arms such as attack, bombardment, reconnaissance, or utility (troop transports, staff planes, ambulance craft, or freighters). The part pursuit plays in helping to achieve and maintain command of the air is quite obvious. To carry out these assignments, flight patterns, or formations, are employed to (1)permit a number of ships to be maneuvered under a single command, and (2) obtain the highest possible concentration of fire power. There are *combat* formations and *search* formations. The former may be offensive or defensive, and of these, there are two types: *open* formations, wherein the planes are spaced far enough apart to maneuver but are within supporting distance of one another, and *extended* formations, for comfortable cruising and patrol work. An occasionally used third type known as *close* formations are wing-touching patterns employed only for close-order drill and exhibition work.

"Wait a minute!" hollers a client. "Let's get this straight. First it's elements, then flights, squadrons, groups, and wings. Then

there are combat formations and search formations, and either of these kinds may be flown close, open, or extended." He hesitates a moment, says, "Correction, search formations are always flown extended, so as to cover more area—right?" Right.

The squadron is, of course, under the tactical control of the squadron leader, but this control is exercised through his flight commanders and their deputies by one, or a combination of three methods. "Indoctrination," meaning that pilots have been trained and drilled in the execution of V's, echelons, stagger formations, and variations of these basic patterns; radio command; and visual signals of various sorts. Pilots who have been thoroughly indoctrinated require only preliminary orders concerning disposition of forces, and the command to attack.

So that the squadron may know the details of the mission, "combat orders" are posted. Information supplied by Intelligence reveals the position, strength, et cetera, of the enemy forces and of friendly elements—ground and aerial. The main provisions include:

The route out (direction from which objective or area is to be approached).

The route back (usually, the most direct line of flight to the home airdrome). *(Turn to page 52)*

"Rat-race" beginning. These training Boeings break formation to chase each other's tails in deadly circle. Each protecting plane ahead.

Shadow boxing. This A-17A flight of two three-plane elements flies low over the ocean on tactical mission. Personally, we'd want our wheels safely up.

Going to work. This unusual photo shows an eighteen-plane squadron composed of two flights of three elements each in attack maneuver.



Culver Cadet has guarantee of 120 m.p.h. This is the only light plane with completely retractable landing gear.





FINE FEATHERS *make*

Ahead of itself. The Ercoupe, clean and sturdy in design, has twin rudders. Great stability and tricycle gear let ship land itself.

The smart appearance of the current light plane hides a multitude of amazing technical improvements.

BY HANS GROENHOFF

Al Williams likes 'em fast but he likes the Stinson 105 also for its slots, flaps, hydraulic brakes, good looks.

Right—Pioneers in all-metal construction for light planes, the Luscombes have made an enviable record for themselves in recent months. This shows the new Silvair.

Taylorcraft's modern version of the light plane has done much to make this branch of flying popular. These economical ships are good-looking and safe.



Light plane luxury. This modern interior and plastic instrument board is but one of reasons for popularity of 1941 Aeronca Super Chief.

Family fun. Excellent visibility of the new Cub is demonstrated by Al Bennett and "company." Note modernized engine cowling and spinner.

FINE BIRDS

BACK in the year 1932 Joe, a good friend of mine living a half hour's ride from New York in the lowlands of New Jersey, owned a car known as the Model A Ford, a good little car with a reliable four-cylinder engine. It was cheap in price and cheap to run. But its looks were cheap, too, compared with the automobile of today. It had none of the smooth flowing lines of the 1941 models. In the same year Joe also had one of those queer-looking light airplanes which was cheap in price and cheap to own. Its appearance never made much of a hit. It, too, had a reliable little engine, but scarcely enough power, and it was looked at with much suspicion, if not with a sneer, by the old-timers at his airport who flew circles around him in high-powered expensive ships. Joe's flivver of the road was the mass product of an industry many years old. His flivver of the sky was something entirely new.

Today in 1940 Joe again owns a Ford, but it's larger and more powerful. Its body is streamlined, its interior more cheerful and more luxurious. He also owns a brand-new light airplane which is in every respect as well finished, as comfortable and as luxuriously equipped as his car. Its engine is considerably more powerful than the one in his old model. It's equipped with a muffler and it runs like a clock.

The interior is soundproofed, heated and ventilated. Upholstery is colorful and comfortable and the appearance of the instrument panel will stand comparison with that of any modern car. With power and range added, Joe's flivver is constantly being used for cross-country travel. No longer is his flying confined to the four boundaries of the airport, and no longer need he flee to the protective cover of the hangar when a slight breeze blows across the field. Moreover, his pilot friends have ceased poking fun at his little craft, for most of them are now flying similar ships.

What the flivver of the road has accomplished on the highways, the flivver of the air is now repeating in the sky—and in a comparatively shorter time. Even mass production is developing to a point where one manufacturer already is producing 400 complete airplanes a month. Judging from recent developments in the light plane, much of the progress would have seemed incredible only five years ago. *(Turn to page 61)*

ENGINEERING MADE EASY

While giving you no scholastic credit, experience in model building is a big help when you're ready to go to aeronautical school.

BY PETER BOWERS

Thank Heaven for "slip-sticks"! Pete and his trusty slide rule ponder a weighty equation in the Boeing drafting class.

DURING the course of a long model-building career, I have often been asked just what I got out of model airplanes besides a lot of exercise and a flat pocketbook. I always managed to defend the hobby in some way: by saying that I was developing good craftsmanship, or that I was learning how an airplane flew. I wasn't aware at the time just how much I really was getting from it. I didn't know then that the boy who builds model airplanes closely parallels the course of the engineer who builds the real thing. Both accomplish the same thing, the boy turning out a model by trial-and-error methods, the engineer producing a real plane by scientific means.

My model-building program has been a very intensive one, embracing just about every known type of model, from the most elementary glider to the most streamlined gas model, so I can safely say that I have built as many models as has anyone my own age. I may have carried it too far in some places, as my teachers and parents lost no time in pointing out, but at the same time, I was laying a sound foundation upon which to build a career.

Not until I entered the Boeing School of Aëronautics did I begin to appreciate what models had done for me. It was then that I found the difference between a model builder and an engineer to be one of degree only. Where the model maker proceeds by rule of thumb with his crude tools, the engineer constructs with scientific knowledge built on an understanding of mathematics and physics, using delicate precision tools to help him. From the very start, the experience gained in ten years of designing and building models proved its worth. The vocabulary of aëronautical terms built up by reading aviation magazines, visiting airports and talking to people connected with aviation made the study of aircraft nomenclature a pleasure rather than a task. When the instructor would ask for the definition of the term "power loading," for example, the students without previous acquaintance with the words could write the definition as given by the book, while any model builder, having had to figure power loading for contest models, could write the term from first-hand knowledge. In aërodynamics classes, the lift and drag formulas that help to produce a well-designed model provide a practice in their *(Turn to page 46)*

Rib assembly comes easy to anyone who has wrestled with the tricks of gas-model construction.



Even full-size engines are easier for one who has tinkered with gas jobs. Principles are the same.

WHAT'S YOUR QUESTION

This department will attempt to answer any questions concerning aviation. Those of general interest will appear on this page; others will be answered by mail. Inclose a three-cent stamp to insure a reply. ★ All inquiries regarding appointments for U. S. army air corps flight training should be addressed to the Adjutant General of the Army, Washington, D. C. Those concerning application for naval aviation training should be addressed to U. S. Navy Bureau of Navigation, Washington, D. C. ★ Persons interested in applying for air corps ground training, such as that for airplane and engine mechanics, riggers, instrument and radio men, as well as aerial photography and parachute work, should address the Commandant, Aircraft Technical School, Rantoul, Ill.

QUESTION: Is the Ranger-powered Fairchild 24 equipped with dual stick or wheel control? Where can I get kits or plans for models of the SB2U-1, P-36, SBC-4, A17-A and the Grumman JF-2? M. L., Fargo, N. D.

Answer: The Fairchild 24 is equipped with dual stick controls. Regarding the models of the above ships, suggest that you write to some of the model manufacturers who advertise in the magazine.

Question: I would like to know where I could get plans for a simple training glider. Would the plans cost anything? How much would it cost to build? F. C., Boissevain, Me.

Answer: Stone Aircraft Co., Box 57, Detroit, Mich., sells plans and kits for a simple primary training glider. The plans cost $8. It would cost about $150 to build.

Question: I'm planning to build a glider or sailplane. Please tell me where I can obtain information or plans to build either one. Is a license required to fly a glider? C. D., Takoma Park, Md.

Answering: Write to the Soaring Society of America, Box 71, Elmira, N. Y. You must have a glider pilot's license to fly these ships.

Question: What colleges have aëronautical engineering courses? What languages should I take in my last two years of high school? E. H., Chicago, Ill.

Answer: Regarding names and addresses of colleges offering aëronautical engineering courses, write to the Civil Aëronautics Board, Washington, D. C. In regard to languages, would suggest Spanish and Latin.

Question: Could a pilot in a closed-cockpit ship traveling at a speed of 9 G's or over bail out? Could he bail out if the wings had folded up? R. E., Boston, Mass.

Answer: You are using the term "G" wrongly. It is not the speed at which the ship travels; it's used to measure acceleration during change of attitude such as a pull-out from a dive. While subjected to a 9G acceleration the pilot would not be able to get out of a plane. If the wings folded up the pilot could bail out, provided the wings have not folded around the cockpit.

Question: Do you know of any firm which sells gliders or sailplanes in either kit form or as a finished product? B. P. W., Oakland, Cal.

Answer: Yes, the Bowlus Sailplanes, Inc., San Fernando, Cal., and the Briegleb Aircraft Co., 16005 Bassett St., Van Nuys, Cal., sell ships both in kit form and ready built.

Question: What is the price of a 1940 Taylorcraft? Can I enter naval flight training without college education? H. N., Middletown, Conn.

Answer: The prices of Taylorcraft range from $1,685 to $1,835. You must have a minimum of two years of college education to enter the naval air service for training.

Question: I would like to know where I can buy a good aëronautical dictionary or encyclopedia. P. W., Dallas, Tex.

Answer: Write to the Aviation Press, 580 Market St., San Francisco, Cal.

Question: Please give me the formula for finding area chord and maximum span of an elliptic wing. Also, what is a good airfoil for an outdoor fuselage model? S. W., Chicago, Ill.

Answer: $(\text{Span})^2 = \text{aspect ratio} \times \text{area}$; $\text{maximum chord} = \frac{\text{area}}{.7854 \times \text{span}}$; $\text{area} = \text{span} \times \text{chord} \times .7854$ (chord measured at center of wing). It is hard to say what is the best airfoil to use, as a number of model makers design their own.

Question: Where can I find pictures of modern European military planes? Do you keep back copies of Air Trails and how much do they cost? R. W., Belmont, Mass.

Answer: You can find pictures of European military planes in most aviation magazines. Photographs are obtained from photo news services. We have some back issues of Air Trails; they cost 15 cents each.

Question: Could you tell me where I can buy plans to build a small plane? About how much would a designer charge to design a small ship to my specifications? H. E. O., Schofield Barracks, T. H.

Answer: The Heath Airplane Co., Benton Harbor, Mich., used to sell plans and kits for a small single-place monoplane. Write to them about it. A designer will charge a great deal of money to do it for you. It may run into a couple of thousand dollars.

Question: Would you please give me details of the new light plane made of plastic which is being built by Howard Hughes? F. K., Salt Lick, Ky.

Answer: Sorry, we have no information concerning this ship.

Question: I would like to know the markings and identifications on pursuit planes belonging to the GHQ air force. I would like to be acquainted with all their characteristics. B. R., Great Neck, N. Y.

Answer: In our November 1939 issue we published an article by Roger F. Parkhill, "Identification of Army Aircraft," which answers all your questions. Send 15 cents to Mr. Clifford of our circulation department for a copy of this issue.

Question: I'm anxious to know if there are any clubs in New York where a girl of 16 can join. M. M. M., New York City.

Answer: We do not know offhand of any clubs in the vicinity of New York City. Suggest that you write to the managers of either the Flushing Airport, Flushing, L. I., or Floyd Bennett Field, Brooklyn. We understand that several clubs operate from these airports.

Question: What are the requirements for appointment in coast guard aviation? Where may I obtain solid model plans of the Northrop A17-A and the Curtiss P-36? G. F. P., New York City.

Answer: Regarding appointment in the coast guard, write to the U. S. coast guard, Floyd Bennett Field, Brooklyn. You might be able to obtain plans for the above ships from Cleveland Model & Supply Co., 4508D1 Lorrain Ave., Cleveland, O.

For training, auto towing is ideal. Speed is controlled by car driver; therefore, flight of student is under his direction.

If terrain does not permit other methods of launching, shock cord is used. This drops off as glider passes crew.

Although more expensive, launching winches are by far most efficient method.

Traffic flagman. Down goes the green flag and glider starts down runway.

IT TAKES *Pull!*

—to get a glider up. And skill on part of launching crew. Watch 'em handle various problems.

BY ALEXIS DAWYDOFF

When thermals are weak, or cannot be reached from a soaring slope, airplane tow is employed. This calls for skilled pilots.

NEITHER the glider nor the sailplane possesses its own means of getting into the air, and therefore some outside agency has to be used to launch them. The prime requisite for the take-off of any flying machine is attaining sufficient speed so that the wings can acquire lift. Since the sailplane lacks the engine and propeller necessary to pull it forward in order to attain flying speed and rise into the air, some other method had to be originated.

There are four distinct methods of launching gliders and sailplanes: catapulting them by means of a rubber shock cord, towing them behind an automobile or airplane, and getting them up with a winch.

The shock-cord method is the oldest and, although almost extinct, it is still used when ships are launched from hills where the take-off area is too small to permit the use of the other three. In itself it is not unlike the catapult launching used on battleships. The sudden acceleration is very great, the rate being from a standstill to approximately 40 to 45 m.p.h. in five seconds. The launching equipment consists of a length of rubber shock cord, five eighths of an inch in diameter, about 200 feet long and laid out in a V. The apex of the V has a ring attached to it which is affixed to an open hook in the nose of the glider. The tail of the glider is provided *(Turn to page 60)*





BOMB BOX

In the miniature range building at Kelly Field, Texas, students of the advanced Flying School learn observation on a small scale.

Gunfire below. From the circular galleries about the walls these student observers report the simulated artillery flashes via radio.

The man behind the "gun" works this control board to produce the tiny flashes that represent widespread artillery or bomb bursts.

Spotter's-eye view of the floor of the Bomb Box showing the diorama of the battlefield. There are six hundred lights that flash simulating shell bursts.

Down to earth. This shows the tower's floor that represents a battlefield. For size of field note the door in upper left corner.

Realism in miniature. This closeup of the battlefield diorama shows the advancing soldiers, wounded, trucks, tanks and cannon.

Unusual Douglas B18-A with machine gun blister under bombardier's post removed and faired over. Taken by Bill Jones, South Gate, Cal.

It's contagious! Here's a Martin B-10 sans nose turret, too. Taken by George Kimball of Kearny, N. J. Note fairing over turret post.

BT-9 warms up. This North American basic trainer was photographed at Newark by the same George Kimball. This is a national guard ship.

What Do You Think Aviation Owes You?

GREETINGS, Air Adventurers!

One is never quite sure how to approach the subject of "You and Aviation." We get many opportunities to talk to young fellows from all over the country and we are always interested in what they think about this great industry. We try to feel them out and we try to find out what they are thinking.

There are many, of course, who like anything about aviation. They don't care what it is as long as it is aviation and they are dabbling in it. They accept commercial or military aviation. They build models or stand on airports and watch the airliners come in. They read about World War aces or about the men in today's control towers—anything, as long as it is aviation. But there is also a group who question everything when it pertains to them or their personal interest. If they are model builders, they are model builders to the limit and they see nothing else. If they are commercial, military planes are just so much junk, and they consider anyone who shows the slightest interest in military planes as something between a warmonger and a fire-eating fanatic.

All this, of course, is good healthy competition along certain lines. These types make up aviation as we know it. They are all necessary to push the various phases of aviation.

The man we can't figure is the man who argues that there ought to be a place for him in aviation. He argues that because he only has a high-school education, aviation as a profession closes its doors to him. He is sore because he can't step into an air-corps job, with flashing wings, trim uniform and a $40,000 airplane to fly—all by himself. He also argues that since he can draw airplanes well, some manufacturer ought to make a place for him in his engineering department. He wants to fly, too, but because he can't find an "angel" who will teach him while he pays for it in working time, aviation is accused of being a closed shop.

These fellows come under the head of "grousers," to use an old-time war expression. Don't be a grouser. If you want something to happen to you, by all means wish and hope for it, but above all *do* something about it! Any man or woman, any boy or girl can get into aviation, if they really wish it, without a college diploma, or without friends on the board of directors. There's so much work open in the industry today that you can almost take your pick. But you can't get into aviation by grousing about the business.

In the first place, you must believe in aviation. Aviation does not have to believe in you. You must know what *(Turn to page 59)*

Actual size of your Air Adventurers pin.

(MEMBERSHIP COUPON)

To the Flight Commander, Air Adventurers,
79-89 Seventh Avenue, New York, N. Y.

I am interested in aviation and its future developments. the best of my ability I pledge myself to support the principl and ideals of AIR ADVENTURERS and will do all in my powe to further the advance of aviation.

Please enroll me as a member of AIR ADVENTURERS and send me my certificate and badge. I inclose ten cents to cover postage and handling

Name..... Age.....

Address.....

.....

☐ Check here if interested in model building.



Sikorsky in Hawaii. One of the Inter-Islands ships in open-side hangar being checked and loaded. Photo by Air Adventurer Hideo Murakmi, of Olaa, Hawaii.



Two of a kind. Pickaback Clipper, Atom-powered, is released at any desired altitude by Austin timer. Big brother has an Ohlsson 60. Left—Fred Frazier and Lee Sherman of San Antonio, who worked out the combination, and, below, the two ships just after releasing. The big ship speeds on; little one zooms.

Model matters

The Dope Can by Gordon Light. Contest flashes.

THE DOPE CAN. (By Gordon S. Light.) No. 230 is the room in the Willard Hotel in Washington, D. C., where Al Lewis and Bruno Marchi hold forth in the interest of the Academy of Model Aeronautics. Dropping in one night, we hinted broadly we'd like a cigar or anything else that visitors usually don't have a right to expect. But they saved those things for the cash customers and gave us several hours of model talk.

These two boys have plenty of enthusiasm and are doing a good job in putting the A. M. A. across. Do they have their troubles? Diplomacy is an unknown factor until it's been used in co-ordinating the dozens of model factions, each with a different viewpoint. The problem is to keep old members happy while new members are converted to the A. M. A. viewpoint.

Typical of the troubles is the matter of license numbers. Several members took them to task when they failed to get the same number upon renewing their license. Actually it was the applicant's fault in not writing his name and address clearly. At any rate they took the criticism smiling. Then a short time later Marchi got the ax from a boy who scornfully told him: "I got the same license number again this year. Why couldn't you change it? What's the big idea?" And that's what you're up against when you're in A. M. A. work.

The next time you sit down to write about your pet peeve, remember they probably have a few dozen letters on file calling them names for doing the things

Who said rubber events aren't popular? Look over this collection entered at Paterson, N. J., sponsored by Teaneck Kiwanis and Society of Model Engineers, Ridgefield Park.

Airacobra has nothing on this for climb. Louis Garami turns loose his latest "Degravitator" for points straight up. Uses new Atom!

MODEL MATTERS

Some of us like 'em realistic, so this streamlined Class B biplane with its cockpit is interesting. Joe Hudson, Philadelphia.

August Streuning, Maplewood, N. J., is sold on New Ruler's all-around performance and good looks. Plans from April, May A. T.

you want. Marchi and Lewis can take it and they'd like to hear from you regardless of your frame of mind.

Several puzzling technical terms were cleared up by the last issue of *Prop Wash*, club publication of the Bridgeport Aëronuts:

Rubber motor: Choice pieces of shredded inner tube.
Rubber lube: Never use the stuff myself, but hear that it is a better grade of drained crankcase oil.
Stick model: The hottest thing on wings.
One-bladed propeller: Oh, well, some day I'll carve two blades the same.

If the cold weather hasn't frozen the pond in your meadow, why not ship out and establish a hydro record? It's an easy way to get your name into the list of national records, since many of the outdoor hydro categories are blank (based on the last official release of the A. M. A. contest board, September 1st). An official R. O. W. flight of any length would give you a record in Class C fuselage, Class C and D stick, and Class A and B gas. Helicopter, ornithopter, and Class E fuselage are other fertile stamping grounds for would-be record setters.

Indoors, the list of records is practically filled. An autogiro flight of any length would do the trick. Two R. O. W. listings remain unfilled—open stick Class A and B and Class B fuselage.

The highest official gas model flight in the records is R. O. G. Class B held by Bobby Davis of Atlanta, Ga., a junior, with 21:33.8 (three-flight average). For convenience in setting a record, steer clear of the gas categories. All these flights would take plenty of time to beat, considering only the flying time itself and not the time lost hunting suitable thermals.

Have improved kits reduced the number of boys who really have

Streamlined Pacemaker, James 60, at Creedmore. Plans in January A. T. Original used a Denny.

Dan Bunch, left, and Bill Butler, pres. Southern Cal. Gas Association, are Academy supporters.

California contests are gala occasions. These are a few of the jobs at Los Angeles August 25th meet. Pits stretched for one half mile.

Count New Rulers instead of sheep when your next brainstorm keeps you awake. This one flown by Bill Mason at Lock Raven.

Well, men, are we going to stand for this? Of course we are. The gals flip a mean prop. Bunny Geteskunot, Dorris Eggert, Quaker City.

A California Champ from September A.T., by Howard and Bill Salmor, Stan Ownes.

Tomahawk, Class B, from August Air Trails, by Dick Opperman. Seen at Philly meet.

a thorough knowledge of model design, building, and flying? In many cases the beginner can get satisfactory results by assembling a kit without going through the painful learning stage so necessary in the kitless era a few years back. This pain had its reward in teaching answers to those who hung on—something the kit builder is apt to miss, since the company designer does much of his thinking for him. By following instructions with reasonable accuracy, the builder gets results without knowing why.

A new type of gas flying was in the program of the Virginia Model Association State Championships. Known as the transport class, its [illegible] is to encourage model flying under conditions similar to those of the full-size ships. A weight rule calls for fifteen pounds per cubic inch motor displacement. Take-off must be unassisted. Buddy Jacobs of Hampton won this event with a ratio of 2.43. (Usual power flight to total flight ratios are 6 to 8 with thermal flights boosting it to 24 in rare cases.)

This sort of flying should be up Buddy's alley. His father, Eastman N. Jacobs, aëronautical engineer at the N. A. C. A. laboratories, presented the idea to the Academy convention last Thanksgiving week end. In his paper titled "Comparison of the Weight and Power Requirements of Model and Full-scale Airplanes," he pointed out that models flown under contest rules are overpowered and much too lightweight to be truly a scaled-down version of a large airplane. Yet a scaled-down model is the only type presenting the same problems of design and construction as the prototype. Model experiments will represent much more in actual research value if they are conducted on the basis of a true flying scale model of some type of airplane. Using Froude's Laws of Comparison, he *(Turn to page 53)*

Idea of the month. Outer third of wing folds against bottom of wing for high, spiral climb; timer release springs tips into place for superglide. Amazing! By Herb Drake, Easton, Pa.

Maximum performance with minimum of plane. It's a Class C boom tail by Charles and Ted Ipsen, at Lock Raven, Md., meet.

"Yehudi," Jerry Stoloff's pontoon job, uses three floats. Note curved step on main floats.

Air raid! Vosa, Trenton Model Engineers, gets off 14-footer. Co-designer, Chester. Molnar engine.

We all like the scale jobs. This Brownie-powered S.E.5 was built by F. Hernandez, Audubon, N. J.

THE ARROW

Champion A job of the Nationals, it flew 47:32 to set a national record. It's a winner, Class A or B.



Wing mounting pylon detaches from fuselage, giving easy access to batteries and timer.

Bill Gibson and the Arrow, after the winning flight at Chicago. Right—With Modelcraft perpetual trophy.

ESSENTIALLY the Arrow, like many planes, is not a completely original design. It is composed of the better elements of several planes which the designer has built and flown. Plans for the Arrow were first drawn in early December, 1939, and the original ship was finished late that month. As a matter of fact, the first test flight was made on a local golf course on the day before Christmas. The results of this flight indicated that we had all and more than we had expected on paper. The plane has a fast spiraling climb, and a slow soaring glide. The glide comes as a result of the ample wing area of approximately 392 square inches. The ship is quite strong and will stand the worst kind of contest flying. As an example, the original, built by Francis S. Beeler, has been flown all summer and is still in excellent condition, with its original covering still intact. Beeler has flown his ship in six contests, and according to their order, has taken the following places: two thirds, one second, one fourth, and two firsts. At the time of writing, the last contest he flew the plane in was at Chilicothe, Ohio, where the plane finally flew out of sight after a time of about six and one half minutes. His total time that day, for first place, was a little under eleven minutes. The plane was recovered three days later, having landed twenty-seven miles from the contest field, and was absolutely intact. All of these flights were in Class A, with an Ohlsson "19" for power. Beeler flew the plane once in Class B, using an Ohlsson "23" and took first place with a total time of about sixteen minutes.

William Gibson, who has really done more with the plane than Beeler, has built several models of the original and has flown them in both Class A and Class B events, using Ohlssons "19" and "23" for power. In Class A he has won three firsts, one second and three thirds. In Class B, Gibson has always placed well up in the money in all contests. His most notable achievement with the plane was his remarkable flight at the Chicago Nationals, where he won the Class A open event. For forty-seven minutes and thirty-two seconds the plane soared around in view of the timers and finally came to rest at a point about seven miles from the field. This flight not only won the Modelcraft Trophy for Gibson, but established a new record for Class A flights.

On Sunday, August 11th, Gibson released his plane for his first Class B flight. After six minutes, the plane passed from the sight of the timers and was not recovered.

Amply tried and tested, this plane is offered for your use with the suggestion that instructions be strictly followed.

CONSTRUCTION

First cut out all of the body formers for the bottom half of the fuselage from 1/8" sheet balsa. Glue a strip of $^1/_{16} \times {}^3/_{16}$" piece of hard balsa across the top of all open formers. Cut out the fire wall from $^3/_{16}$" three-ply white pine or birch. Pine is better because it is lighter. Notch all formers and the fire wall as shown on plan.





Left—With wing pylon in place. Center and right—The completed model, ready for first official. Its 392 sq. in. wing area affords exceptional glide. Climb is fast spiral.

BY WILLIAM GIBSON AND FRANCIS S BEELER

Attach the $^5/_{16}$" bass motor blocks by using flat-head wood screws that are countersunk into the fire wall. Before screwing the blocks on, place plenty of glue on the joint. It is also well to screw the screws in about three quarters of their length, then remove them, fill the holes with glue, and then tighten the screws. It is best to use one-inch screws that are fairly narrow. Put two or three coats of glue around the joint on the wall. Attach the landing gear wire to fire wall. Use $^5/_{64}$" or $^3/_{32}$" music wire for the landing gear. The lighter wire is preferred. Drill the motor mounts for your motor. The width of the mounts and the holes shown are for either an Ohlsson "19" or an Ohlsson "23" motor. Glue nuts on the bottoms of the holes. Use three or four coats of glue. The screws can then be removed at will. Although it is not necessary to draw up complete three-views of the fuselage, it will be necessary to draw a top view with correct former spacings.

Next, take the top view of the fuselage and crease the plan along the line which indicates the back of the fire wall. (Former 1.) Secure a flat board, about three feet long, and place the top view of the fuselage on this board so that the crease along Former 1 is *exactly* perpendicular to the center line drawn through the middle of the top view and also is against the squared-off end of the board. Cover the plan with wax paper and pin the $^3/_{16}$" square longerons to the board and in the position shown. We recommend that you soak the longerons in water before pinning them. Slip the fire wall, upside down, onto the longerons and tack the fire wall to the end of the board with two thin *(Turn to page 42)*




M-3
ALL 1/8" SHEET
M-2
M-1
5
1/32" SHEETING ENDS HERE
9
6
STABILIZER PLATFORM
3/32" MEDIUM BALSA
APPROXIMATE EYELET
POSITION TO HOLD KEY
DOWEL OF STABILIZER
M-4
10
M-5
3/16" SHEET
9-W
NOSE BLOCK
3/8" THICK
HARD BALSA
2T
1A1
COIL BOX
1/8" SHEET
1A3
3T
1A3
1A2
7
6" SHEET)
7T
3/16" SHEET
5T
1T
4T
4
FORMERS 2 TO 7 HAVE
1/16"X3/16" FOR
BRACING
HOLE FOR DOWEL
FIREWALL -
3/16" 3-PLY WHITE PINE
MOTOR MOUNT
BLOCKS ARE
5/16" BASS
BRASS OR
TIN CLAMPS
6T
8
3
COIL BOX
5AT
5A SHOWN IN
DOTTED OUTLINE
10T
2
9T
8T

1/8 HARD SHEET TO HOLD AUSTIN PEN LIGHT DURAL BATTERY BOX

DO NOT MOUNT TIMER UNTIL PLANE IS ENTIRELY COMPLETED. THEN USE TIMER TO BALANCE PLANE. APPROXIMATE TIMER POSITION SHOWN.

"N"
NOSE BLOCK
COIL BOX
"X"
3/16" SQ. SIDE LONGERONS

1/16" BIRCH DOWEL

FUSELAGE COVERED WITH 1/16" FAIRLY SOFT SHEET UP TO FORMER 4. 1/32" SHEET USED AFT OF THAT POINT. BEVEL BOTTOM LONGERON BEFORE COVERING FUSELAGE.

RUDDER OUTLINE CUT OUT OF 3/16" SHEET AND SANDED TO STREAMLINED CROSS SECTION AFTER ASSEMBLY.

1/16" X 3/16" RIBS - ONE ON EACH SIDE.

ALUMINUM TAB

1/2" SQ'S

M4 M-1 M M5 M-2 M-3 M6

1/16" BIRCH DOWEL

1/8" BIRCH DOWEL WELL GLUED

1/16" SHEET

3/16" SQ.

WING INCIDENCE - 1/8" STABILIZER INCIDENCE - 1/8" NEG.

NOTCH FOR RUBBER BANDS

1/8" X 3/16"

1/16" BIRCH DOWEL

R-1 R-2 R-3

STABILIZER MOUNT

"S"

1 2 3 4 5 6 7 8 9 10

"N"

3/16" SHEET

PORTION BETWEEN FORMERS 8 & 9 ABOVE SIDE LONGERONS NOT COVERED WITH 1/32" SHEET - COVER WITH PAPER OR SILK.

2-15/16" 5-7/16" 8" 10-7/16" 13-1/8" 16-3/32" 19-5/8" 22-1/4" 24-3/4" 27-1/4" 30-3/8"

LEADING EDGE - 1/4" X 1/2" MEDIUM HARD

LEADING EDGE TAPERS TO 1/4" SQ. AT TIP.

1/2" SQ'S

1/8" DOWEL KEY

A B C D E F G H I

2 1 2 3 4 5 6 7 8 9 10 11

TIP SPARS

W4 W-3 W-2 W-1

USE 2-1/4" TO 2-3/4" BALSA WHEELS

FRONT WING SPAR - 1/8" X 11/16" HARD BALSA

REAR WING SPAR - 1/8" X 9/16" HARD.

FRONT TIP SPAR TAPERS TO A 5/16 DEPTH AT TIP.

REAR TIP SPAR TAPERS TO A 1/4" DEPTH AT TIP.

SCRAP 1/32" SHEET

W2, W3, AND W4 ALL CUT FROM 3/16" SHEET.

NOTE HOW SPARS OVERLAP. GLUE ALL SPAR JOINTS SECURELY.

TRAILING EDGE-3/16" X 13/16"

2-1/16" 4-1/8" 6-3/16" 8-1/4" 10-5/16" 12-7/16" 14 1/2" 16-5/8" 18 5/8" 20-5/8" 22-7/8"

11" 9" 7-7/16" 5-7/8" 4-5/16" 2-3/4"

1/8" X 3/8" STABILIZER SPAR TAPERS TO 1/8" X 3/16" AT TIP.

1-3/16" 1/4" SQ. 1/8" DOWEL KEY

1/8" SHEET

1/16" X 3/16" STRIPS GLUED TO EACH SIDE OF NO. 1 RIB FLUSH WITH TOP CAMBER OF RIB.

RIB NO. 1

1 2 3 4 5 6 7

1/2" SQ'S

G

F

1-3/8" 3/4" 5-5/8" 1-1/4" 5-1/2" 1-1/4"

1/32" SHEET - BOTTOM ONLY SMALL KEYS CEMENTED IN THESE APPROXIMATE POSITIONS AFTER STABILIZER IS FINISHED.

FUSELAGE, WING, STABILIZER, AND LANDING GEAR ALL SHOWN ONE-QUARTER ACTUAL SIZE. ALL RIBS SHOWN ACTUAL SIZE.

A-B-C-D

E

H

NO. 1 STABILIZER RIB CUT FROM 3/16" SHEET.

DIHEDRAL NOTE:- 1" DIHEDRAL UNDER RIB NO. 6 AND 3" TIP DIHEDRAL.

1 AND 6 2 TO 5 2 TO 6 2 TO 6

ALL WING AND STABILIZER RIBS CUT FROM 1/16" SHEET. CENTER WING RIB IS CUT FROM 1/8" SHEET

GOODS' CHAMPIONSHIP RADIO MODEL

PART TWO



Reliable and workable, this equipment is the result of four years' experimentation. Has made over 150 good flights.

BY WALTER AND BILL GOOD



Walter tests responses. Large door provides access to receiver, visible through top of fuselage. Receiver mounted on sponge rubber.

HERE are the details of the radio equipment used in the Goods' Championship Radio Model which has proved its reliability by over 150 successful radio-controlled flights. Although the model has two controls, it is advised at the outset for the beginner to use one control, the rudder. This is because of the great versatility of the rudder control—and the increased complexity of additional controls.

The equipment is the result of over four years of experimentation—both in the laboratory and on the field—and hence represents a reliable, workable product.

Since not all modelers are endowed with a twin brother "radio bug" (Bill Good, W8IFD), hunt yourself an amateur operator before you start. He will have lots of good ideas, too. So you should easily be able to adapt this equipment to your own gas job.

The basic radio-control circuit is shown in Fig. 1. The signal from the transmitter is picked up by the receiver (in the plane) which sends current through the sensitive relay. This causes the relay (really a switch) to close the circuit which makes the control mechanism turn the rudder. A similar outfit operates the elevator. Thus, for two controls, this system requires two receivers, two sensitive relays, two control mechanisms and a two-frequency transmitter. The details follow.

The receiver is a one-tube superregenerative type built to work on five-meter wave length. Extremely high sensitivity, broad tuning, freedom from ignition interference and low cost make this type of receiver suitable.

The circuit of the receiver is shown in Fig. 2 and below it are listed the values of the various components for using either the RK42 (not RK62) tube or the Type 30. The actual arrangement of the receiver parts is pictured in Fig. 3. Duplicate the parts as closely as possible, especially the national quench coil.

The receiver base of hard 1/8" sheet balsa has a hole cut in it for the tube to be glued in place. For lightness the base of the





tube is removed (no, this won't bother the vacuum!) by soaking in hot water, unsoldering the wires at the prong tips, and gently working the base loose. Sometimes a coping saw will hasten this operation. The two center wires go to the filament, the outside wires to plate and grid. Glue the tube in place and also the quench coil and variable condenser. Note from the receiver photograph how the isolantite insulation has been chipped away to reduce weight. Careful use of a pair of pliers will do this.

Use as short wires as possible when wiring the receiver and make good soldered connections. Cement all parts in firmly so vibration cannot loosen them.

To obtain peak performance of the receiver a small amount of adjusting is required. If the construction has been carefully done and proper values used, this adjusting will be a minimum. The direct object in adjusting the receiver is to obtain the maximum possible plate current change through the relay and still retain good reliability.

First hook up the receiver with the relay and a 5 or 10 milliampere meter in series. The antenna should be sticking up so as not to interfere with the operator's hands. Now there are three things to adjust, the main tuning condenser (c_1), the antenna padding condenser (c_2) and the variable grid bias resistor (R_1). To begin, screw the padding condenser about halfway down and set the grid resistor at full resistance. Turn on the transmitter with low power (or put it upstairs with high power) and tune (using an insulated aligning tool) the main condenser until a dip is noticed in the plate current. The receiver is in tune at the bottom of this dip. Leave this main condenser at this setting.

Sending slow dashes on the transmitter key should cause the meter to change about 0.3 of a milliampere. Keep sending the dashes and at the same time slowly decrease the grid resistor. The total plate current will increase and the change in plate current will do likewise. There will be found a certain region in the setting of the grid resistor, for which the change in plate current is tremendous. This is the setting we're after. The change is about 2 milliamperes for the RK42 and may be as high as 3 milliamperes for the Type 30 tube. Further decrease in the grid resistor brings only a very small change in plate current, or the set becomes inoperative. A systematic repetition of the foregoing procedure, starting each time with the antenna padder slightly different (say one half turn) will find the optimum operating conditions for the receiver. The current change will be rapid (not sluggish) in response and the setting of the grid resistor will not be critical. For the RK42 the idling plate current (transmitter off) is about 5 milliamperes, while the plate current with transmitter on is about 3 milliamperes. The Type 30 will have about the same or slightly higher values.



Receiver rack (two controls), shows two receiver antennae, sensitive relays, grid bias adjuster, battery clips. Wgt. 14 oz.; 6" high.

A Good family: Guffie, Class A; Guff, Class C; and the radio job, a development of the same design. Has both elevator and rudder control.





Far left—Sensitive relay (DG-6) unassembled, showing left to right: Armature and bearing, coil and field piece, and the permanent magnet. Left—The assembled sensitive relay weighs 2½ oz.

Below—Key: A—Armature ($^1/_{64}$" iron transformer lamination); B—Fiber coil ends ($^1/_{64}$" thickness); C—Coil (approximately 2,300 ft. #40 enameled copper wire, resistance 2,500 ohms); D—Celluloid coil form ($^1/_{64}$" sheet); E—Armature bearing ($^1/_{64}$" sheet brass); G—Armature contact and contact spring (contact, coin silver), (contact spring, shim brass ½ x $^1/_{32}$ x .010"); H—Contact screw (2-56, brass machine screw tipped with coin silver contact); J—Stop screw (2-56, brass machine screw tipped with cement for insulation); M—Permanent magnet (Alnico magnet); P—(2-56, nuts). Sensitivity of relay, one milliwatt. Weight is 2½ ozs.

GOODS' CHAMPIONSHIP RADIO MODEL

PLANS BY PAUL PLECAN





If a pair of headphones is inserted in place of the relay it is possible to hear the characteristic "hiss" of the superregenerative receiver. When a signal is tuned in, the hiss disappears and the drop in plate current occurs.

As the B battery voltage decreases with age, a slight readjustment of the grid bias resistor will be necessary. If the voltage falls below 40 volts, the capacity of the antenna padder may have to be reduced slightly. Experience will dictate how low a filament voltage may be tolerated. A voltmeter is extremely convenient for keeping a check on the voltage of the batteries.

By extending the recently developed superregeneration theory, it is not difficult to explain the theoretical basis for the required adjustment. Having the receiver well adjusted, now turn to the relay (Fig. 4).

Experience with the DG-6 sensitive relay will make its unique and excellent behavior apparent to the builder. The snap action will be surprising at first, but that makes for better control while flying. Here's the quickest way to adjust it. Put the milliammeter in series with relay (as when tuning receiver). The meter will read about 5 milliamperes. Back off both Screws J and H (see Fig. 4), leaving plenty of movement for the armature (A). Lean the armature against Screw H. Run in Screw H until armature just flips away and comes to rest on the other screw. Now with transmitter on (receiver plate current at about 3 milliamperes) run in Screw J until the armature leaps away from it. This sets the limit of swing of the armature. To assure positive operation, turn each screw in about one eighth turn.

With transmitter on, the armature rests against Contact H. With transmitter off, the armature leans against Screw J. The relay will now respond to a rapid series of dots sent on a straight key or bug. Be careful you don't "while away" your evening just listening to the fascinating "click" of the relay.

The exact current at which the relay drops in and out may be determined by turning the grid resistor back and forth and noting the current when the relay clicks. In fact, it may be more convenient to adjust the relay to work half a milliampere "in" from either end of the operating range. That is, if the range is 3.0 to 5.0 milliamperes, then have the relay close at 3.5 and open at 4.5 milliamperes, thus giving both the receiver and the relay a little safety factor. A well-built DG-6 will work on a change of one half milliampere.



Rudder mechanism. Key: A—Escapement wheel ($1/64$" sheet brass); B—Armature rocker (bent from 0.010" shim steel); C—Magnet coils, each coil 80 ohms, wound with #40 enameled copper wire (core $9/16 \times 3/16$" diameter soft iron, back piece ½ x ¼ x $1/16$" soft iron); D—Armature $1/32$" soft iron; E—Wheel shaft $3/64$" piano wire); F—Frame $1/32$" sheet aluminum); G—Ball-bearing washer; H—Rocker adjustment screw, size 2-56; J—Spring adjustment screw, size 2-56; K—Rocker spring ($1/16$" wide watch spring); L—Rocker bearing ($1/64$" sheet brass, glued to end of coils).

The transmitter with control box on top. Due to theft of transmitter the night before the 1940 Nationals in Chicago, Bill Good had to build a new one from scratch in a single day. Was good enough to win!



Complete control mechanism resting on match box. Weighs ½ oz.



DG-6 SENSITIVE RELAY

The sensitive relay, called the DG-6, is one of the outstanding features of the receiving outfit. It has an unusual sensitivity of about one milliwatt, a high "drop-out percent" and a low weight of 2.5 ounces. A permanent magnet makes it a polarized relay. Its balanced construction and lack of springs causes it to be unaffected by vibration. (A very important point.) The contacts will easily carry 1.5 amperes. Inspection of Fig. 4 and the photographs reveals the essential parts. Study these carefully before construction is begun.

The coil form (D) is made from sheet celluloid bent around a $1/16 \times 5/8$" temporary core. The celluloid is overlapped and cemented and placed in a vise to dry. Cement on the fiber (or cardboard) coil ends (B) after being slotted. The coil (c) of some 12,000 turns is wound on this form. But that isn't as hard as it sounds. The No. 40 enameled copper wire may be obtained (places listed at end of article) on a fifteen-cent spool having just enough wire for relay and tail escapements. Wind the tail magnets and use the remainder of about 2,300 feet on the relay The resistance of the relay will then be about 2,500 ohms. Now we are ready for the winding.

Set up a hand drill (Pete Dillon used the family Mix-Master!) horizontally in the vise, with the coil form attached to the chuck. Also set up the wire spool parallel to the form and in front of it, making sure the spool spins freely. No. 40 wire is easy to break! Now crank the drill handle with one hand and guide the wire with the other hand. Even rows are not necessary or easy. Wind the coil firmly and as smoothly as possible. If the wire breaks, merely solder it, coat with clear dope (for insulation) and continue. It is wise to solder heavier wire leads to the fine wire. When finished winding, check the resistance and cover the coil with a strip of paper or empire cloth.

Cut out the armature (A) and solder to it the piano wire shaft. The contact (G) is a small piece of a dime. The contact spring (G) prevents the contact from sticking in operation, so it is very important. Solder the contact to one end of the spring and solder the other (lower) end of the spring to the armature.

Be sure to solder a connecting wire to (E), the brass armature bearing. The armature, when mounted in its bearing, should be capable of rotating freely back and forth through about 6 degrees.

The field pieces (F) are bent from soft iron. Solder on the two 2-56 nuts (P), noting one is mounted on a *(Turn to page 49)*

GOODS' CHAMPIONSHIP RADIO MODEL

GENERAL LAYOUT (FIGURE 1)

BASIC CIRCUIT (ONE CONTROL)



CIRCUIT DIAGRAM (TWO CONTROLS)



RUDDER CONTROL MECHANISM SEQUENCE (FIG. 6)

(AS SEEN FROM ABOVE)



RUDDER CONTROL MECHANISM (FIGURE 5)



TWO FREQUENCY R.C. TRANSMITTER (FIGURE 8)



C_1, C_2, C_3 — 100 $\mu\mu$fd. MIDGET MICA
C_3 — 35 $\mu\mu$fd MIDGET VARIABLE
C_4, C_5, C_6, C_7, C_8 — 0.002 μfd. MIDGET MICA
C_M — 15 $\mu\mu$fd MIDGET VARIABLE
R_1 — 0.1 MEGOHM, .5 WATT
R_2 — 50,000 OHMS, 2 WATT
R_3 — 150,000 OHMS, 1 WATT
R_4 — 25,000 OHMS, 1 WATT
R_5 — 25,000 OHMS, 10 WATTS
C — 45 VOLT MIDGET "B" BATTERY
M_1 — 100 MA. M_2 — 5.0 MA.

L_1 — 9 TURNS OF NUMBER 14, TAPPED ONE TURN FROM GROUND
L_2 — 8 TURNS OF NUMBER 14.
L_3 — 6 " " " 12.
L_4 — 3 " " " 12.

$\frac{3}{4}$" DIAMETER FORM USED FOR ALL COILS MENTIONED ABOVE. WINDINGS SPACED DIAMETER OF WIRE USED. L_2 IS TUNED BY SQUEEZING OR PULLING OUT THE WINDING.

DESIGNED AND BUILT BY BILL GOOD, W8IFD.

CIRCUIT OF RADIO CONTROL RECEIVER (FIGURE 2)



TUBE —	TYPE RK42	TYPE 30
C_1 —	15 $\mu\mu$fd. NATIONAL ULTRA-MIDGET UM-15	C_1 — SAME
C_2 —	ANTENNAE PADDING CONDENSER 3-35 $\mu\mu$fd. (SMALL SIZE)	C_2 — SAME
C_3 —	0.00025 μfd. MIDGET FIXED CONDENSER	C_3 — 0.00015 OR .0002
C_4 —	0.002 μfd. MIDGET FIXED	C_4 — .002 TO .005 μfd USE VALUE THAT GIVES BEST RESULTS.
C_5 —	0.005 μfd. MIDGET FIXED	C_5 — SAME
R_1 —	10,000 OHM VARIABLE RESISTOR	R_1 — 25,000 OHM VARIABLE RESISTOR
R_2 —	2,500 OHM SENSITIVE RELAY - DG6	R_2 — SAME
L_1, L_2, —	FIVE TURNS OF #14 WIRE, $\frac{3}{8}$" DIAMETER SPACED TO OCCUPY A LENGTH OF $\frac{7}{16}$"	L_1, L_2, — SAME
RFC —	WIND #32 D.S.C. WIRE ON $\frac{3}{16}$" DIAMETER FORM TO A LENGTH OF $\frac{3}{4}$". FORM IS MADE OF CEMENTED PAPER TUBE.	RFC — SAME
Q —	NATIONAL QUENCH COIL. (LOW FREQUENCY OSCILLATOR COIL - NATIONAL OSR)	Q — SAME
A —	1.5 VOLT CELL, ONE REGULAR FLASHLIGHT CELL	A — 3 VOLT BATTERY, TWO PENLITE CELLS
B —	45 VOLT BATTERY. BURGESS W30FL	B — SAME

RACK FOR RECEIVERS (TWO CONTROLS) (FIGURE 7)



FAIRCHILD PT-19 ARMY TRAINER

A real PT-19, breezing along at its 125 m. p. h. cruising speed, is the last word in primary trainers. Left—Completed model and, below, construction, ready-to-fly, and flight!

BY EARL STAHL



A "natural," either in the air or on the ground, your PT-19 model will be a standout.

DESIGNED to meet the rigid requirements for training planes of the United States army air corps, the Fairchild PT-19 is of a design similar to the majority of combat planes, yet it possesses the flight and strength characteristics required of training aircraft.

This two-place, low-wing monoplane is powered by a Ranger engine of 175 h.p. which gives a speed of 135 m.p.h. Construction is conventional, wood, metal and fabric being used; the cantilever wing is plywood covered. A high degree of visibility, an important factor in all training planes, is achieved by the use of the inverted, in-line engine and the open cockpits.

From the modeler's point of view the PT-19 affords a fine subject for a flying scale model. The test model was built to exact scale except for a slight modification of the stabilizer area and, of course, the enlarged propeller; it is capable of making flights of about one minute. Because of the plane's simple, efficient design, it is not difficult to construct an authentic, sturdy model from the full-size plans which are presented here.

CONSTRUCTION

The fuselage under-frame is constructed first. Work directly over the plan and make two side frames. The longerons are $^3/_{32}$" square, while the uprights are $^1/_{16}$ x $^3/_{32}$" balsa. When dry, the side frames are inverted over the top view of the fuselage and the cross pieces are cemented in place. Check frequently to assure proper alignment.

Formers are cut from soft grade $^1/_{16}$" sheet balsa. It will be noticed that a number of the formers do not have notches for the stringers; where this is true, the stringers are to be attached directly to the sides, as shown. Cement the formers to their respective positions and then add the $^1/_{16}$" square stringers. On the bottom of the fuselage between Sections 3-B and 6-B the stringers are omitted, since the wing is later placed in the re- *(Turn to page 46)*

FAIRCHILD PT-19 ARMY TRAINER





NOSE PLUG

THE NOSE IS "FILLED-IN" WITH 1/16" SHEET; SECTION FROM 3 TO 6T COVERED WITH 1/32" SHEET

CRASH PROTECTOR

1/2 WINDSHIELD PATTERN



NOSE BLOCK

PROP BLANK
7/8" X 1 3/8" X 7 1/2"
HARD BALSA



SECTION FROM 3B TO 6B FINISHED ONCE WING IS FITTED



FAIRCHILD PT-19
by
EARL STAHL

COCKPIT SHAPE



FORMERS CUT FROM 1/16" SHEET




BAMBOO PIN
8B
OUTLINES CUT FROM 1/16" SHEET
7B
6T
7T
8T
9T
6B
FORMERS 1/16" SHEET
STABILIZER POSITION
STRINGERS 1/16"X1/16"
7T
8T
9T
NOT COVERED
3/32"X 3/32" LONGERONS
1/16"X 3/32" CROSS MEMBERS
8B
7B
WING ROOT PIECE W-R
W5
W4 1/16 SHEET
W6
W3
W7
W2
W1
W8
RIBS CUT FROM 1/32" SHEET 2 OF EACH REQ'D
1/64" THICK FILLETS 2 REQ'D
1/8"X 3/8"
W7
W6
W5
W4
W3
W2
W1
1/16"X 1/16"
THE LANDING GEAR STRUTS ARE ATTACHED BY THREAD & CEMENT
3/32"X 3/32"
1/16"X 1/4"

LANZO NATIONALS STICK WINNER

BY CHESTER LANZO

A 300 square inch wing and timer rudder control enable this 4½-foot job to stick in any thermal. Best flight is 63 minutes!

Lanzo holds "bomber," Korda winding. Both are from Cleveland.

MOST of the present-day rubber models have a wing area of approximately 200 square inches and weigh almost 8 ounces. This makes the average model 2 ounces overweight. When figured in percentage it gives one something to think about, and, with this thought in mind, I designed this stick model, which won the 1940 Open Stick Contest in Chicago.

I knew a large 300-square-inch model would not weigh much more than the former 200-square-inch job, yet it would have a larger wing area and a lighter wing loading. This would produce a ship with improved flight characteristics. The original model weighed 9¼ ounces.

On its first test hop this ship did 7 minutes and on its first official flew 14 minutes without gaining more than 300 feet altitude. Other contest flights by this ship went for 15, 10, 63, and 30 minutes. It is stable, consistent, and sensitive to the slightest risers.

Second consideration was to produce a model of simple design and construction.

CONSTRUCTION

The fuselage being of rectangular cross section, the usual procedure of building the two flat sides first, and then placing in the



ALL UPRIGHTS BETWEEN STATIONS 2. AND 20 ARE SPACED 1-3/4" APART.

ALL LONGERONS AND UPRIGHTS ARE 5/32" SQ.

ALL DIMENSIONS BELOW FUSELAGE REFER TO DISTANCE BETWEEN LOWER EDGE OF LOWER LONGERON AND CENTERLINE.



1" DIHEDRAL UNDER RIB "D". 5-1/4" UNDER WING TIP.

1/16" STOCK USED FOR ALL WING RIBS.

1/32" OR 1/20" STOCK USED FOR STABILIZER RIBS.

ALL SPARS ARE 1/16" X 1/8"

WING AND STABILIZER LEADING EDGES BOTH 1/8" SQUARE.



ALL STABILIZER SPARS ARE 1/16" SQUARE.



WING MOUNT SHOWN HALF ACTUAL SIZE



CUT-OUT POINTS MAY BE REMOVED FROM TIMER.

SILK THREAD TO PIN IN TUBE ON RUDDER

POSITION OF TAB WITH TIMER HANDLE PULLED BACK.

POSITION OF TAB WITH TIMER HANDLE IN FORWARD POSITION (IN FLIGHT, DURING GLIDE)

CROSS-SECTION OF RUDDER AND TAB

RUBBER BAND PULLS TAB OVER TO ONE SIDE AFTER PIN HAS BEEN PULLED FORWARD BY TIMER.



AFTER PROP IS CARVED, IT IS CUT IN TWO AT THE CENTER AND THE 3/8" X 3/4" X 1-9/16" CENTER PIECE IS ADDED TO FORM A HUB.

FUSELAGE, PROPELLER, WING AND STABILIZER SHOWN ONE-QUARTER ACTUAL SIZE. TIMER DETAIL IS HALF ACTUAL SIZE.

PLANS BY PAUL PLECAN

top and bottom cross pieces, was used. Details of the construction are included in the drawings. Before covering the fuselage round off the longerons and sand the outer framework, taking care that no bits of glue remain within the body, for, if they do, they will surely cut the rubber.

The flight timer is optional and may be discarded if the builder wishes. Note that the usual rear hook has been dispensed with. A $^{3}/_{16}$" dowel is slipped in place through the sides of the fuselage, and, in addition, small aluminum plates are cemented to the inside surfaces of the sheet-balsa fill-in. Upon finishing the nose block be sure to put in the proper amount of downthrust and sidethrust; otherwise the propeller blades will not fold properly against the sides of the fuselage. Paint a small red mark on top of both the nose block and the fuselage, so that the nose plug may be slipped quickly in place after winding.

When carving the prop try to leave as much blade area as possible. This will give maximum climb. When making the hinge fittings be sure that they are loose, so they will not bind after the tensioner catches. This might cause the plane to spiral in. The $^{1}/_{16}$" holes in the prop and nose fittings should be a loose fit, so that the spring will pull the catch against the stop without binding. If the left-hand blade will not fold properly against the fuselage, a small rubber band will pull it up. Make two small hooks from .016 music wire and glue one at the trailing edge of the blade one inch from the hub. Glue the other one on the hub just one quarter inch from its center. To bend the prop shaft start at the bobbin hook. This hook should be square with the sides clamping the bobbin to prevent its turning and twisting, or "climbing" the hook.

The bobbin has proved itself beneficial in preventing cuts in the rubber and rattling or wrapping around the hook.

The wing is of a high lift section and utilizes the multispar type of construction. Cut out the necessary ribs and assemble in the usual manner. Be sure to prop up the trailing edge with $^{1}/_{16}$" balsa before cementing the ribs to it. If desired, the wing may be built in four panels. However, this necessitates getting the end ribs on each panel at the proper slant to allow for dihedral. I have found bamboo tips the easiest to make. They absorb shock better than balsa.

The elevator is quite large. It is built in the same manner as the wing. The $^{1}/_{8}$" square leading edge must be bent over steam and then baked in an oven for a few minutes to make it rigid.

The rudder is of a streamlined section and contains only one main spar. When gluing the rudder on the *(Turn to page 58)*

LANZO NATIONALS STICK WINNER

RIB R-1 IS CUT FROM 1/8" SHEET.
ALL OTHERS CUT FROM
1/32" SHEET.

R-1 R-2 R-3 R-4 R-5

FULL SIZE WING RIB

19 WING RIBS OF LARGEST SIZE REQUIRED - 2 EACH OF TIP RIBS

11 LARGE STABILIZER RIBS REQ'D. 2 TIP RIBS REQ'D.

STABILIZER RIB

2 INTERMEDIATE RIBS REQUIRED.

1/8" SHEET RUDDER OUTLINE

R-5

1/8" SQ. SPAR

R-4

R-3

A

B

D

FULL SIZE PROP TEMPLATE - USE ONE CUT FROM CARDBOARD TO OBTAIN AN IDENTICAL OUTLINE OF BOTH BLADES

1/8" SQ. LEADING EDGE IS STEAMED TO CURVE SHOWN.

RUDDER SHOWN FULL SIZE

R-2

1/8" SHEET GUSSETS

TISSUE PAPER OR SILK HINGE

R-1

"U" SHAPED WIRE FITTING

SOLDER

1/8" HARD BALSA

RUDDER TAB (1/32" SHEET)

1/16" X 1/8"

C

A

B

D

E

1/8" SHEET

MUSIC WIRE PIN

TUBING

RUBBER BAND

BOBBIN

5 OR 6 1/4" WASHERS

3/16" DOWEL IN NOSE-PLUG FOR REINFORCING WOOD SCREW

A REAL GASOLINE ENGINE $4.95



Everything is in the kit including Champion spark plug, coil, condenser, tank and cap, ignition wire, cylinder, piston, connecting rod, timer, crankshaft, all screws, nuts, bolts, simple illustrated instructions, etc. Every part is fully machined and finished. A SCREWDRIVER IS THE ONLY TOOL YOU NEED.

EXACTLY THE SAME PARTS THAT GO INTO THE G.H.Q. ASSEMBLED ENGINE.

New Features:

Light weight 3-volt spark coil; chrome-steel, drop-forged one-piece counter-balanced 5/16" crankshaft; 1¼" Bronze Bearing; Uniflow steel piston giving extra high compression; Champion Spark Plug.

EVERY PART FINISHED



SPECIFICATIONS

4 Port 2 Stroke Cycle—¼" Stroke—15/16" Bore—300-7,000 R.P.M.—Bearing Surface, 1¼" Long—Crankshaft, 5/16" Diam.—Invertible—Rotation, Either Direction—Height, 4½"—Width, 2½"—H.P. Approx. 1/5th.

Displacement, .517 cubic inches
Class "C" under N.A.A. Rules

Over 35,000 G.H.Q. Engines in Use Today Is Your Guarantee of a Good Investment!!

DEALERS! Write For New Discount Schedule

Here is your opportunity to buy a kit of the famous G.H.Q. Gasoline Motor. ABSOLUTELY COMPLETE—ALL MACHINING DONE—READY TO ASSEMBLE. All you need is a screwdriver. No mechanical knowledge required.

$4.95 COMPLETE

A large bore 1/5 H.P. engine at a lower price than any small bore engine.

AN ENGINEERING TRIUMPH . . .

Never Before at So Low a Price!!

Indeed an engineering triumph—accomplished by outstanding G.H.Q. designers and engineers, who have constructed into the G.H.Q. motor everything that years of exhaustive scientific aerodynamic research could produce—geared to the highest possible degree of perfection. But more than that, the acid test . . . an overwhelming response. Thousands of users in all parts of the country are praising, recommending, and endorsing this scientific achievement. It seems as if everyone in America wants one. The most hair-raising thrill you've ever experienced will be yours with the G.H.Q. motor—actually one of the most powerful motors ever constructed. Has broken records for amazing performance.

30 MINUTES TO ASSEMBLE • ALL PARTS WARRANTED

Imagine operating your own G.H.Q. 1/5 Horse Power gasoline engine—small enough to fit in the palm of your hand—yet turning up over 7000 revolutions per minute and powerful enough to fly model airplanes of from 4 to 10 foot wingspan, and propel model boats from one to six feet in length and midget cars that travel over fifty miles an hour!! There are also hundreds of other ways you can enjoy using this miniature yet powerful power plant—for small pumps, generators, compressors, blowers, fans, grinders and countless other experimental purposes.

Your G.H.Q. gasoline engine will be far more than just a toy for your spare moments. It is a scientifically constructed mechanical marvel that will thrill you with thousands of hours of pleasure. You will get a real kick out of controlling with your finger tip the surge of power your engine develops.

This engine has been tested and proven over the last seven years. Over thirty-five thousand of these powerful little G.H.Q. engines are now in actual daily use. Why not join the ranks of these hobbyists?

AT LOWEST PRICE IN HISTORY!!

The G.H.Q. Gas Engine sold five years ago for $35. Over 7000 have been sold at $8.50. Today you can secure a vastly improved engine kit for only $4.95. How is this possible? Simply because we have invested thousands of dollars in tools, jigs, dies and equipment to produce the only mass-production motor in the market. All parts are uniformly perfect.

ENGINE IS COMPLETE AND READY TO ASSEMBLE!

Your engine comes to you with every part completely finished. Our factory-trained skilled mechanics, using the latest automatic precision machinery, have finished each and every part to the last detail. You merely assemble the parts in accordance with the few simple instructions given, using only an ordinary screw driver, and inside of thirty minutes, your engine is ready to operate.

Not only will you and your friends have the thrill of seeing an engine ASSEMBLED BY YOURSELF operating, but you will gain a knowledge of gasoline engine theory and practice that will be a real practical value to you.

This identical G.H.Q. Gasoline Engine Kit is also available in factory assembled, fully bench tested and ready-to-run form.

This comes to you already tuned up . . . ready to mount and run.

G. H. Q. "Ready-to-run" Engine $6.50

SEND FOR FREE Literature or 6c For Jumbo Catalog.

HOW TO ORDER:

SEND ONLY $1.00

We ship Express
Collect C.O.D. for balance

For shipments outside the U. S. send full amount plus $1.00 for packing, postage and insurance.

ORDER FROM

G. H. Q. MOTORS, Inc.

MANUFACTURERS OF

Miniature Gasoline Engines and Hobby Supplies

40 EAST 21st STREET Dept. T NEW YORK, N. Y.

ORDER TODAY-24 HOUR SERVICE

G. H. Q'S. SEVENTH Year!!

Thousands of Satisfied Users! Read some of these testimonials on file with us:

J. B., Providence, R. I.—"A few weeks ago I received the G.H.Q. motor kit and it is running perfectly. I hope to write you soon and tell you about some excellent flights."

R. H., Prairie du Chien, Wis.—"Your motors sure can take a lot of abuse and knocking around and yet perform perfectly. I have had two in a period of about two years and have seen higher priced motors give less service and performance."

W. W. W., Russellville, Ark.—"I received my G.H.Q. Motor Kit and am very well pleased. I had motor together in 1 hr. 40 min. I will place order next week for G.H.Q. Sportster Kit."

W. L., Claysburg, Penn.—"A wonderful motor that thrills any air-minded person. Strong and neat looking. As good as motors costing twice as much."

A. K., Hillside, N. J.—"I still can't understand how you can put such a dependable and rugged engine on the market at such a low price."

E. T., Sayville, N. Y.—"Received my G.H.Q. Kit okay and am more than delighted with same. You've got 'em all beat for price and performance."

R. P., Hamburg, N. Y.—"I want to extend my personal thanks to G.H.Q. for their prompt service. The motor I ordered was received within 24 hours. Such service cannot be surpassed. I also want to say that I have the motor running perfectly. I promote the success of G.H.Q."

H. H., Midlothian, Ill.—"Motor assembled correctly and performs perfectly. I am fully satisfied."

W. H., Birmingham, Ala.—"I have assembled one of your motor kits. It runs fine both with flywheel and propeller."

D. D., Canton, Ohio—"Four fellows in my neighborhood have an engine like yours and they are well pleased. Please send me your $5.00 gas engine kit."

N. T., Sparks, Nevada—"I have one of your motors and it has given good service for nearly five years."

M. M., Richmond, Va.—"I received my gas engine Christmas and am fully pleased with it."

F. S., New Haven, Conn.—"I was very much surprised with the motor. It exceeded my expectations so far as construction is concerned and will compare favorably with motors three times the price."

L. N., So. Euclid, Ohio—"Received my finished motor. I am very pleased with it and runs fine. I will be glad to encourage others to get G.H.Q. motors."

C. C., Chicago, Ill.—"I received my motor and I am quite satisfied and surprised at the precision parts for the money."

J. G. G., Ocean Laus, B. C., Canada—"It sure is a little dandy and runs like a clock."

C. O. S., Garden City, N. Y.—"I saw your advertisement in the magazine Mechanics and Handicraft for the G.H.Q. Model Gas Engine. I have seen several in operation and I am very much pleased with their performance. Enclosed please find a money order for which, send me a G.H.Q. Kit, complete with a flywheel."

D. E. P., Chamberlavry, S. Dak.—"Am well pleased with my motor. I have purchased a model plane for it."

1940 Sales Of G. H. Q. Engine Kits 15,000

Scientists Say:

"ELLIPTICAL DIHEDRAL"



THE TOPPER

A scientist reveals the secret of the Topper's amazing performance—Elliptical Dihedral. The only perfect dihedral in use today and exclusive with the Bay Ridge Topper. Either in Class A or B this ship proves tops. Has a remarkable record of contest achievements that is being added to daily. Pre-fabricated kit, sells itself on sight against any other similar class model. Wing outline ready cut, all formers cut, firewall formed, landing gear ready shaped. Silk for body, Silkspun for wings, M.&M. Airwheels . . . a real deluxe kit at this remarkable price.

$4.95 POSTPAID

A RECORD MAKER Since INTRODUCED

The DIAMOND DEMON set a new Class B record in its first gas model meet, and has performed sensationally in every meet since that time. For sheer performance, plus ruggedness and ease of construction, this outstanding ship is tops! Complete kit, which includes air wheels, precision full-size plans, printed sheets, covering materials, cements and dopes, comes to you for only $2.95 post paid.

A 1st Prize Winner at $1.49!



BAY RIDGE MIKE

FLASH First in Class A at South Jersey Fall gas meet, a first at Sky-scraper meet, and many other top performances throughout the country. The Bay Ridge Mike is a sensation under the new rules. Build one and see!

Again a ship that can fly in Class A or B. Four-foot wing span, and ideal for 1940 Bantam, Ohlsson 19 or 23 or similar motors. Complete kit, less wheels. $1.49 PP. Deluxe kit, with airwheels, silk for body, plenty of extras, only $3.50 PP.

$1.49 PP.

RELIABLE, SENSATIONAL AND THOROUGHLY PROVEN — THERMAL MAGNET

A six-footer of outstanding performance and rare beauty. In kit form, less air wheels, for $4.95 PP. Kit contains all printed sheets, super-clear Ray Helt drawings, bamboo paper, dopes, cement, all wood and fittings. DeLuxe kit with covering silk, Trexler air wheels, finished prop, and color dopes, a real bargain at $7.50 PP.

BAY RIDGE MODEL AIRPLANE & SUPPLY CO.

4419 3rd AVE. DEPT. A18 BROOKLYN, N. Y.

The Arrow

(Continued from page 26)

brads in order to hold it in position. Use a T square and be sure that the fire wall is mounted absolutely straight up and down and straight across. Cut the ends of the longerons and fit them to the motor blocks as shown. Before gluing them, glue a piece of $^3/_{16}$" scrap sheet, cut to shape, in the space between the longeron and the motor blocks. Then glue to longerons, to these pieces, and to the motor blocks. Glue pieces of ½" square balsa along the motor blocks, below the longeron (as shown on plan) and cut and sand to shape. Cut the nose block, making an opening to fit your motor, and glue to end of motor blocks.

Glue all formers to longerons as shown on plan. Then glue the bottom longeron of $^3/_{16}$" square balsa along the bottom of each former. Glue Former N from fire wall to nose block. Glue R1 in place. Formers 1A1-1A2 and 1A3 are not glued in until later.

Remove pins that hold one side of longerons and glue a piece of $^1/_{16}$" soft sheet balsa, four inches wide, to the side of the body. This piece runs from the *center* of the fire wall to the center of Former 4. Glue a piece of the same sheet from the center of the fire wall to the nose block. Then glue a piece of $^1/_{32}$" sheet, 4" wide, from the center of Former 4 to the center of Former 8. Do not glue $^1/_{32}$" sheet on the bottom rudder until you have covered the other side of the fuselage as last described. Trim off the [illegible] covering along the edge of the bottom longeron. Then remove the pins from the other longeron, and cover the other side of the fuselage as you covered the first side. Trim off excess balsa from the edge of the bottom or keel longeron. Cover the body from Former 8 to the front edge of S2 with one piece of $^1/_{32}$" sheet balsa. This piece covers R1 and forms part of the bottom rudder. As quickly as you can, cover the opposite side of the fuselage in the same manner, making sure that the rudder lines up properly. All sheets can be held with pins until the glue has dried. The writer neglected to mention that all sheet should run *only* to the center of the longerons along the middle of the body. This will leave a lap for gluing the top sheeting.

As soon as the glue has set well, remove the fuselage from the board by first pulling the brads holding the fire wall. Check the fuselage and be sure it is in perfect alignment. If it is not, soak it in hot water, place it on a flat surface, weight it down and allow it to dry at least twelve hours.

Next build the entire wing-mount section as indicated on the plan and fit it carefully to the fuselage. Be sure that the peg which goes through the fire wall fits tightly and does not allow the wing mount to move in front. Cover the vertical part of the wing mount with $^1/_{32}$" sheet. Then cover the rounded part of the mount with soft $^1/_{16}$" sheet.

Glue Formers 5AT and 5T in place and be sure that Former 5AT fits flat against Former 5A on the wing mount. Glue the rest of the body formers in place. Glue Former S in place and follow this by gluing Former S1 in place. Glue tail-mount pegs in place, using plenty of glue to hold them. Cover top of body, one half at a time, with $^1/_{32}$" soft sheet from Former 5AT to Former 8T. Also cover with $^1/_{32}$" sheet from Former 9T to S2. This sheet runs from middle of side longerons to top of Former S. Glue tail-mount platform in place.

Glue $^1/_{16}$" round birch dowel in place along Former 4 as indicated, for holding wing-platform rubber bands. This dowel runs through entire fuselage. Glue 1A1, 1A2, and 1A3 in place. Build coil box and glue in place. Glue in strip of ⅛" hard sheet after having attached battery box to it. Wire motor according to standard hook-up, but leave unattached wire for wiring to flight timer. The timer is used for balancing and does not go in until entire plane is finished, including covering and doping. Booster points are not indicated on the plan, this being left to the modeler's own choice and judgment.

Cover the fuselage and wing mount with silk, wet and shrink. Give the same no more than two coats of colored dope. Be sure to coat the motor blocks, fire wall and inside of the nose with two or three coats of dope.

The sheet $^1/_{16}$" balsa, covering the top part of the nose, is attached last and should be cut out to fit your motor. Cover this with silk and dope inside and out with two coats of colored dope.

In making the wing, cut out W1, W2, W3, and W4 from $^3/_{16}$" medium-hard sheet balsa. Glue W2 and W3 together. Place wing plan on a flat surface, cover with wax paper and pin W1, W2, and W3 in place. Place a piece of $^1/_{32}$" scrap balsa under trailing edge of wing at each notch in trailing edge. Do not extend the $^1/_{32}$" scrap back more than ⅛" under the trailing edge. This scrap piece is used to maintain the undercamber of the airfoil. Next soak the leading edges in hot water and pin in place on the plan. Bevel the edge of W4, where it joins the leading edge and W3, in order to secure a good fit, and glue it in place. Glue Ribs 7, 8, 9, 10 and 11 to the leading and trailing edges. When glue is dry, slip spars in place and glue well. Glue Ribs 2, 3, 4 and 5 in place. Slip spars in place and glue well. Be sure all spars do not extend below the bottom of the ribs as this would spoil the contour of the airflow. Remove pins that hold the tip end of the wing to the working surface and lift it off the plan. File or sand the leading and trailing edges and tip of this section, to proper airfoil shape as indicated by the plan. With the aid of blocks, place the tip section in place with the tip itself raised 3" from the working surface. Cut the ends of the spars, where they are glued to the center-section spars, so that Rib 6 will fit flush against the ends of the tip spars and will also be perpendicular to the working surface. Also level the leading and trailing-edge joints to secure a good fit. Glue the tip section to the center section,

SILKSPAN

IMPORTANT! "Silkspan" covering tissue is insoluble in water. Can be applied wet or dry, like silk. Made in U. S. A.

DEMAND SILKSPAN!

ALDINE PAPER CO.
373 4th AVE. NEW YORK

Capitol's

NEW DELUXE SERIES

48 to 50 IN. WINGSPAN MODELS

ALSO
- TAYLORCRAFT for 1940
- STINSON GULLWING SR-10
- MONOCOUPE 90-A

FEATURING
- Complete Materials
- Aluminum Cowls
- Cut-out Wheelpants
- Aluminum Spinners
- "Silkspan" Covering
- Master Plans

$1.00 BY MAIL ADD 15c

EXCLUSIVE DISTRIBUTORS FOR EASTERN PENNSYLVANIA

M. B. SPOTTS
3141 N. BROAD ST.
PHILADELPHIA, PA.

DISTRIBUTORS FOR THE ENTIRE CAPITOL LINE
DEALERS: WRITE FOR SCHEDULES

using plenty of glue, and allow to dry well before removing from plan. After the wing half has dried and been removed from the plan, glue the bracing strip in place behind the joint of the center and tip sections, where the leading edges join. Glue Rib 6 in place. Sand or file the leading edge and trailing edge of the center section to proper shape. Glue False Ribs D and E in place. Place wing on a flat surface and check for warp. If there is any warp, soak the wing in hot water, place on flat surface and hold down with weights. Allow twelve hours for drying. This will remove any warp.

Build the other half of the wing in exactly the same fashion as above outlined. When the two halves are completed, they can be joined in the center. In this place, the spars are overlapped by pushing the two spars on one half of the wing inside of the two spars on the other half of the wing. Try this first one way and then the other in order to determine which combination brings the leading and trailing-edge joints together for the best fit. Bevel the spar tips and leading and trailing-edge tips to secure a perfect fit. Pin one side of the wing to a flat working surface, place the other half in position and use blocks to raise the other half of the wing two inches above the working surface at the point where the polyhedral begins. Be *positive* that at this point both the leading and trailing edges are exactly two inches above the working surface. This will insure a level wing without warp. Glue the wing well at the center and allow several hours for drying. Remove wing from working surface and glue in braces along leading and trailing edges where they join in the center. Sand all joints to proper shape. Glue Rib 1 in place. With fine sandpaper, *carefully* sand the top and bottom edges of Ribs 2 and Rib 1 down about $1/32$". Glue pieces of $1/32$" sheet balsa across center section between Ribs 2. This sheeting should be glued to the bottom first. It runs, with the grain crosswise to the ribs, from Rib 1 to Rib 2 on each half. Glue in the piece of birch dowel which is used as a key. This piece extends out of the bottom of the wing about $1/8$". Then cover the top of the center section with $1/32$" sheet balsa. Sand this covering until it is smooth.

We recommend covering the wing with Silkspan as it is light and strong. Cover the bottom of the wing first and be sure that the paper is glued to each rib in order to maintain the undercamber of the airfoil. The grain of the paper should run from tip to tip. Dampen the paper, one half at a time, and place on flat surface with weights until dry. Then do the same for the other half. Dope each half, one side at a time, and weight on flat surface while drying. Do not give the wings more than two coats of dope. This method of weighting the wings, while it takes longer, will insure a flat wing when you are finished. When the bottom half of the wing is covered and doped, then cover and dope the top half in the same manner, except that you do not have to glue the papers to each rib. The finished wing should not weigh over four ounces.

(Turn to page 45)

GUILLOW

presents 6 NEW

MODERN MILITARY PLANES

FIGHTERS -- INTERCEPTORS -- PURSUITS

Models that are making headlines. Swift British fighters, newest American aircraft. Each one an amazing replica of its "big brother."

Flying Model Construction Sets

24-inch wingspread

25c

Flight tested. Easy to fly. Sturdy construction. Complete kits including cement and colored insignia.

At dealers. Mailing charge 10c.

SUPERMARINE "SPITFIRE" GRUMMAN F4F-3

BELL PURSUIT P-39 BREWSTER FIGHTER

IMPORTANT: Watch the next issue for the announcement of 3 NEW 50c "in-the-news" flying models. Exceptional values!

Also available:—a complete line of ready-to-fly gliders retailing at 1c to 10c—shelf model construction kits at 2 for 1c to 25c—flying model construction kits from 5c to $1.50

PAUL K. GUILLOW

WAKEFIELD - - - MASSACHUSETTS

CHRISTMAS AVIATION GIFTS FROM KARL ORT OF YORK

ALL PRICES POSTPAID to any part of U. S.

• KARL ORT IS HEADQUARTERS FOR AVIATION SUPPLIES •

AERO MUFFLER—Beautiful white rayon. Size 19 x 51 in. Imprinted with handsome aviation design. No. P1515 **1.50**

PARACHUTE SILK Muffler, with De Luxe non-fading, embroidered, flyer's insignia. Large size, 6 feet long, 18 in. wide. No. P1510 **2.95**

AVIATION PINS

Real Beauties—Shown Actual Size

P501	P602	P504	P502	P503
Lapel Pin	Red & Gold	10K Gold	Screw Back	Lapel Pin
.98	.49	.95	.47	.58

AVIATORS' BILLFOLDS

P1601—Combination Bill Fold and License Case. Genuine CALFSKIN. Holds C. A. A. licenses trimmed and folded. 4 windows. Zipper closed **3.49**

P1611—Same size and construction as above, except made of MOROCCO leather **2.50**

PATHFINDER COMPASS

Excellent gift for airplane, boat or car owner. Built-in compensator. Electric lighted. Suction cup mounting. P2382 **7.50**

BEAUTIFUL AVIATION RINGS—*Low Priced!*

No. P308—Boys' and ladies' ring of STERLING SILVER with beautiful, modernistic aviation design. State size. **.99**

No. P302 — Large, Massive, "HEMAN'S" STERLING SILVER ring. Elaborate aviation design, with eagles on sides. State size. **1.95**

No. P321—For men or women. STERLING SILVER, with genuine DIAMOND in center of winged, radial engine design. State size. **2.96**

No. P311 — Unusual aviator's ring, STERLING SILVER, with aviation emblem on jet black mounting. Distinctive. State size. **5.00**

AVIATION GOGGLES

No. P207—Shatterproof, non-fogging, with large rubber face mask. Gives comfort and wide vision. Very popular aviator's goggle..... **3.85**

No. P206—"Seesall" (not shown) famous for its large curved lenses and wide vision. The "air-conditioned" popular training goggle..... **7.85**

AVIATION LOG BOOKS

No. P1464—Imitation Morocco grain imprinted with gold airplane design. Handy pocket size. Conforms to C. A. R. ..... **.78**

No. P1468—Finest quality brown Morocco leather, with modernistic airplane in gold. Very best Log Book obtainable. Meets C. A. R. **1.37**



AVIATION JEWELRY—*For Men and Women*

No. P1751—Ladies' Blue Lavaliere. Sterling Silver, with blue enamel. Very handsome..... **2.69**

No. P413—Ladies' Blue Wristlet. Sterling Silver, with blue and black enamel..... **2.67**

No. P463—Airman's Pride Wristlet. Sterling Silver, Modernistic design, snake chain..... **2.50**

No. P410—Supreme Wristlet. Made of polished Dirigold. Handsome modernistic design..... **1.95**

No. P408—Wings Wristlet. Made of polished Dirigold. Sturdy, long-wearing..... **1.98**

No. P459—Women's Wristlet. Sterling Silver, with handsome red stones..... **2.89**

AVIATION WINGS PIN

No. P507—Made of Sterling Silver, with delicately wrought wings, engine and propeller design. Has safety catch..... **1.25**

CIVILIAN FLYER'S PIN

No. P509—Made of Sterling Silver, with initials CF on shield and finely wrought wings design. Has safety catch..... **.75**

LICENSE CASES

No. P2324—High grade genuine leather, with gold imprinting. 6 windows take C. A. A. licenses slightly trimmed and folded..... **1.00**

No. P2316—A beautiful, very high grade FINE LEATHER case, with 6 windows for licenses and cards. Handsomely imprinted in gold. Zipper opening on 3 sides..... **1.95**

PROMPT SHIPMENT

•Satisfaction Guaranteed or Your Money Back

My Pledge to You-

• Satisfaction Guaranteed or Your Money Back

IF within 3 days, after you receive your order, you tell me that anything I sent you is not satisfactory in every respect, I'll refund your money immediately without argument—no questions asked. I can well afford to offer such a fine, clean-cut GUARANTEE because I know the extra high quality of the goods I offer and I want to keep you a satisfied customer. Send in your first order promptly and get my new BARGAIN CATALOG absolutely FREE.

(Signed) **KARL ORT**

No Order Accepted for Less than $1

FLYING - *and how to do it*

By Assen Jordanoff. who want facts. New Edition No. P1018 **1.25**

SKYBIRD TIE—Hand made of luxurious silk. Beautifully woven airplane design against cloud background. Blue, Red or Green. No. P1363 **1.19**

CLIPPER TIE—Lustrous silk, with Yankee Clipper embroidered in 4 colors. Specify Blue, Maroon, Green, Brown. No. P1358 **.88**



AVIATION COMPACTS

Loose powder double compact with gold-tone aviation insignia. Blue enamel. No. P1412 **1.95**

Loose powder double compact with gold-tone aviation insignia. White enamel. No. P1413 **.95**

ASH TRAY

Streamlined, sturdy 7 in. long. Has Douglas DC-2 Airplane. Handsome, All-Chrome finish. No. P1286 **3.50**

MAIL THIS COUPON NOW!

To KARL ORT (State Ring Size.....) Check or Money Order Enclosed for.....

676 West Poplar St., YORK, Penna.

All right, Mr. Ort, please send items checked, POSTPAID, as per your Guarantee (also send me Free Catalog).

Quantity		Quantity		Quantity		Quantity	
No. P206		No. P413		No. P509		No. P1464	
No. P207		No. P459		No. P602		No. P1468	
No. P302		No. P463		No. P1018		No. P1510	
No. P308		No. P501		No. P1286		No. P1515	
No. P311		No. P502		No. P1358		No. P1601	
No. P321		No. P503		No. P1363		No. P1611	
No. P408		No. P504		No. P1412		No. P1751	
No. P410		No. P507		No. P1413		No. P2316	
						No. P2324	
NAME.....						No. P2382	

ADDRESS .....

CITY..... STATE.....

The Arrow

(Continued from page 43)

After finishing the wing, it should be placed upon the wing-mount platform, carefully aligned, and an eyelet glued into the wing-mount platform to hold the birch key. The writer used only one key and aligned the wing after each flight. Glue pieces of balsa along the edge of the wing-mount platform and sand to the shape of the wing undercamber. Be sure to secure a snug fit for the wing on the platform. Also be sure that both the trailing edge and the leading edge are resting on the platform. The use of balsa strips along the edge of the platform increases its strength and prevents splitting.

The stabilizer is of conventional construction and uses a modified "Clark Y" airfoil. It is of large area and is extremely effective.

Place the plan on the working surface and cover with wax paper. Glue the trailing-edge parts together on the plan, holding them down with pins. The leading edge is one piece of medium-hard ¼" square balsa. *Soak* it well in hot water, knead with your fingers to approximate shape, and glue in place. Hold it on the surface with pins. It is an excellent idea to put a coat of glue along the inside edge of this piece, as this will reduce pull and warping tendency. Glue the tapered spar in place. Glue all ribs in place. When the glue has dried for at least six hours, remove stabilizer from plan and glue a piece of $^1/_{32}$" sheet, in one piece, from the leading edge to the back of the trailing edge and between the No. 2 ribs on the stabilizer. The piece of sheet is glued on the bottom of the ribs. Glue the tail key of the ⅛" round birch dowel in place, extending about ⅛" below the surface. There are two pieces of $^1/_{16}$x$^3/_{16}$" balsa which run along the joint where the rudder is glued on top of Rib 1. These pieces should not be glued in place until after the rudder is glued onto Rib 1. The pieces run from the leading edge to the trailing edge, add strength to the rudder mount and also provide a place for attaching the covering. Sand the edges to proper airfoil shape.

The rudder is of conventional construction and needs little in the way of construction hints. Glue the outline (R1-R2 and R3) together on the plan. Allow glue to dry. The airfoil is streamlined and is formed by gluing $^1/_{16}$" balsa strip on each side of the $^3/_{16}$" square spar. We suggest that you glue the spar to the top of the rudder and at the same time glue the bottom strips in place, holding them with pins. Be sure to glue both strips (i. e., on each side) at the same time. Then glue the remaining strips in place. Cut the rudder tab out of light sheet aluminum. Bend the hinges so that two fall on one side of the trailing edge of the rudder, and the middle one falls on the other side of the trailing edge. The rudder should be sanded to streamline shape before gluing the tab in place. Glue the finished rudder on top of Rib 1 on the stabilizer after gluing the two $^1/_{16}$x$^3/_{16}$" strips, mentioned above, in place. Place the stabilizer on the fuselage platform, align the rudder perfectly and mark the key position. Glue an eyelet at that point and on the stabilizer platform. Next, holding the rudder in perfect position, turn the fuselage over and carefully mark a line with a pencil on the bottom of the stabilizer and along the rear edge of its platform. Remove stabilizer from fuselage and glue a small piece of ⅛" square hard scrap balsa along each side of the stabilizer, at the point indicated by the pencil marks. The pieces will key the stabilizer in place.

Cover the bottom of the stabilizer with Silkspan. Shrink and give no more than two coats of dope. Be sure there is no warp. Cover the top of stabilizer and the rudder with *tissue*. Shrink and give two coats of dope.

When the entire plane has been completely finished, doped, wired, motor placed, batteries in sockets, and everything made ready for flight, with the exception of the flight timer, carefully balance the plane at the exact center of the wing—fifty-percent point of wing chord. By balance, we mean with the thrust line horizontal to the floor. Reach this point of balance by moving the flight timer around inside the fuselage until you have it in the proper place. Then mount it at this point. Your plane, finished, should weigh from twenty-two to twenty-four ounces.

FLYING

Take the plane to an open, smooth field, where you have plenty of room. You can, if you wish, try gliding it by pointing the nose at a spot about sixty feet ahead of you on the ground and give it a firm shove—into the wind. If you have balanced according to instructions, the plane will ride out with a slight tendency to nose up. Here is an unusual statement. If you have built this plane according to instructions, have the rudder set in a neutral position, you can open your motor wide for a test flight. Obviously you probably will not have perfect adjustment on the first flight, but this model will not spiral into the ground. It is extremely stable and will pull out of almost any bad position.

With your rudder set in a neutral position, make your first flight and observe the climb under power, and the glide. The climb should be in a slow spiral—either right or left. If the climb is too straight and the model hangs on the prop, move the tab very slightly either right or left until you have obtained a proper climb. If, after the motor cuts off, the plane glides straight, it should have a tendency to dip a little. This indicates proper balance. Subsequent rudder tab adjustments to cause the model to circle either right or left in about four-hundred-foot circles will eliminate this dip.

With respect to motors, this plane operates best with the Ohlsson "19" or motors of like bore and stroke. The smaller bore Class A motors will not bring out its peak performance because of insufficient power. An Ohlsson "23" takes it up like a skyrocket.

THESE ARE THE BOOKS the AIRMEN USE to make themselves BETTER, SAFER FLIERS

The standard books on flying – the world over –
***by* ASSEN JORDANOFF**

Foremost aviation authority—pilot, instructor, engineer and technical adviser to leading American airlines since 1921.

A complete flying course between covers that will shorten your dual time instruction and help prepare you for all grades of Federal licenses . . . .

YOUR WINGS
The Manual of Flight

REVISED EDITION just off press!

DOZENS of brand-new, specially-made drawings, showing newest type planes, have *improved* this book. More than ever before it gives you the perfect mental picture of the way to fly an airplane that every pilot *must* have to be successful.

Never has there been such a book on flying! The text is written in simple, natural, instructor-to-student words, *yet every word is technically correct.* Hundreds of specially-made *drawings and diagrams show graphically every step in the training of an experienced pilot,* plus the operation of planes, motors, controls, instruments, radios, navigation, etc.

Published with the stamp of approval of the entire aviation industry, YOUR WINGS has been translated into seven languages, and is used by both professional and student airmen, and accredited aviation schools, the world over. *425 illustrations,* size 7" x 9½", $2.50.

Step-by-step representation of a flying maneuver—one of hundreds, from YOUR WINGS

The best work on meteorology and all the new instruments recently installed to make flying safer . . . .

THROUGH THE OVERCAST
The Weather and the Art of Instrument Flying



C. R. SMITH, President of American Airlines, Inc. says: "This book has taken the subject of meteorology out of the mathematical equations and has made it simple to understand. It explains instruments, radio and all allied subjects, through a series of pictures, so thoroughly that it will help not only the professional airmen, but the fledglings."

THROUGH THE OVERCAST is the first complete and *practical* book on what has been incorrectly called "blind flying". Written in the same, easy-to-understand and-remember manner of "Your Wings". *300 specially made illustrations of all kinds of weather and instruments.* Size 7" x 9½", $3.00.

OVER 700 ILLUSTRATIONS
show aviation's every secret

Together, YOUR WINGS and THROUGH THE OVERCAST form the most complete and practical aviation library available today. They are incomparable training and reference books for anyone who is airminded: students, pilots, mechanics, instructors, private plane owners, manufacturers, airline employees and executives, hobbyists — anyone interested in planes and flying.

In these two volumes, everything from basic principles of flight through the newest developments in navigation, instruments, meteorology, engines, radio, aerobatics, instrument flying, military and scheduled airline aviation, etc., is completely described in *words* and *pictures,* by *experts.*

SEND NO MONEY

Just sign and mail the coupon. When books are delivered, deposit price with postman. If, in 10 days, you decide not to keep them, return books and your money will be refunded.

This 10-DAY TRIAL OFFER protects you fully

YOUR WINGS and THROUGH THE OVERCAST are available at any bookstore or from the publishers. The coupon below will bring them to you *on approval* for 10 days. You have nothing to lose. YOUR WINGS costs $2.50, *only if you decide to keep it.* THROUGH THE OVERCAST, only $3.00. Save money by buying both books, boxed, for only $5.00. Books may be returned within 10 days for full refund if you are in any way dissatisfied. Mail the coupon today!

Tear out, sign, and mail to
FUNK & WAGNALLS COMPANY
Dept. 126 354 Fourth Ave., New York, N. Y.

Send me the books I have checked below. When the postman delivers them, I will deposit with him the price indicated, plus a few cents postage. I understand that if I am in anyway dissatisfied, I may return both or either of these books within 10 days for full refund of purchase price.

☐ **YOUR WINGS, $2.50** ☐ **Both books, boxed, $5.00**
☐ **THROUGH THE OVERCAST, $3.00**

Name.....

Address.....

City & State.....

Check here ☐ if you enclose remittance. Books will be sent post *free.* Same return privilege applies.

HIGHEST QUALITY...
MORE-FOR-YOUR-MONEY
DOPES


and
CEMENT
by
TESTOR
Dopes by Testor . . . packaged in big, handy, clear-glass bottles . . . have tremendous covering power, true colors and brilliant gloss, no blushing, firm but flexible "draw", a smooth finished surface, light weight. The complete line includes clear dope, colored dopes in a full range of colors, banana liquid, thinner. Testor's Model Airplane Cements . . . including Formula M-77 developed especially for gas models . . . are quick drying, strong and tough, crystal clear, light in weight. Insist upon TESTOR'S *by name!* At dealers everywhere . . .

BIG, NEW DOUBLE SIZE TUBE 5¢
(HOLDS 1 FULL OZ. SHOWN ACTUAL SIZE)
TESTOR CEMENT CO.
"The House of Adhesives"
ROCKFORD, ILLINOIS
WORLD'S LARGEST MANUFACTURERS OF MODEL AIRPLANE CEMENTS

Engineering Made Easy

(Continued from page 18)

use that is most helpful when those formulas are to be used in an examination.

I had been building gas models for four years before I entered Boeing, and had spent many hours tinkering with motors and looking for the thousand and one bugs that always creep into this type of ship. I came to regard all of this taking apart, regasketing, and rewiring as part of the price paid for being an advanced aëromodeler. Model engines, however, operate upon exactly the same principles as do the real ones, and the knowledge gained from work with the little ones is applicable to the real thing. The fact that model engines are practically all of the two-stroke cycle type does not prevent their teaching a lesson about dirt in the bearings or in the fuel. The same thing can be learned from a real engine, but the boy who has had his Baby Cyclone ruined by grit has learned his lesson just as well as has the mechanic who has ruined a twin-row Wasp.

The school's electricity course covers many elaborate features of ignition systems, but the wiring of gas models provides a fundamental knowledge of the subject that is not wasted merely because the material is gone over again and elaborated upon in complete detail.

The wood shop gave my ten years' experience in the handling of thin strips of wood a chance to express itself, where high school and college manual training shops, with their bulky projects, had not. Steaming strips of wood and holding them in jigs was practically a habit, as was the cutting of gussets and clamping of glued joints.

The construction and repair of aircraft is another shop course where model experience comes in handy. Models, while smaller and more simple than real machines, are nevertheless faithful replicas of them as far as basic structures and principles of operations go. The course covers all the major parts of the airplane, and the lessons learned from models again prove their worth. In one project, for instance, the problem is to determine the pitch of a certain propeller. Having done this with model props many times makes this problem a familiar, and therefore simple, one for a model builder.

The same course teaches, among other things, about dope and its uses. What the class learns from the lecture, model builders learn from experience: namely, that doping is best done in a warm and dry room. Many model color jobs are ruined by blushing or by uneven drying before the builders catch on, but that lesson, taught by experience, is as well learned as is any classroom demonstration.

Model experience has helped my meteorology course in more ways than one. I have had experience with thermals, lee eddies, convection and deflection currents just from flying models, but in traveling to contests I have acquired a pretty good knowledge of the topography of the surrounding country for a radius of three hundred miles, and am able, therefore, to understand just why different parts of the State have such different kinds of weather.

It is in mechanical drawing, though, that model experience has given the most help. My model drawings have always been several jumps ahead of my school drawings. In designing my first gliders, I had to use projection drawings before ever enrolling in a drafting class. The building of tapered wings and elliptical fuselages made it necessary for me to work out a method of lofting ribs and formers long before reaching that advanced stage in a drafting room. In addition to this, I acquired a practice in the use of instruments that would have taken many hours of classroom time to get.

The examples that I have given here are a few that will show how working on model airplanes has helped me with my study of the real thing. The fundamentals of the subject can be learned from a book, or they can be learned from experience, but experience is generally the best teacher, especially when the situation calls for a bit of independent research.

I do not mean to imply, however, that model airplanes can be used as a substitute for a course in a specialized aëronautical school like Boeing. The experience gained in the designing, building and flying of models is basic, and provides a sound foundation upon which the school, with its scientific treatment and correlating courses, can build a substantial education.

I have a year at Boeing still before me, and I expect during that year to find more ways in which the lessons taught by the building and flying of models can help me.

Fairchild PT-19 Army Trainer

(Continued from page 35)

cess. Stringers which run back the sides are cemented directly to the under-frame.

To represent effectively the metal engine cowling of the real Fairchild, the nose forward of Section 2 should be "filled in" with pieces of $^1/_{16}$" sheet. Accurately cut the individual pieces so they will fit neatly within the space between the stringers and formers. The nose block is cut from a medium-grade piece; cut out the square hole, as shown, for the rubber motor to pass through. Cement the roughly cut block to the nose and then sandpaper the whole nose to a smooth, attractive shape. If desired, the nose can be covered with thin sheet balsa instead of the suggested method.

The top of the fuselage from 3-T to 6-T is covered with soft sheet. Space limitations prevented making a complete pattern of this part but the cockpit shape is indicated. A piece $^1/_{32} \times 2 \times 4\,^9/_{16}$" is required; check the plans for the exact position of the cockpits. Cement the covering in place, using pins to hold it fast until dry. Finish the section between 2-T and 3-T by "filling in" with sheet balsa as before.

It is necessary for the wing to be of sturdy construction since the landing gear is attached to it. Ribs are cut from $^1/_{32}$" sheet with the exception of W-4 which is $^1/_{16}$" thick; two of each are required. A full-size left wing plan must be made. The various parts are assembled directly over the plans. Sizes of the various spars, et cetera, are noted on the plan. The $^1/_{16} \times ¼$" hard balsa spar to which the landing struts are attached is not placed until the dihedral is added. Scale dihedral of 1⅞" proved satisfactory on the original model, but to those not interested in exact scale we recommend an increase of about ¼" in each wing for an added measure of stability. The wings must be joined together accurately and solidly. Attach the ¼" deep spar and reinforce the junction necessitated by the dihedral. Trim and sandpaper the leading and trailing edges as well as the tips.

Any excess weight in the rear of the model must be balanced by additional weight in the nose, so exercise care to prevent any unnecessary weight in making the stabilizer and rudder. Both are constructed in a similar manner; the outlines are cut from $^1/_{16}$" sheet and the spars and ribs are $^1/_{16}$" square medium stock. Light strips are cemented to both sides of the ribs and when dry they are cut and sanded to the streamline shape indicated on the plan. Surfaces constructed in this manner are light yet they will not warp readily.

The landing-gear struts are fashioned from .040 music wire. The wire is bent in such a manner as to join the spar provided for that purpose and Rib No. 3. Attach the struts in place with thread and plenty of cement; use a needle and sew right through the rib and about the wire. Be sure to make a right and left strut. The balsa and rubber tubing covers are added after the wing is covered.

Wheels are made from laminated disks of balsa, or they may be purchased. Bearings should be cemented to the sides so they will revolve accurately and smoothly.

A neat, attractive covering is necessary for any fine flying scale model. The frame must first be prepared for the covering by lightly but thoroughly sanding every part to remove all flaws and roughness. Blue and yellow colored tissue is used. Cover the fuselage, first using the blue tissue. Thin dope or banana oil is used as adhesive to stick the tissue to the frames. Grain of the paper should run from

(Turn to page 48)

Ladeez—Gents 'n' Folks: Meet the New Lightweight Champ!

I don't know nuttin' about no labatory t'eeories, see—but I knows a tough, fightin' champeen when I sees one, see! 'n' take it from me, folks, this new Super ATOM is got what it takes!

It's built rugged-like, like a champ should be, see, tall-like and lean—without a excess bulge on its frame. The fin area of the new high compression cylinder has been tremendously increased which means it runs cooler—and you know what that means in steppin' up the stamina!

I seen many a champ in my days,—but I'm tellin' ya this Super ATOM is the busiest, fightin'est, speediest ever—it's a honey! Take a tip, folks, put a Super in *your* corner and you're a cinch to cop the duke.

BIFF—The Trainer!



SUPER ATOM SPECIFICATIONS

STROKE ½" BORE ½" DISPL. .097

WEIGHT Complete with TANK & PLUG **1¾ OZS.**

The SUPER ATOM *INCLUDING* spark plug, coil, condenser and tank weighs less than the next comparable class 'A' engine *BARE*.

SUPER ATOM'S precision engineering assures maximum compression at any RPM. The secret lies in the new valve seat of ingenious design. The rotary valve action has been advanced to achieve perfect coordination between intake and combustion establishing a new high RPM peak.

When first introduced, The MIGHTY ATOM established a new era for Class 'A' flight (construction economies, higher speeds, greater endurance) this new, SUPER ATOM raises the ceiling even higher!

The Super is more ruggedly-built, more masculine in looks—tougher—and its enormously increased power will keep it the darling of the Class 'A' flyers.

In the sub-piston alone, the ball and socket joint has been *trebled* in strength! The Super will fight its very heart out for you—up to 9,000 RPM (with prop) without missing a beat—without fatigue! We guarantee this engine will develop the highest-power-to-weight ratio of any engine regardless of price.

Cylinder porting has been enlarged almost 60%! Results in lower gas velocities (minimum power loss) plus the fastest, most complete scavenging ever achieved.

Whether you buy on the basis of price—or performance!—The new SUPER ATOM *delivering 60% more power* is the best dollar-for-dollar investment!

24 HOUR DELIVERY GUARANTEED!

NO PRICE INCREASE!

The Super ATOM is priced right—not too low at the sacrifice of quality, not too high at the sacrifice of friends! It remains the same.

$12.50 ANYWHERE IN THE U. S.

WITH MATCHED COIL SPARK PLUG & CONDENSER

IT'S THE NEW Super Atom

At all dealers Now—or you can order by mailing this coupon→

MICRODYNE ENGINES INC.

Dept. AT-12 BOX **245** GENERAL POST OFFICE NEW YORK, N. Y.

FACTORY ORDER COUPON

MICRODYNE ENGINES (Dept. AT-12)
General Post Office Box 245, New York City

I enclose $12.50 for which please send the new SUPER ATOM Complete with coil, condenser, spark plug, and tank.

☐ Check here for C. O. D. service.

NAME.....

ADDRESS.....

CITY..... STATE.....

IF YOUR DEALER cannot supply you, rush coupon (giving dealer's name) for same day shipment.

(New ATOM descriptive Booklet 6c)

SWEEPING THE COUNTRY!

THE NEW DE LUXE SERIES BY

Capitol

MONOCOUPE 90-A

STINSON GULLWING JR-10

TAYLORCRAFT FOR 1940

RYAN STM-2—ARMY TRAINER

FEATURING

- **GIANT ALUMINUM COWLS** ON STINSON AND MONOCOUPE
- **ALUMINUM SPINNERS** ON TAYLORCRAFT AND RYAN
- **NEW MASTER PLANS** PLENTY OF ILLUSTRATIONS & PHOTOS
- **CUT-OUT WHEELPANTS** AND SEMI-FINISHED PARTS
- **"SILKSPAN" COVERING** AMERICAN MADE—BETTER—STRONGER
- **COMPLETE**
- **STURDY AS GAS MODELS** WILL HOLD SMALL MOTOR
- **REALISTIC**
- **WINGSPANS—48 to 50 in.**

ACCLAIMED BY EXPERT BUILDERS AS THE GREATEST DOLLAR FLYING MODELS EVER MADE. BUILD ONE AND YOU'LL UNDERSTAND WHY THEY ARE "SWEEPING THE COUNTRY."

$1 **AT DEALERS**

BY MAIL ADD 15c

DEALERS—JOBBERS: WRITE ON LETTERHEAD FOR INFORMATION ON THESE KITS AND THE SUPERB LINE OF 25c and 50c KITS, GAS MODELS $2.00 and $5.50.

CAPITOL AIRCRAFT & SUPPLY CO.

1613 EAST NEW YORK AVE. BROOKLYN, N. Y.

DISTRIBUTORS FOR EASTERN PA.
M. B. SPOTTS
3141 N. BROAD ST. PHILA., PA.

DISTRIBUTORS FOR EASTERN MASS.
STANLEY-WINTHROP'S,
7 REVERE RD. QUINCY, MASS.

SYNCRO B 30

$6.95

Complete with coil and condenser

Head of the B Class

THE BEST THAT MONEY CAN BUY

The Syncro B 30 engine has swept the country. Its amazing power, speed, easy starting and light weight has made this engine the leader in the B class.

Enthusiasts like the new Syncro timer which eliminates trouble caused by dirt, oil or grime. There are no points to file or adjust. Self-cleaning, foolproof, self-adjusting and self compensating for wear.

Positive-set carburetor insures correct adjustment in spite of vibration, landing shocks, etc. No burnt fingers with this feature.

Cylinders and manifolds of special aluminum alloy are moulded in one unit—gives better service than either cast iron or steel. Pistons fitted with 3 rings give long periods of perfect performance.

Forced-Feed Lubrication through crankshaft insures bearing protection.

SPECIFICATIONS

Syncro B 30:—Bore 13/16" Stroke 9/16"
Displacement .292. H. P. 1/7-1/6. Weight 5½ oz.
R. P. Ms. 700-15,000. May be inverted
Class B: A. M. A. rules.

Buy Syncro B 30 from your favorite dealer. Catalog L40 on request.

SYNCRO DEVICES, Inc., 743 Beaubien, Detroit, Mich.

Member Model Industry Assn. N. Y. Sales: 200 Fifth Ave.

Fairchild PT-19 Army Trainer

(Continued from page 46)

the nose to the tail. Numerous small pieces of tissue must be used to prevent wrinkles; individual pieces should be lapped neatly. The nose and other wood parts should be covered with tissue, too. The wings and tail surfaces are covered with the yellow tissue; the grain runs spanwise. Attach only the extremities of the area being covered. Tips, et cetera, require separate pieces. The parts are lightly sprayed with water to tighten the tissue, but they are not doped until the model is assembled.

The various parts should now be assembled. Cement the wing in place; if the structure has been reproduced accurately the angle of incidence will automatically be correct. Finish the under section from wing to fuselage with pieces of $^1/_{16}$" square. Wing root pieces W-R are cut from $^1/_{16}$" sheet and attached between the wing and fuselage. Fillet pieces to be cut from $^1/_{64}$" sheet are shown on the plan. The pattern indicates the shape of the fillets on the original model, but since more miniatures will vary a little, paper patterns should be made to fit your model exactly before the sheet balsa ones are cut. After the fillets are cemented in position, they are covered with blue tissue, as is the uncovered portion under the wing. It will be necessary to cut the rear of the fuselage temporarily to admit the stabilizer, which is attached at the exact angle indicated. Offset the rudder a bit to counteract torque. Tissue fillets are placed between the stabilizer and rudder. Any wrinkles in the covering should be moistened with water and permitted to dry before the entire model is given a coat of clear dope. Dope should be applied in a dry room to minimize the chance of "blushing."

Numerous details can be added to improve the model's appearance without harming the flight ability. Streamline covers at the top of the landing gear struts are made from pieces of balsa, while the lower part of the strut is covered with rubber tubing of the correct size. Washers soldered to the ends of the axles will hold the wheels in place. The stars, rudder stripes, "U. S. ARMY," et cetera, are made from colored tissue and the effort required in making them will be amply repaid by the snappy appearance they add to the model. Control surfaces are outlined by thin strips of black tissue. The pylon between the cockpits—it protects the pilots in the event of a turn-over—can be made from thin pieces of bamboo. Celluloid windshields, the tail wheel and other details should be added.

For best flight performance any flying model must have an efficient propeller. Select a hard block $\frac{7}{8}$ x $1\frac{3}{8}$ x $7\frac{1}{2}$" and cut out the blank as shown. Carve a right-hand prop with a bit of undercamber in each blade. The spinner is made in two pieces and glued to the sides of the prop. Cement a washer to the back so it will revolve smoothly. A freewheel device of some sort should be used to help improve the glide. Sand the propeller and color-dope to a nice finish.

The removable nose plug is shown. A disk of $^1/_{32}$" plywood forms the front while the back is laminations of balsa. Fix the thrust line by cementing washers to the front and back of the plug.

For the prop shaft .034 music wire is used. A loop to which the winder can be attached should be bent on the front of the shaft. Place several washers between the propeller and nose plug.

Eight strands (four loops) of $\frac{1}{8}$" brown rubber are used to power our trainer. Hook the rubber to the prop shaft and with the aid of a weighted string drop the other end through the fuselage. A bamboo pin holds the motor in the rear.

FLYING

To prevent damage to the model at this crucial stage, test flights should be made over deep grass. The descent from a hand glide should be flat and smooth; a small corrective weight may be required to obtain the desired results. Once the glide is good, all further adjustments are made at the nose plug. Right or left thrust will control the amount of circle and a bit of downthrust will correct a tendency to mush or stall.

The author's PT-19 has been flown many times and proved to be an excellent performer. When winder-wound it climbs in large left circles until the power is exhausted and then it descends in easy right spirals. It is tough, too, having emerged from encounters with trees and other model catchers with only minor tears in the covering.

Earl Stahl's fine PT-19 is the result of careful work. Take your time.

Free Offer

Your choice of these 2 offers FREE with orders of $1.00 or more for supplies only.
A. 60 1/16x1/16x18 Balsa, 1 bottle Cement, and 1 pair 2" wheels.
B. Any two 20" Flying Plans listed below.

18" BALSA
1/16x1/16 100, 5c
1/16x¼ 35 for 5c
1/16x3/16 18, 5c
1/16x¼ 15 for 5c
3/32x3/32 30, 5c
⅛x¼ 30 for 5c
⅛x⅛ 10 for 5c
3/16x3/16 8, 5c
¾x⅛ 6 for 5c
⅛x⅛ 2 for 5c
1/64x2 4 for 10c
1/32x2 8 for 10c
1/16x2 8 for 10c
3/32x2 7 for 10c
⅛x2 6 for 10c
¼x2 3 for 10c
3" or 36" double above prices: 5 foot, double 36"—prices. Add 10c package, for 36"—20c for 5-foot.

SHEETS 12"x2"
1/16 10 for 10c
⅛ 7 for 10c
¼ 3 for 7c

18" PLANKS
1x1 5c; 1½x2 6c
1x1½ 9c; 1x2 10c
1x3 15c; 2x2 18c

WIRE
6-8-10-12-14
2 ft. 1c
1/16 dia. 5 ft. 12
.050 3 ft. 5c
3/32 dia. 5 ft. 15c
⅛ dia. 5 ft. 25c

PROP SHAFTS REAR HOOKS
12 for 8c

CAMEL'S HAIR BRUSHES
Small 3c; Lge. 5c
Extra large ..8c
Flat, large...10c

PROP BLOCKS
½x ¾x 6 6—5c
¾x1 x 8 3—5c
¾x1¼x10 3c ea.
¾x1¼x12 3c ea.
1x1½x12 4c ea.
1x1½x15 7c ea.

WHEELS per pr.

Dia	Birch	Blsa	Celu
½	.01	.03	
¾	.02	.04	.05
1	.03	.05	.07
1⅜	.04	.08	.10
1⅞	.07	.10	.16
2	.15	.15	.30

CEMENT and COL. or CLEAR DOPE
1 oz. 5c
Large bot. 8c
½ pt. 35c

CLEAR DOPE
½ pt. 30c

PROPELLERS

Balsa	Mach. Cut	Paul-O-Wlna
5"	4c	10c
6"	5c	15c
8"	7c	25c
9"	8c	30c
10"	8c	35c
12"	10c	45c
14"	14c	
15"	15c	55c

TISSUE, AA
All col., doz. 19c
Silver ....ea. 5c
Superfine, wh. 5c
Prop Hinges 15c

THRUST BEARINGS, dz. Sm. 10c; lge. 15c

NOSE BLOCKS
1x2x1 .....1c
2x2x1 .....2c
3x3x1 .....5c
3x3x2 .....8c
3x3x3 .....10c

WASHERS
1 doz. ⅛ or ¼ 1c

NOSE PLUGS
½" .....12 for 3c

15" BAMBOO
1/16x¾ 6 for 5c
Shredded 3¢—5c

SPONGE RUBBER WHEELS
pair 1" 15c
1¼" 18c

PNEUMATIC WHEELS
3½" pair ..$1.25

CELLULOID
6x8 ..... 5c
12½x16 .....19c

RUBBER LUBE
Bottle 10c
Paste, can ...10c

BAMBOO PAPER
White ..2 for 15c
Yellow, red, green or blue, each 10c

RUBBER
.045 ...25 ft. 5c
1/16 sq. .15 ft. 5c
⅛ flat ..15 ft. 5c
Skein 55c
3/16 ..10 ft. 5c

REED
1/32-1/16 2 for 1c
3/32 or ⅛ 1 ft. 1c

INSIGNIA
24 and stripes 5c
Water Sprayer 15c
Sandpaper 12 for 5c

ALUM. TUBING
1/16,3/32,⅛,ft.7c
3/16, ¼, ft. 10c
5/16.. ft ..15c

SHEET ALUM.
.0004x4x15
2 sheets 3c
.005 in...6x6..5c
.010 in...6x6..6c
1/32 ..6x6 ..15c
1/16 ..6x8 ..30c

PLASTICBALSA
Large can ...25c

MODEL PINS
½" or 1" Pkge. 5c

DUMMY RAD. ENGINE (Cellu.) With or without Cowl
1¼" d. 15c; 2" d. 20c; 3" d. 25c

PURSUIT MACH. GUNS
¾", 1¼" or 1¾", ...each 5c

ALUM. COWLINGS
1½" 15c; 2" 18c
2½" 25c
Specify whether Anti-drag or closed

BOMBS
¾"..4c; 1½"..7c
3" ..12c

GUNS WITH RING MOUNT
1¼" 10c; 1¾" 15c

FREE POSTAGE
Add 10c packing charge on all orders in U. S.; Foreign 15c, over $1.00 add 15%. No C.O.D's. No stamps.

DOWELS
1/16x6" ..doz. 5c
⅛x18" ..2 for 3c

METAL PROPELLERS
2 blades 3 blades
1½"...5c ...8c
2½"...10c ...15c
3½"...15c ...20c
4½"...20c ...25c

M&M WHEELS
1⅜ to 1⅝ ...50c
1⅞ to 2⅜ ...60c
2⅝ Gas. Mod. 90c

WING AND TAIL LIGHTS
12"..10c 15"..15c
21"..20c

BATTERIES
Penlite 5c
Large or Int. 10c
Battery Boxes
Penlite & 1" 35c
Penlite, 1½" 35c

IGNITIONWIRE (High tension)
High tension leads 15c
Hookup ...ft. 2c
Ball bearing washers ...10c
Gas funnels 10c
Bushings 4 for 1c
Spinners 25c
Brown F. $ 7.50
Ohlsson 23 16.50
Atom 12.50

Gas. Mod. Silk, ... yd. 45c
Austin Timer 1.00
Clock Timer 0 sec. to 1 min. 1.75
Smith Coil $2.50
Model Knife 10c
3 extra blades 10c
Pine center
Balsa wheels for Gas.Mod. 3" pr. 35c
2" pr. 25c
Spark Plugs..65c
M. Motor mounts 25c
Fly Wheels..1.00
Tog. Switch 25c
Alligator clips .2 for.....15c
Plugs and Jacks Set.....20c
Condensers ..15c
Imperial Gas Kit 66" $4.50 complete
wheels and prop.
Comet Kits
Berkeley Kits
Scientific Kits
Gasprops all sizes 25c-35c-50c-60c
FREE Wheeling sets 10c
Transmission sets 25c-40c-50c
Triple 75c

20" FLYING PLANS 10c — 3 FOR 25c
Sparrow Hawk, Spad Chass., Vought Corsair, Curtiss Swift L. W., Waco Cabin Biplane, Douglas Dolphin, Boeing P12F, Fokker D-VII, S.E.5, Goshawk, Gee Bee, Boeing P26A, Monocoupe, Northrup Gamma, Fairchild 24 Cabin, Corben Super Ace.

SELECT ANY 1 OF THE ABOVE PLANS in 20 in. FLYING KIT postpaid... 35c

COMPLETE 16-page CATALOG, 5c
Dealers: New low prices on orders for $2.50 or more. Send 3c for list.

IMPERIAL MODEL AERO SUPPLY
263 MAIN ST., Dept. 12-A, HACKENSACK, N. J.

NEW LIONEL CATALOG

Just Out! 64 PAGES BRISTLING WITH NEWS

Packed in this great, new Lionel Catalog is the most amazing fleet of trains Lionel has ever rolled out on the rails. Get the whole story. Send for catalog today.

MAIL THIS COUPON!

LIONEL Dept. 70 15 East 26th Street, New York
Enclosed is 10 cents to cover postage and handling. Please send a copy of the new Lionel Catalog at once.
NAME_____
ADDRESS_____
CITY_____ STATE_____

Goods' Championship Radio Model

(Continued from page 33)

small lift. (Solder a conecting wire to this same piece.) The 2-56 brass screw (J) is tipped with cement for insulation. A small piece of coin silver (from dime) is soldered to screw (H) for a contact. The relay is now ready for assembling.

Slip armature (A) and frame (E) into the coil slot (C). Frame (E) should fit snugly and armature should be free to rotate. Cement field pieces (F) in place with a spacing of $^3/_{32}$" between their ends. This spacing affects the sensitivity and range of the relay. Glue the permanent magnet (M) to the bottom of the field pieces. (Small Alnico magnet, thirty-five cents, Central Scientific Co., Chicago, Ill.) Note that when in operation, *the armature does not touch the field pieces.* The movement of the armature will be about equivalent to the thickness of a sheet of paper. The contacts will easily handle ten times the current needed to operate the control mechanism.

CONTROL MECHANISM

The control mechanism (Figs. 5, 6) for rudder and elevator is the rubber-powered electro-magnet escapement type. It has several distinct advantages. Its small weight of one half ounce makes it easy to mount directly within the fin or stabilizer, resulting in a direct mechanical connection to the flap. The five-position cycle and rapid action results in a fast, yet precise control. The escapement stays "in step" with the special transmitter switch (Fig. 9) and may be jerked through as many as four or five complete cycles per second without missing. Little electrical power, 150 milliamperes at 6 volts, is needed, thus conserving batteries.

Examination of Figs. 5 and 6 shows the details of the mechanism. The operation is as follows: In Fig. 6a the escapement wheel (A) spoke (1) is held against the armature rocker (B) by the tension of the wound rubber band. Note in spoke (3) the pin which travels in the slot of the rudder arm. Turning on the magnet (by turning on transmitter) pulls the armature rocker away from spoke (1) and stops it in the position in Fig 6 (b). This is the "one-half right" position of the rudder, giving a large right circle. Turning off the magnet (transmitter off) releases spoke (1) and stops spoke (4) in Fig. 6 (c). This is the full "right" position of the rudder and results in a small right circle. Thus it is seen that turning the transmitter on and off advances the spokes one quarter of a turn. A complete cycle would be N-½R-R-½R-N-½L-L-½L-N, giving a variety of positions. This fast-acting escapement can pass through the whole cycle in one-fifth second!

Construction should not be difficult with the help of Fig. 5 and the photograph.

Each of the coils (c) has about 80 ohms resistance and will require about 70 feet of No. 40 wire. The fiber coil ends are glued to the iron core and the core is doped with thick

TAYLORCRAFT SPORTPLANE

36" Span. Length 22". 1" Scale. Weight 2 oz.

Model on floats

COMBINATION LAND AND SEAPLANE SET

A beautiful exact scale flying model with unusual flying range, so light it will rise from land or water in 6 feet. Const. set contains all parts printed on balsa, carved propeller, hardwood wheels, 2 oz. white dope, ½ oz. black, glue, full sized scale drawing, and all parts to build, including materials to make floats **$1.50**

BOEING B-17 FLYING FORTRESS

44" Span. Length 30". Color, silver

Set has all parts printed on balsa, four 2" turned balsa motor fronts, four 4" carved props, celluloid wheels, set of paints, glue, and full size drawing. Set, postpaid..... **$4.50**

SEVERSKY P35 ARMY PURSUIT

32" Span. Length 25". 1" Scale. Color, silver

Set has all parts printed on balsa, set of colored paints, glue, 4" balsa motor front, full size drawing, and all parts to build. Set, p.p. **$3.25**

CURTISS F11C4 NAVY PURSUIT

32" Span. Length 25". 1" Scale

Finest equipped model in the world. Set has 4½" scale celluloid motor, aluminum cowl, 10" prop shown, alum. step plates and wing walks, insignia, rubber, complete set of four colored paints, full size drawings, wheels, and parts printed on balsa. Const. set, postpaid..... **$4.50**

NORTHROP A-17 ARMY

24" Span. Length 17". ½" Scale

Set has turned balsa motor front, complete set of paints and all parts to build..... **$2.50**

BOEING P26A ARMY PURSUIT

22" Span. Length 17½". ¾" Scale

Set has 3" celluloid motor, 3½" tapered aluminum cowl ring, paints. All parts printed on balsa. Full size drawing. Set, postpaid.. **$2.75**

GRUMMAN F5F1 NAVY FIGHTER

24" Span. Length 17". Flying Model

Const. set has all parts printed on balsa, 2½" turned balsa motor fronts, grey and yellow paints, glue, etc., 7" carved props, full size scale drawing and **$2.95**

CURTISS P36 ARMY PURSUIT

37" Span. 1" Scale. Color, silver

Set has turned motor front, set of paints, glue, all parts printed on balsa, and full size drawing. Set, postpaid..... **$3.25**

CURTISS SO3COI SCOUT

30" Span. Length 24"

This is latest Navy Seaplane. Set has all parts printed on balsa, paints, glue, drawing. Flying Model. Const. set, postpaid..... **$2.95**

BOEING F4B4 NAVY FIGHTER
Solid Exhibition Model

22½" Span. Length 14½". ¾" Scale

Set contains completely finished balsa fuselage, with cockpit cut out, motor hole cut out and headrest attached; all you have to do is paint it. The wings, tail, and rudder are all cut to shape, but have to be sanded to proper curve. A 3" celluloid motor with aluminum motor front, 3½" tapered aluminum cowl, 7" scale chromium plated propeller, celluloid wheels, complete set of colored paints, glue, filler, and full size drawing. Set, postpaid..... **$3.95**

CURTISS HAWK F11C4 NAVY
DeLuxe Solid Exhibition Model

10½" Span. Length 7½"

This is a special deluxe solid model. Set has completely finished balsa fuselage, cockpit cut out, routed pants, wings cut to shape. 1½" deluxe cast motor, alum. cowl, 3 bladed cast prop, paints, drawing and all parts. Set p.p..... **$1.50**

NEW ELF CLASS A SINGLE

Bore 15/32. Stroke 9/16. .097 Cu. In.

Type 2 cycle, 4 port. R.P.M., 7500. CYLINDER: Cast aluminum lined with carbon steel. PISTON: Forged aluminum "micro-machined". BEARINGS: Two main bearings. TIMER: Elf "No-Drag", fully enclosed. AIR FILTER on carburetor intake. WEIGHT: 3 ounces. Flying weight, 8¾ oz. Price, ready to run with coil, condenser, and prop..... **$21.50**

NEW ELF CLASS A OR B TWIN

Bore 15/32. Stroke 9/16. .198 Cu. In.

BEARINGS: 12-ball thrust bearing, two main bearings. WEIGHT: 5 ounces. Flying weight, 8¾ oz. WIDTH across cylinders, 4¼". These motors are the finest to be had. They are especially ideal for scale models, etc. Price: Twin, with coil and condenser..... **$31.50**

New Catalog No. 6—10c

Beautifully illustrated 7½" x 9½" 16 page catalog showing large photos of Army and Navy Fighters, Gas Motors, Gas Models, etc. Get yours today. 10c coin.

MINIATURE AIRCRAFT CORP. 83 LOW TERRACE STATEN ISLAND, N. Y.

Originally Ours

Sensational COMPLETE Gas Job Offer!

EVERYTHING Included!

- NEW Syncro B-30 Gas Motor
- Flight Timer
- "Bullet" Kit - 48" Wingspan - $1.50 alone including
- Air Wheels • Gas Propeller

ONLY $10.00 P.P.

PLUS **FREE MERCURY X-MAS GIFT**
Gas Motor Maintenance Kit
- Three gas-motor wrenches (in leather case)
- Electric soldering iron
- Magnetic insulated screwdriver

TRADE IN your old motor! We will allow you $1.50 no matter what condition or make. Include all parts. Send $8.50 and that old motor for this complete gas outfit!

We think this gigantic combination offer is the best value ever offered to American Model-Builders! Other companies have tried to copy this combination, but don't be fooled. BE SMART—BUY MERCURY! Thrill to the flight of the potential PRIZE WINNING "BULLET"! Make this the swellest X-MAS ever for yourself or someone you really like. . . Rush only $10 for this stupendous combination offer today!

CHOICE OF THESE GREAT DOLLAR KITS



Flying Cloud
Stinson Gull-Wing
Taylorcraft 1940
Monocoupe 90A
Ryan S.T.M.
Howard D.G.A.9
Stinson 105

Biggest Dollar Values ever. Complete in every detail. Easy-to-Build, Easy-to-Fly giant models. Tremendous wingspans. Really tops 'em all. Send $1 plus 15c postage.

THE "BEE"—CLASS B CHAMP! OF SKYSCRAPER CONTEST



Unusually high performance and sleek appearance. 48" span. The nation's sensation! Has Everything! $1.95 plus 20c postage.

MERCO ENGINE REPAIR KIT
Ideal X-Mas gift-item for gas model enthusiasts. Hundreds rely on it! Worth much more. Contains over 17 major items: Vise, soldering iron, nuts, bolts, tape, wire, file, wrenches, etc. Practically a necessity! $2.50 P.P.



FREE—EXTRA SURPRISE GIFT if you order SOON!
Send 3c for Latest Catalog of Motors, Kits, Supplies. Dealers write.

clear dope for insulation. Wind the coils in the same manner as the sensitive relay. Cover each coil with a strip of paper for protection and connect them in parallel.

The armature rocker (B) is bent from sheet steel and the corners are soldered. To the rocker (B) solder the armature (D), the shaft, and the spring (K). The rocker assembly is slipped into the rocker bearing (L) which is cut from sheet brass. Cement the bearing (L) to the face of the coils. When closed, the armature should fit flush over the whole core ends. A thin hard coat of clear dope over the end of the cores will prevent the armature from sticking (magnetically).

The frame (F) is cut from sheet aluminum. Take particular care with the holes for shaft (E). Cut escapement wheel (A) from sheet brass and solder shaft (E) and the control pin to it. Note ball-bearing washer is same type as used on outdoor rubber job. Installing adjustment screws (H) and (J) finishes the construction.

Adjust screw (H) so the armature travel is $^1/_{32}$". When armature is closed, the spokes should just clear the stop. Shimming the back of the coils takes care of this adjustment.

Set the spring tension with screw (J) so armature will close, using 1½ volts (without rubber). Before placing the mechanism in the plane, hook on a loop of $^1/_{32}$" rubber and wind in several hundred turns. It is possible to make it work on 3 volts. However, adjust it to function on 4½ volts. In the plane we'll use 6 volts—just to

Cement the mechanism in the fin or stabilizer, making sure the alignment is true, to give a neutral and an equal left and right. About 500 turns in the loop of rubber will be sufficient for several flights.

MOUNTING

The adjusted receivers and relays are mounted in a balsa rack shown in Fig. 7. Wires from the receivers are led to spring clips along the front of the rack. The battery wires are brought up to the clips. The front panel of $^1/_{16}$" sheet balsa is recessed so that none of the parts projects out in front of the rack. The rack may be built one-half size for one control.

The rack is tied down with rubber bands onto blocks of sponge rubber mounted in the ship. This isolates the unit from motor vibration and landing shock.

The battery board used with the two RK42 receivers is also shown in Fig. 7. Standard battery cases are used. Bind the batteries to the floor of the plane with rubber bands, remembering that the c. g. position of the plane is not to be altered.

Three wires from the rack back to the tail are tipped with spring clips at the tail end to allow easy removal of the tail surfaces. The complete circuit is detailed in Fig. 1.

TRANSMITTER (By Bill Good, W8IFD)

After some difficulty in awakening the airport manager at 5 a. m. to get into the hangar to plug our AC-operated transmitter into the 110-V circuit, it was decided to design and build an all-portable, 5-meter "super-dooper" transmitter just for radio control. Here is the result.

For both rudder and elevator control two wave lengths are needed. The transmitter is a two-frequency one, powered by a storage battery and genemotor. It represents one workable version involving the least number of parts and still retaining reliability. In brief, it consists of two 6V6G electron-coupled oscillators with their respective cathode coils tuned to 20 meters and a common tank circuit tuned to 10 meters. The 807 amplifier doubler is capacity coupled to the preceding plate coil and its output circuit is tuned to five meters. In other words, the single 807 acts as an amplifier for both frequencies, determined by the oscillators. Inasmuch as it is almost imperative that the transmitter be built by a licensed amateur radio operator, because it must be licensed and operated by a person who is licensed, constructional details will be kept to a minimum.

The circuit constants shown (Fig. 8) should prove satisfactory. However, some of the variable condensers used happened to be those that were on hand, and don't have to be followed too rigidly. The frequency of the electron-coupled oscillators may be set at any desirable point in the band with the aid of a 5, 10 or 20-meter receiver. Naturally, if using a 20-meter receiver, keep the oscillators between 14,000 and 15,000 KC; if using a 10-meter receiver, stay between 28,000 and 30,000 KC; and if using 5 meters, stay within the limits of the band.

ing condenser across the oscillators plate tank L_2. This coil is tuned by merely squeezing or stretching the coil itself. We tuned ours to the middle of the band by setting one of the oscillators to 14,500 KC and manipulating the coil until maximum grid current to the 807 was obtained (3 to 4 MA). At other frequencies in the band the grid current will naturally be less. Just one mil of grid current with the 807 in operation gives satisfactory results. The grid current is regulated by choice of resistors determining the screen voltage of the 6V6G's. Higher screen voltage—higher grid current. The plate current of the oscillators runs about 25 to 30 MA each. The 807 runs from 50 to 80 MA depending on the loading. Twenty watts input seems to be plenty for most flying. The final tank condenser is tuned halfway between the two frequencies used. A flashlight bulb with a pickup coil held near the plate coil can be used to indicate when the power output of either frequency is about the same (with antenna connected). To eliminate all relays it was necessary to bias the 807 so that its plate current wouldn't be excessive while not being excited—without bias the power drawn is within the plate dissipation ratings, but we hate to see our storage battery run down any faster than necessary! The bias battery is one of the small 45 V ones that has been discarded after serving its usefulness in the plane. If only one oscillator is used the 807 could be keyed in the cathode and the bias battery would be unnecessary.

One novel feature in the design and

NEW DEGREEMETER—EXCLUSIVE BEZELMETER!

Jardur 9 Feature Aviators' Shockproof Chronograph

Black Radium Dial — Non-Magnetic — 17 Jewels — 12 Hour Register

NO. 950

EXACT SIZE
SEND FOR NEW CATALOG

This new precision "Jardur" Aviators' Chronograph has been especially designed for Fliers. It is a necessity in modern flying—timing blind turns and air navigation in general. Indispensable in any cockpit. Used and endorsed by leading Pilots everywhere. **Also an ideal time-piece for technicians, model airplane enthusiasts, contest officials and sportsman.** Incorporates easy, quick-reading dial scales and registers. Controlled by two handy push-buttons—no complicated gadgets. Simple instruction sheet included.
Now you can afford the world's most modern and dependable Aviation Chronograph, ruggedly built to last a lifetime.
With unbreakable clear white "Lucite" Crystal and *new shockproof ("Incabloc") Protector.*

ACTUALLY 9 ACCURATE PRECISION-BUILT WATCHES IN ONE

(1) REGULAR WRIST WATCH (17 Jewels—Non-Magnetic)—black radium dial including radium sweep second, hour and minute hands—(2) TIME-OUT WATCH (Allows repeated starting without clearing the watch)—(3) STOP WATCH (1/5 split-second timing)—(4) TACHOMETER (indicates the number of miles—60 to 800—per hour any aircraft or object is moving over a known distance)—(5) 30 MINUTE REGISTER (indicates a total of 30 minutes of uninterrupted, accumulated time in minute recordings) First 2 minutes marked in red for timing turns.—(6) 60 SECOND TIMER—(7) 12 HOUR REGISTER (shows the exact time consumed continuously or intermittently in flight, without any calculations). (8) BEZELMETER—12 Hour Turning Bezel—This new important Bezelmeter is subdivided into 15 minute periods up to 12 hours, and by means of this free moving bezel which turns in either direction, the Pilot is able to tell instantly and automatically the actual gas or flight time remaining without any calculations. This bezelmeter works exactly opposite to the 12 Hour Register described above, which records the elapsed time.—(9) DEGREEMETER—For timing turns this scale is very valuable and is calculated on the standard rate turn of 360 degrees in two minutes. The scale is plainly marked up to 180 degrees for a 15 degree turn every five seconds covering the complete revolution of the sweep hand in one minute.

"Staybrite" solid stainless steel, satin-finish case, as thin as a regular wrist watch. Fully guaranteed and serviced for one year at no charge. If this Jardur Aviation Timer does not meet with your entire satisfaction, return it to us within ten (10) days, and your money will be refunded in full.

LIST $100.00—SPECIAL PILOTS' PRICE $49.50 DELIVERED

IN WATERPROOF AND DUSTPROOF SOLID STAINLESS STEEL CASE—LIST $125.00 SPECIAL PILOTS' PRICE $58.50 DELIVERED

JARDUR IMPORT CO., 21 West 19th Street—New York, N. Y.

operation of the transmitter is the incorporation of a switch in the positive lead going to the 807 plate and screen. When this switch is off, a weak or low-powered signal is given off when the oscillators are keyed, allowing the operator to tune his receivers at a distance of 10 or 15 feet from the transmitter and have about the same signal strength that the plane will experience should it get several miles away, after full power has been turned on. We call this our "hi and low" power switch, and always check the controls with both high and low power before taking the ship off.

The power supply for this transmitter is a 400 V-125 MA dynamotor powered by a 6-volt storage battery. Genemotor or vibrator packs of the 300 V, 100 MA variety are less expensive and will serve the purpose just as well. Be sure you use heavy wire from dynamotor to storage battery. We have a 300-volt DC power supply for testing and tuning of the equipment around the house where 100 volts AC is available.

The antenna consists of two auto-whip antennas mounted horizontally with an overall length of about 8 feet, fixed at the top of a 9-foot fish pole. The antenna is fed at the center with a half-wave-tuned line. The easiest way to adjust the line is to cut it to approximately the right length and slide the antenna in and out until maximum loading on the 807 occurs. If your whip antennas just reach 8 feet, as did ours, tuning can be accomplished by leaving the antenna set (at 8 feet), snipping off the feeders (approximately 8 feet) until maximum loading occurs. The antenna coil was quite closely coupled to the cold end of the 807 tank coil.

In the picture one can see the 6V6G oscillator tubes with their respective cathode coils in the shields-tuning knobs on the ends of the shields—located in the lower right-hand corner. The 807 on the left with its plate tank and antenna coil, in the upper left. Center right finds the plate milliameter and plate (hi-low power) switch. The hole above contains the bias battery and the control box with its 15 feet of flexible three-wire cable.

The switches on the control box (Fig. 9) were made from revamped Western Electric anticapacity switches and were positioned so as to simulate actual airplane controls. The switches were modified so that a dash was sent —contact made and broken—as the switch was pushed from neutral to left or right positions. This allows the rudder movement exactly to duplicate the position of the tiny "control stick" on the box. A push button may be used, for it is obvious that for every pulse sent from the transmitter the rudder moves through one position. It is only necessary to know what position the rudder is in to figure out the number of dashes or pulses that need be sent to the ship to get the required effect. The small "control stick" switch mentioned above saves a little brain work while on the field.

Our transmitter mounting was a semibrainstorm built of Presdwood—fastened where necessary with aluminum brackets and squashed inside a one-dollar "airplane luggage" overnight bag measuring approximately 5½x7¼x11" on the inside. The han-

Another Scientific Scoop . . . Just In Time For Christmas!

"ENSIGN" CLASS "B" MODEL AIRPLANE

Complete! Nothing Else To Buy!

Complete Combination Includes "Ensign" Kit and Everything Else Necessary!

A—"ENSIGN" KIT....*Sells Regularly for* $2.95
COMPLETE including: HOOK UP WIRE, WHEELS, PROP and BATTERY BOX MATERIALS.
B—TIMER.....*Sells Regularly for*.....1.00
C—BATTERIES (2).....*Sells Regularly for*.....20
D—MODEL KNIFE....*Sells Regularly for*.....15
E—BOTTLE OIL .....*Sells Regularly for*.....15
F—TEST BLOCK.....*Sells Regularly for*.....15
TOTAL VALUE.....$4.60

You Pay Only

$3.95

FOR EVERYTHING



SYNCRO B-30.....$6.95
COMBINATION 3.95
(Kit and Accessories)
$10.90

BROWNIE.....$7.50
COMBINATION..... 3.95
(Kit and Accessories)
$11.45

FORSTER "29".....$15.50
COMBINATION..... 3.95
(Kit and Accessories)
$19.45

OHLSSON "23".....$16.50
COMBINATION 3.95
(Kit and Accessories)
$20.45

It's Taking Top Honors Everywhere! SCIENTIFIC'S

ALL AMERICAN $1.00

45" WINGSPAN! *Postpaid or at Your Dealer . . . . .*

Although introduced to the public just one month ago, Scientific's "All American" has already won the acclaim of model airplane enthusiasts throughout America! And no wonder—for here's a plane that will capture your heart! Designed to fly, it has consistently made long, graceful flights of 2 miles and more! Its dashing, patriotic color scheme of red, white and blue has an irresistible appeal! Easy to build, too, even for a beginner! Complete kit, including detailed, full size plan is only $1.00 postpaid or at your dealer.

Scientific's New 1941 **BIG BARGAIN CATALOG** *Send* **5¢**

Chock full of flying thrills.

It's New! It's Different!

PARACHUTE PLANE

with automatic trap door release!

You model airplane builders who are looking for something "different" will find Scientific's new "Parachute Plane" to your liking—for here's a plane with features that are unequalled by any other plane on the market. Picture this—after climbing 300 feet or more, out comes a pilot with his parachute, floating gently to the ground, while the plane continues gracefully in its flight! And it's all done automatically! It's a trim endurance model, too, that will easily make flights of a mile or more! Postpaid or at your dealer. Only..... **$1.50**

SCIENTIFIC MODEL AIRPLANE COMPANY

218-220 AT-12 MARKET STREET, NEWARK, N. J.

NO OTHER SHIP CAN CATCH THE SPOOK!

CLASS A or B 48"

CLASS C 72"

ALL EYES ARE ON THE

SPOOK

Modelers are saying it is one of those models that happens once in a long time. SPOOK "48" Specifications—Wing span 4 ft. Flying weight with Ohlsson "19", 18 oz. Wing Loading 8 oz. per sq. ft. Can be flown as Class B with Ohlsson 23, Hi-Speed, or Brownie. Kit is complete with cement, dope, covering, and wheels. (Plans only 25c) $1.50

SPOOK "72" The first model that can handle an Ohlsson 60 Custom at full throttle! Climbing speed equal to the average B class ship. Put this ad where one of your relatives will see it as a "hint" for Christmas. Specifications—Wing span 6 ft. Flying weight 3 lbs. Power with Brown, Ohlsson 60, or other Class C engine. Kit complete with cement, dope, covering; and wheels. One of the finest performing models we have ever sold. (Plans only 50c)..... $3.95

GET A SPOOK FOR CHRISTMAS

MODELCRAFT SOARING GLIDER

TOWLINE GLIDER

New! 31½" Soaring Glider that has turned in many flights of better than one hour. Note: Modelcraft kits always contain enough wood to build your model!

Kit complete Add 10c Postage 25c

FREE!

Clip out headline "No other ship can catch the Spook" and mail for 1940 Modelcraft catalog. Send for yours today. It's FREE.

MODELCRAFT
7308 S. VERMONT AVE.
LOS ANGELES • CALIF.

dle was moved from the side to the top for portability.

It should be emphasized that *any* 5-meter transmitter with a few watts output will work the controls. Therefore, it isn't necessary to duplicate the one described, although it has proved highly satisfactory.

Again we repeat what has been mentioned in previous radio-control articles. The business of transmitting radio signals is regulated by the government, therefore a licensed radio amateur *must* be an integral part of your transmissions. So find yourself one of these hams to help you with the radio end of the control. He may already have a 5-meter transmitter! If you don't know of any amateur in your vicinity, write to the American Radio Relay League, West Hartford, Conn., for the name of the secretary of the local radio club. This contact should enable you to locate a dandy, interested amateur.

Remember, there is plenty of work and two fellows are a minimum. Some are working on R. C. as a club project.

The next and final installment will give in detail the operation and flying of a radio-control model. This includes necessary ground tests, plane adjustments, maneuvers, precautions and, yes—a few tales.

Radio parts can be obtained at: Rissi Brothers, Inc., 443 S. Division, Grand Rapids, Mich., or 5027-31 Hamilton Ave., Detroit, Mich; Allied Radio Corporation, 883 W. Jackson Blvd., Chicago, Ill.; Radio Wire Television, Inc., 901-911 W. Jackson Blvd., Chicago, Ill.; Burstein-Applebee Co., 1012-14 McGee St., Kansas City, Mo.

All these companies have free catalogues.

TO BE CONCLUDED.

Break Formation!

(Continued from page 15)

Time of stations (in plane cockpits), taxi-out, and take-off.

Assembly (place, time, altitude, and formation. If more than one squadron is to participate, "assembly" will mean rendezvous point where the squadrons join up).

Rally (reorganization of elements and flights following withdrawal from the combat, type of formation).

Landing instructions (designation of airdrome, and the order in which elements come in for landings).

Ammunition (type, such as ball, armor-piercing, incendiary, or explosive, amount of ammo. Bomb loadings, if any, will include type and fuse settings).

Special measures for ground defense.

Supplied this data, the pilots have a pretty fair idea of just what is to be done. Now our squadron taxies out for the take-off. According to circumstances, or the commander's dyspepsia, the planes may be ordered to take off individually, by three elements, or by flights. The commander's element slows up, at the assembly point, and the others catch up and fall in formation. (If other squadrons are participating, they, too, fall in their respective positions at this point.) Our force is "supporting" certain friendly operations and pursuit opposition is expected momentarily, so a combat formation is employed.

Each of the three three-element flights is flying an echelon of V's, and each of these patterns is, in turn, echeloned backward and to the left, each 1,000 feet above and behind the other. The lower, or guiding, flight is called the "assault echelon," and this unit tangles with the enemy craft first. The second flight, 1,000 feet up, is the "support echelon," and this group of nine planes drops down to support the leading group immediately upon contact with the enemy. Highest in the squadron formation flies the third flight, or "reserve echelon," whose duty it is to reconnoiter above until it is apparent that no enemy craft are lurking above, then the echelon dives to pick off stragglers or disorganize enemy pursuits. Clever? When the three-squadron group is awing, it comprises a chain of these assault, support, and reserve echelons; the latter flying very high—15,000 to 30,000 feet—so that the enemy cannot attack without being completely sandwiched.

Planes do not just go up and fight, but follow definite routine which consists of four phases. First of these is the approach. Immediately upon sight of the enemy, our squadron enacts this all-important phase which has to do with the most effective direction of approach and the best disposition for concentration of fire power—the manner in which the forces "spar off." Second is the *combat*. Put very briefly, the tangle is a duel in which pilots fence—maneuver—for an opening, then drive home the vital thrust.

Above the roar and heat of battle, the smell of burnt powder and oil, the sight of flames and blood and horrible collision, the emotional stress of fear and anger and uncertainty, the physical reaction to 5-G verticals, rolls, and dives, and perhaps the pain of wounds—the pilot must keep the four axiomatic combat principles foremost in his tortured mind:

1. Surprise—in order to strike *first* by taking advantage of sun, clouds, or other conditions of visibility. And, after engaging the enemy, to further surprise him by attacking from within his blind angle, or taking advantage of his "preoccupation" and catching him unawares.

2. Offensive—in that one must seek to be the aggressor; attacking and *following up* all thrusts in a determined manner. If placed on the defensive, the pilot must strive to outmaneuver the enemy and regain the offensive as *soon*—seconds count—as possible.

3. Concentration of effort—wherein fire power must be directed to the most vulnerable parts of the adversary's ship—pilot, fuel tanks, or controls, in that order. (It would seem to the author that, with the advent of successful leakproof fuel tanks, the order might be changed. When using incendiary ammo, however, a tank can be set afire after it is half empty—leakproof or no.)

4. Security—in that one must not take undue risks. One must watch the sky as well as enemy; particularly the sky above. Don't sacrifice—or be tricked into surrendering—superior altitude, for top man is usually best man. Don't fly *straight at* the enemy when within range of his fire power, unless actually firing at him. Don't fly or dive *straight away* from him when withdrawing from close combat.

Of course, it is difficult to remember these under physical and psychological stress, but this is a part of indoctrination—so to inculcate these principles that the pilot reacts to them subconsciously, as a matter of *habit* and training. The enemy, meanwhile, is applying them, too; all of which makes combat plenty tough.

The third phase is *exploitation*, which follows the shock of attack if the enemy is at a disadvantage. This is carried out in a determined manner until the enemy is destroyed, or has eluded pursuit: a military way of saying, "Get him down and don't hesitate to kick him while he's down!" There is no more "sportsmanship" in do-or-die combat affairs.

The *withdrawal* is the final phase. This is conducted in a precise, orderly manner upon some prearranged plan or radio signal. Now the squadron reforms and carries out the "rally," then heads home in the formation, et cetera, prescribed by the combat orders. Neither gas nor ammo last long in pursuits powered by 1,000 h.p. motors and having four or more 1,200-round-per-minute machine guns.

Formation fighting—it should be obvious without going into the discussion of the technique—sounds thrilling in fiction, but has yet to be made practical for fighters and pursuits. Interceptors, which engage, for the most part, in hit-and-run tactics, can and do employ certain formation attacks, but even these are limited. Pursuits, because they are more maneuverable than interceptors and are therefore employed for close-in fighting, cannot maintain formation after the enemy is engaged. Sooner or later they all break up; when that occurs, the *individual's* ability to perform aerobatics, shoot accurately, and think for himself determines whether or not he shall survive—figuratively speaking. The outcome of combat also is dictated by the pilot's mental attitude (morale and experience) and circumstances, or "breaks." Today's air warrior fights on his *own* initiative and not that of his squadron commander!

Today, they're all aces. The staffs seated around their respective tables are playing for the highest stakes in history. Playing with their cards close to their chests. They've aces back to back on the board, and aces wing to wing in the blood-red sky.

Boy! What a Scoop!

A Class "B" MOTOR for $3.95 Postpaid

Knocked down with plan & instructions

Motor can be assembled and ready to run in 30 minutes

LAPPED PISTON & CYLINDER

COUNTER BALANCED CRANKSHAFT Fully Machined

COMMUTATOR TYPE TIME (No points to adjust)

Entire motor made of Aluminum alloy for lightness and strength

Champion Spark Plug **All for $3.95**

This motor is designed thruout to give the maximum performance. Test motor was run 200 hours continuously without changing anything but the spark plug.

Be the first to have this record breaker. This is the best buy of the year. Send for it now, IMMEDIATE DELIVERY.

BOMBS and TORPEDOES

13/16" ..2 for 5c
1¾" 5c

DEMOLITION BOMBS
15/16" ..2 for 5c
1¾" 5c

FRAGMENTATION BOMB
1¾" 5c

TORPEDO
3" 15c

Dummy Motors
1" 9 Cylinder 15c
1½" 9 Cylinder 25c

Celluloid Motor Plate

1½"	9c	5c
2"	12c	5c
2½"	14c	
3"	17c	5c

PURSUIT GUNS
¾" .....2 for 5c
1" 3c
1½" 5c

Browning Guns
¾" .....2 for 5c
1¼" 3c
1¾" 8c

LEWIS GUNS
¾" .....2 for 5c
1¼" 3c
1¾" 5c
2" 8c

Dummy Ratchet Gun
¾" long 5c

MARLIN GUNS
1½" 5c
2" 10c

SPANDAU GUN
1¾" 5c

VICKERS GUN
1¾" 5c

Anti Aircraft Gun
2" 25c

Ring Mount Guns
1¾" Type A 25c

Swivel Type C
2" d'ble action 8c

WING & TAIL LIGHTS

3 to Set	Set
Small	9c
Medium	12c
Large	15c

IMPORTANT—Minimum order, 50c. Add postage on all items but if over 15c on less than $1.50 order add only 15c. Orders over $1.50 add 10%; west of Denver 15%.

SELLEY MFG. CO., Inc. Dept. 412
1377 Gates Avenue, Brooklyn, N. Y.

HAVE YOUR OWN STATIONERY—

100 LETTERHEADS AND ENVELOPES $1.00

PRINTED WITH YOUR NAME AND ADDRESS — LIMIT 3 LINES — PRINT COPY—SATISFACTION GUARANTEED 25c WITH ORDER—BALANCE C.O.D.

Letterheads on Whippet Bond — a Hammermill paper—Windsor Envelopes

JOHN DEVINE
Box 613, Vinita, Oklahoma

CHAMPIONS SAY

Dear Sir:
I am writing to congratulate you on your fine product. I have found by actual flight test that your propeller gives thrust far in excess of any I have used previously. I have placed high in several meets already this summer among which were the Beloit meet, the Milwaukee meet, La Fayette, and the Nationals.

Yours truly,
(signed) HOWARD HECKENDORF
CHICAGO, ILLINOIS

FLO-TORQUE PROPELLERS
3150 CLYBOURN AVE. CHICAGO, ILL.

Model Matters

(Continued from page 25)

scaled down a typical transport in current use to a true flying scale model.

	Full Scale	Model
Span	85 ft.	6 ft.
Weight	18,500 lbs.	6.5 lbs.
Wing loading	19.4 lbs./sq. ft.	1.37 lbs./sq. ft.
Power	1,420 h.p.	1.33 h.p.
Power loading	12.8 lbs./h.p.	49 lbs./h.p.

Possibly the business of building and flying a gas model would become a more scientific and exacting task if we confined our designs within the limits set up by scaling down full-size airplanes.

Marvin K. Wallach of University City, Mo., sent a time-worn clipping from an October, 1933, magazine. It showed a photo with description of Maxwell Bassett's gas model which had just won the New York City Nationals. Marvin was somewhat upset by the technical description of the motor. Here it is: "The small mouse-power motor is stream driven, developing $^1/_{10}$ h.p. for a sustained flight of several hours. A compressed-air tube feeding into a gas burner heats the boiler, which is shielded against the wind currents." This is the way they described a Brown Jr. motor back in 1933. (The magazine was not a model magazine but a semi-technical publication that certainly should have known better.)

Builders are not particularly happy when their pride and joy soars out of sight. It's financially discouraging to see your investment take wings and disappear. But what really burns up the boys is having their models stolen. F. E. Pepin of Rock Island, Ill., is a builder who is really burned. His Denny (#2,000)-powered Guff was stolen after its first official flight at the Ottumwa, Iowa, contest July 28th. He gave his Ohlsson "23" (#8,947) to a fellow club member and this ship was lost on its first flight. Karl Girten of Milwaukee was fortunate in recovering his through a dealer in Des Moines. Another builder had to wrestle with two rascals whom he caught stealing his. One ship was stolen from the processing tent after it had been returned there. Several others were misplaced. In general it was the sort of day that makes a manufacturer happy. If anyone comes across motors with the above-mentioned pedigrees, restore Pepin to his normal happy self and tell him about them.

"Don't let that 'grand-champion' title fool you; I was lucky"—so says John T. Dilly of Galt, Ontario, when asked about his winning this title at the Canadian National meet in Toronto. It's one of the summer's big meets and attracted about 250 entrants from Canada and the United States. Whether he admits it or not, John is probably tickled pink since he's been itching for such a victory since way back. He's too good a builder and has followed this crazy business too long for bad luck always to haunt him. But we couldn't blame bad luck for liking John, since we, too, think his company is just fine.

The 1940 contest season is over. Now is the time rule changes for 1941 are considered. There's no strong feeling for changes other than an indication that fifteen-second motor run would be preferred to the present twenty-second. Virginia Model Association has been promoting a new rule based on power-flight to total-flight ratio with the duration of the motor run left up to the individual builder. While this rule has worked out nicely in State and sectional meets, many feel it has yet to pass the test in a large-scale contest where any additional bookkeeping is troublesome.

The Air Cadet Corps is planning nationwide expansion. Originated in Chicago and sponsored by the *Times*, membership has grown to 40,000 in this city alone. Maurice Roddy, aviation editor of the *Times*, has nursed the idea from the beginning and will handle the national organization. Activities will operate through twenty-some newspapers throughout the country with the interest divided between large and model planes. Roddy has always done right by the builders, his efforts reaching a new high at the last national meet where he went to bat for the youngsters regardless of how unreasonable the request. The A.C.C. is the largest group in the country affiliated with the A.M.A.

Contest model builders are probably all crazy. But they represent the frame of mind you are certain to fall into if you get at all serious in this business of building models. So, unless an organization can get along with the contest builder, it's unlikely it will go far past attracting the coupon-clipping youngsters who join every organization that comes down the pike. Roddy's success with the Chicago group is well founded in this respect and it's pleasing to see the A.C.C. expand.

The boys in Little Rock, Ark., financed their third annual meet September 1st by selling gas model wing space to advertisers. About a dozen ads were sold at five dollars per. As the models climbed over the crowd the announcer would give the advertiser a plug over the public-address system. One advertisement was traded for the wooden runways and another paid for the P.-A. system. The flying field rent was traded off for the refreshment concession and the ten-cents-per-car admission fees. The arrangements left everyone happy, including the club treasurer, who reported the club bank still jingled even after the last bill had been paid.

Memphis gang took first in Class B and C, which embarrassed the Little Rock boys. But they were so busy working out the details of the meet, they didn't have much time for actual flying. Anyone who doesn't win with this as the reason is gracefully excused.

ON THE FIELD. (By Carroll Moon.) Out in good old California, land of ready-made and ever-present thermals, one of the biggest gas events of the year is the Second Annual Gas Model Contest, staged by the Midget Air Race Association of Los Angeles. It was held August 26th this year. Frank Knapton, manager and head of the airport, conducted the meet and arranged for the awards; he had some job on his hands judging by the

KNOW THE LATEST ADVANCES IN AVIATION!

A COMPLETE

PICTORIAL and TEXTUAL

SURVEY of AVIATION TODAY!

Now through this comprehensive volume which was prepared with the cooperation of the Army, Navy and the principal airlines and manufacturers, it is possible for you to see and learn how the latest planes are designed and manufactured. Great plants are described, and in them you see each of the many steps in plane construction. The many activities of airports, ground schools, Army and Navy training schools, etc. are vividly described. The latest commercial and private planes are pictured. Military aviation is covered fully: pursuit ships, dive bombers, trainers, attack planes and other sky fighters are shown in action and on the ground.

There is no other volume that can compare in scope and in clarity with this all-inclusive book. *It is required reading for every aeronautical enthusiast!*

More than 300 illustrations. $2.00

HOW TO BE AN AVIATOR

As a Hobby or as a Profession

By DICK MERRILL

Captain and Ace Pilot, Eastern Airlines

Everything you need to do and know. Schools, requirements, specializations, designing, etc. Over 100 pictures shows steps in training, new planes, instruments, etc. Foreword by Eddie Rickenbacker.

"A book which every boy who has ambitions to follow a career in aviation can read with great benefit."—Journal of Aeronautical Sciences.

Revised edition, illustrated $2.00

FIVE DAY FREE TRIAL

TEAR OUT THIS COUPON AND MAIL TO

Robert M. McBride & Co. AT—DEC.
116 East 16th St., N. Y. C.

Please send me at once the books checked below. When books are received I will pay the postman price plus a few cents postage. If cash is included with order add 10c per book for shipping charges.

☐ Young America's Aviation Annual: 1940-41. $2.00
☐ How to Be an Aviator. $2.00

I enclose $.....

Name.....

Address.....

City..... State.....

fact that there were 282 entries in the three classes. One hundred seventy-four fliers entered in Class C, eighty-eight in Class B and twenty in Class A.

A Zipper (powered by a Bunch Tiger) took the top honor of the day, turning in one flight of 24:32, top single-flight performance of the meet. Frank Cummings, who flew the plane, worked twenty-three hours straight to finish the ship, and the seventy-five-dollar cash award and trophy were well worth it.

The same association held a night precision contest on August 24th, ships being judged by a committee. The ships were required to have lights built in. Further points were awarded for flight characteristics, and precision flying paid big dividends. John E. Brodbeck won this event. Hans Wall was second, with Willard Strange third. Howard Broughton reported the meet for Air Trails. Bill Butler is president of the Southern California Gas Model Association, and one of the biggest supporters is Dan Bunch, of Bunch Motors.

The Canadian Nationals of 1940, held on August 26th and 27th in Toronto, in conjunction with the Canadian National Exhibition, set a new high in enthusiasm despite the fact that many prominent Canadian modelers are now members of the R.A.F. The 1940 Canadian Nationals was the tenth held to date and was the largest ever conducted in Canada. Nearly 300 contestants were registered, coming from all parts of Canada and the United States. The Canadian National Exhibition has been an active sponsor for the past seven years, and was of great help in making the meet the success that it was.

National emergency deprived the modelers of the use of planned facilities, and indoor flying was transferred to the Maple Leaf Gardens, where effective ceiling was from 55 to 100 feet, with a maximum of 140 feet. Joe Matulis of Chicago set a new Canadian high mark in the adult indoor stick, turning in 15:29. Lawrence Mark set a new high in junior indoor stick with 12:14, while Dave Rosenberg established a new semi-scale record of 3:14.

Outdoor events were held at the airport of the Toronto Flying Club on August 27th and weather conditions were none too good, judged by any standard. With a temperature of 70°, and a wind velocity of 24 m.p.h., fliers just "did their best." High time of the day was turned in by Bob Dodd's gas job with 7:51, which helped to win him top honors in the senior-junior event. Fred Smith, of Buffalo, won the open gas event with 3:19. In rubber, Fred Bowers (of the 1939 Canadian Wakefield Team) was top flier with a first in stick of 7:19. In the Wakefield Class, Jim Broderick of Chicago averaged 3:10, followed by Roy Nelder (Moffett Trophy winner twice) taking second. Other winners were: junior stick—Brenton Rowe; senior stick—Roy Thomason; open stick—Jim Bohash, first.

Contestants were guests of the president and directors of the C.N.E., on the final evening at a banquet in the dining hall of the Administration Building of the Fair. "Most Active Girl Contestant" award was given to Dorothy Templeton of Toronto, and John T. Dilly of Galt, Ont., was declared the Grand Champion of the meet.

One of the largest gas model meets to be held recently in the Eastern part of the country was the Second Annual Sky-scrapers Gas Model Meet at Creedmore, L. I., on September 22nd.

The day was clear, but a twenty-mile-an-hour wind kept flying times down considerably, none of the contestants establishing new records. Top prize winner of the day was Frank Mesa, of the Manhattan Airscrews, who turned in the high single flight of the day—7:05, and the high average of 2:37 with his Class C original design. His ship was powered with a Brown motor. The performance won Frank the International Balsa Trophy, for the high flight, the Skyscraper's Trophy for first in Class C, a Super-cyclone motor and a kit.

Class B flight times were the lowest in the meet. Ernest Roff, of the Gas Monkeys, took first in the class with a nice average of 2:36, and a high flight of 6:50. His plane, powered by a Torpedo motor, was an H. & F. Bee. In Class A, Fran McElwee, of the Linden Model Aëro Club, was first with an average of 2:41.7 and high single flight of 5:27. In keeping with the rest of the first six winners, Fran used a Bantam motor. Miss Wilma Clemons, of Brooklyn, won the Ladies Trophy, flying a Bantam-powered Bay Ridge Mike to ninth place in Class A. Her ship averaged 1:19.4 with a high flight of 1:40.

New York police estimated that at the height of the meet, nearly 10,000 people were in attendance. All timing, checking, policing and general supervision duties were handled very capably by the Sky-scrapers.

Once a year, amid loud cheers, faint hisses and many side remarks, the Scripps-Howard organization (newspapers, y'know) sponsors the Junior Air Races at Akron, O. This year's races were held August 29th, 30th and 31st, and once again the Cleveland

Photo Credit List

The following list shows the sources from which credited photos were obtained. Abbreviations: Bot., bottom; T., top; U.L., upper left; U.R., upper right; L.C., left center; R.C., right center; L.L., lower left; L.R., lower right; Cen., center; T.C., top center; B.C., bottom center.

Page 8—T.R., William Larkins; T.L., Rudy Arnold; Cent., Wide World; Bot., Rudy Arnold.
Page 9—All by Rudy Arnold.
Page 10-11—All by Rudy Arnold.
Page 12—Cent., U. S. army air corps photo.
Page 14—T., official U. S. army air corps photo; Bot., International.
Page 15—T.R., Rudy Arnold; Bot.L., U. S. army air corps photo; Bot.R., Hans Groenhoff.
Page 16—T.L., Rudy Arnold; T.R., Hans Groenhoff; Cent., both by Hans Groenhoff; Bot.L., Stinson; Bot.R., Hans Groenhoff.
Page 17—T., Aeronca; Bot., Hans Groenhoff.
Page 18—All by Clyde H. Sunderland.
Page 20—T. Cent., Hans Groenhoff; Cent., Hans Groenhoff; Bot., Hans Groenhoff.
Page 21—All photos by U. S. army air corps.
Page 23—All by Three Lions.
Page 24—T.R., Kulick; Cent.T., Kulick; Cent.Bot., Kulick; Bot.L., Moon; Bot.R., Kulick.
Page 25—T.L., Kulick; T.R., Kulick; Cent.T., Kulick; Cent.Bot., Kulick; Bot., two left and right, Kulick.
Page 26—L.Cent., Al Daraghy; Bot., Al Daraghy.
Page 27—T., Kulick; Bot., Al Daraghy.
Page 35—T., Acme.
Page 38—Al Daraghy.

● Be the pilot of a new 1941 Harley-Davidson motorcycle and get all the thrills of the sky-ways without the big investment and upkeep. Your "ship" is a racy, streamlined beauty bristling with zooming power and rugged dependability. See your Harley-Davidson dealer — get the exciting story of the thrills motorcyclists enjoy on club runs — at rallies, hillclimbs, tourist trophy races and other exciting events. Ask about his Easy Pay Plans — and send coupon NOW!

HARLEY-DAVIDSON
WORLD'S CHAMPION MOTORCYCLE

Free

Send Coupon NOW

HARLEY-DAVIDSON MOTOR CO.
Dept. AT. Milwaukee, Wisconsin

Send FREE copy of big 24-page "Enthusiast" magazine filled with thrilling pictures and stories. Also literature on the new 1941 Harley-Davidsons. Stamp is enclosed for mailing.

Name

Address

THE BEST — THE SIMPLEST
THE LATEST IN MODELS

Just out—IDEAL'S
New 18" 25c 25" 25c 32" 50c Flying Models

We have the complete line of all IDEAL Kits & Supplies.

ALSO—
H. & F. MODELS
CONTINENTAL
SCIENTIFIC
BERKELEY
CAPITOL
CLEVELAND
AMERICAN JR.
STROMBECKER
BURD
VARNEY
HAWK, ETC.

NO CHARGE FOR DELIVERY IN METROPOLITAN AREA

PLANES • BOATS • RACE CARS • TRAINS • MOTORS

LEHR-O-PLANE
5 E. 3rd STREET N. Y. C.

More Power USE Easier Starts
REVOIL
To Make Your Engine Run Better
HEEBE PRODUCTS CO. Box 841 ROCKFORD ILL

CLASSIFIED DIRECTORY

An opportunity to contact a large field on a small lineage. Rate 10c per word (Minimum 20 words). Cash with order. Address:

AIR TRAILS CLASSIFIED ADVERTISING
79 Seventh Avenue, New York City

AVIATION APPRENTICES—Air-minded Young Men interested in technical training for entering Aviation as Apprentices see Mechanix Universal Service ad page 57.

AVIATION PIN 25¢

PILOTS, STUDENTS, MECHANICS, HOBBYISTS —IDENTIFY YOURSELF WITH AVIATION, BY WEARING THIS HANDSOME GOLD PLATED, WINGS, MOTOR AND PROP PIN....WORTH 45c

Send 25c for the pin and our new catalogue of aviation jewelry, aircraft sketches, books, etc.

CRAFT ART COMPANY DEPT 12A
246 FIFTH AVENUE, NEW YORK, N. Y.

NEW! AMERICAN MADE BAMBOO TISSUE FOR GAS PLANES

APPLY WET or DRY!

Smooth, silklike finish. Easy to apply! Tremendous strength under severest strains and tests. A sensational improvement—without equal! See it at all dealers!

PROPS

Perfectly finished JA-PROPS in a complete range of sizes for every model-flying need. A better prop for less money! Be sure it's WHITFIELD!

MINIATURE CELLULOID MOTORS

New type, stronger! 1⅜", 2", 2½" & 3".

"BRILLIANTISSUE"
EXTRA THIN—EXTRA STRONG

The famous "AA" Japanese, made expressly to our critical standards. In a complete range of every popular shade. Finest for rubber powered models. It's extra thin—extra strong—and recommended by your dealer! For your very next model—improve its appearance and performance with BRILLIANTISSUE.

WHITFIELD PAPER WORKS
76 VARICK ST., N. Y. C. Est. 1869

Balsa Butchers (Dick Korda et al) were declared champs.

Of course, there were literally hundreds of entrants, and classes ranged from indoor to outdoor in all sizes. First, however, it behooves us to discuss the gas events. Carl Goldberg, flying a Zipper (honest!) powered by a *secret* (shhhhh) motor in Class C, won the open event with an average of 14:38—not bad time at all. Oh, yes, Walt Good finished thirteenth and Ed Naudzius, who was voted the "outstanding modeler at the meet," took fifteenth. Jack Liendecker took first in the junior-senior gas event, with a 9:45.4 average.

Despite the high times, gas events were not the big moments at the meet. Al Blatter took the junior fuselage event with a 5:34 mark. Owen O'Malley was first in the senior fuselage event, hitting an 8:38 mark. Ted Just (on the 1939 Wakefield Team) finished fifth, just to give you an idea. V. Wallschlager won the open fuselage event. Wallschlager's time was 7:41.4. Oh, yes, Dick Korda (Wakefield champ) finished twelfth —s'too bad.

In the Original Design event, Bruce Halleck was top man. Walt Good (the Guff, remember?) was fifth, and Ed Manning (Lackey Zenith) was twelfth. Carl Chakmakian was first in Flying Scale. Chet Lanzo (an old-timer) was ninth.

Henry Thomas won the speed event hitting 65 m.p.h. Chet Lanzo was eighth in this event. Phil Weatherwax won the towline glider event. Time was 1:13.2. Dick Korda took a sixth here, with Henry Thomas seventh and Chet Lanzo fourteenth, just to show how the mighty finish "waaaaay down." Jerry Wylemski took the junior class stick, turning in 2:08.8. Bob Davis, with 3:10.7, took senior stick. Russell Shaffer was first in open stick, averaging 3:59. Chet Lanzo, who, incidentally, used a gas model timer as part of his ship, took second, and Bill Allsopp third. Dick Korda was fourth again, and Earl Stahl (you've seen his articles, of course) finished fifteenth.

Norm Tyson won top honors in a contest sponsored by the Norristown Flying Wings of Norristown (Pa.) A light rain spoiled the list of entries, but Norm managed to turn in 159.4 seconds for top place. Gerald Paul was second and Bill Paige third. Ken Allerton, who was contest sponsor, was Air Trails correspondent.

The Frank Lahm Cadets Aero Club of Mansfield, O., held a meet September 1st. Harold Heston won the gas event, with an average of 2:05. Carl Ridgway won the rubber event, with a 1:10 average. Ridgway also won the glider event. Gerhart won the tow-line event. Gerhart won the Fox Trophy for high-point score.

Times weren't so high in the gas model meet held in August in Marshall, Mich., but a grand day of flying was reported by the Junior Chamber of Commerce, cosponsor of the meet. Leslie Hard won Class A open with a total of 269 seconds. Ralph Littler won the senior event in Class A with a total of 1,085 seconds. In Class C, open, Carl Thunder piled up 658 seconds to take first. Carl is president of the Marshall Model Club. Wayne Hallack took Class C senior.

Between the "Junior Nationals," the "Nationals" and the "Little Nationals" we're slowly but surely growing nuts. However, they're all big events and it's our duty to report them. The Northern Indiana Gas Model Association of Gary, Ind., sponsored the Little Nationals on September 1st, and reported a success for the third successive year. J. B. Pasko, Jr., president of the club, was Air Trails reporter of the event. Bob Roberts was contest director.

Dick Parker, of Fort Wayne, won Class B gas, with a total of 986.3 seconds, and also took the Grand Award. Chas. Eves was first in Class A. Bob Kreigh took what honors Dick Parker left in Class B, with a 549.6-second total. In Class C, Frank Parmenter, with a 780-second total, was first.

The second annual gas model meet of the Pretzel Gas Model Club of Freeport, Ill., held August 11th, was one of the big events of the Middle West during the month. Due to rain the number of contestants was limited, but flight times were good and prizes were even better.

E. Tschernoscha took first in Class C with a time of 566 seconds. Joe Konefes (remember the Buzzard Bombshell?) was ninth and his brother, Ed, was tenth. In Class B, Ralph Muchow turned in a time of 805 seconds for first. John Conusy took first in Class A, with 499 seconds. Contest director was Nolan Kleckner, while Don Whalen, secretary of the club, reported the meet. Thanks, Don—how about a report covering motors used next time?

The Louisville Junior Board of Trade, in co-operation with the Louisville Model Club, held a contest on August 25th, according to Addison Yeaman, chairman of the aviation committee. Gas models were entered in one class (ah, the pity of such things) and E. A. Cheek won first with an average of 2:42. We don't know the plane, class or motor, but Cheek averaged 2:42, which won him cash, trophy and motor. B. Graham won the fuselage model event with a 2:26 average. C. J. Cooper, Jr., won the junior fuselage. Carter also took senior stick with a 2:41 average. Junior stick was taken by Alexander with a 59-second average. Barney Cowherd took the glider event, aver-

Organize A Model Club!

Send this coupon for booklet

AIR TRAILS

79 Seventh Avenue — Dept. D-Q
New York, N. Y.

Inclosed, please find 10c for my booklet on How to Organize a Model Plane Club.

Name.....

Address.....

City.....

State.....

TOP HONORS FOR THE H.& F. "BEE"

FLASH: An H.&F. Bee, built and flown by Ernest Roff took first in Class B at Sky-Scraper's gas contest Sept. 22. Best flight—6:50, average 2:36. Ship weighed 30 ounces BUT was sensation of the day.



FIRST on every Christmas list . . . the H.&F. Bee, a gas model that will make any builder sit up and take notice. Designed to win in beauty and flying events.

For either Class B or A events. 48 inch span, weight 19 ounces with Ohlsson 23 motor. Semi-monocoque fuselage, easy to build but strong and rugged for any type of flying. *Motor inverted or upright.* Kit comes complete with all wood, clean printed sheets, cement, dope, Silkette covering material. A real ship for all builders. (Add 20c postage if ordered direct) **$1.95**

Motors for the "BEE"

(In stock for immediate delivery)

Forster 29	$15.50
Ohlsson 23	16.50
Ohlsson 19	14.50
Bantam	16.50
Syncro B-30	6.95
Madewell Mite	7.50

JOBBERS—DEALERS—DISTRIBUTORS

Write on letterhead for prices and discounts on H.&F. 10c, 25c, 50c, $1.00 and gas kits. Entire line redesigned to meet 1940 demands. Fastest selling line in country today. An immediate order will insure shipment in time for the holiday rush.

Modern 50" Flyer

Ryan St

Specified by U. S. Government for giant air training program. Super detail kit with aluminum prop spinner, cut balsa wheel pants, full size plans, printed sheets, die stamped landing gear, contest rubber, tissue paper, cement, dope, wood, balsa prop, etc. **$1.00**

Howard DGA-9, includes spun aluminum cowl in addition to above. Stinson 105 many extras. All 50" wingspan.

(15c postage when ordered direct)

H. & F. MODEL AIRPLANE CO.

299 Van Sinderen Ave. — Brooklyn, N. Y.

AU ACCREDITED

Careers In Aviation For A. U. Graduates

Things are humming in every branch of the aviation industry. Men are working day and night. Trained men are needed . . . especially skilled engineers and aircraftsmen.

Were you trained NOW, you would have little difficulty landing a job. But it is not too late. Activity in aviation will continue for years.

Get your training at AERONAUTICAL UNIVERSITY. Build for yourself a career in aviation as multitudes of our graduates have. The practical, thorough, time tested training you get here is endorsed by the aviation industry. They reward such training with jobs, advancement, real opportunity.

MAIL COUPON

for free illustrated bulletin telling more about your opportunities in aviation and giving full particulars about our career courses in AERONAUTICAL ENGINEERING, CERTIFIED MECHANICS, ADMINISTRATION.

Aeronautical University
(Founded by Curtiss-Wright)
CURTISS-WRIGHT BLDG.
Dept. B, 1338 S. Michigan Blvd.
Chicago, Illinois

Aeronautical University (B)
(Founded by Curtiss-Wright)
Curtiss-Wright Bldg., 1338 S. Michigan Blvd.
Chicago, Ill.

Send me FREE illustrated bulletin.

Name .....
Street .....
City..... State.....
Age.....
Career that interests me.....

WING SPAN 40" LENGTH 30"
WING AREA 200 Sq. In. WEIGHT 6.14 Oz.
RATE OF CLIMB 1450 FT. PER MIN.
GLIDE RATIO 13 TO 1

Finished — Wing Ribs, Saw Cut, Not Die Cut.
Finished — Wing Spars, Cut to Length and Tapered.
Finished — Leading and Trailing Edges on Wing.
Finished — Nose Plug Assembly Parts.
Finished — Landing Gear Formed from Hard Music Wire.
New — Balsa Shells, Tapered and Shaped, Finish off Nose of Ship, instead of Tricky Former Work. Easy to Cover.

BOYS! GIVE YOURSELF A CHRISTMAS GIFT!

100% COMPLETE

Choose the model that will put you in line with the experts. This ship is basically designed to hang over the field (and not on a string either).

This plane has flown **2 HRS. 20 MIN.** in official contest flight in sight over the field.

New — "Sure-Lock" Removable Nose Assembly; Allows Winding With A Hand-Winder: Result—Longer Flights.
Giant Plan 35"x45" Showing Step by Step Operations, with Perspective Views of Each Detail.
Ball Bearing Washer.
Two Sizes of Fresh Brown Contest Rubber.
Movable Wing and Rudder for Perfect Flight Control.
Streamlined wheels, dope, cement, tissue, balsa, etc., etc.

$1.75 POSTPAID OR AT YOUR DEALER.

YOU'VE TRIED THE REST—NOW FLY THE BEST!

BOYS—send 3c stamp for free list on contest items ——— Dealers—Distributors—get wise!

BEST BY TEST MODEL CO.

175 - T Main St. — Ridgefield Park, N. J.

aging 1:28. Fred Harwood won the speed event. In the gas event, H. Bonner, who finished tenth, turned in the best single flight—6:12.

Although previously unheralded, southern New York State is becoming a mecca for gas modelers, according to our reporters, who state (with pardonable pride) that the Tri-cities Gas Model Meet, held in Endicott, N. Y., early in September was one of the biggest and best ever held in the locality. Five thousand spectators and more than 150 entrants also acclaimed the meet as one of the "biggest and best" in history. They (meaning the Endicott Gas Model Club and the Kiwanis Club of Endicott) arranged "everything," including bleachers for the spectators (at last) and two parachute jumps (not by disgruntled contestants).

Times were moderate, although eight ships were lost in the rubber events. Four models landed in the river, but the committee had provided an outboard outfit for just such an emergency.

New clubs reported: Prop Spinners in Jamaica, L. I., and Gas Gulls of Brooklyn, N. Y. Good luck to them. We solicit any news from new clubs. Include list of officers, and anything of news value.

One more thing. *Please* report motors used in all gas contests. We think such information is valuable to the field and that it is really news. Also tell whether the time you report is total or average of three flights. Thank you and—see you On the Field.

Navy Pilot Mill

(Continued from page 9)

Your first impression of the NRAB is this: The base is actually a going concern. There are a few dive bombbers (SBC-4s), for the training of former Pensacola graduates on two-week active-duty periods—to which *you* may return some day. There are six—soon to be many times that number—of navy-built yellow trainers called N3N's. There are older Grumman Scouts, also flown by reserve aviators, a Grumman JF-2 amphibian, and a scout-trainer built by North American.

As each of these planes is overhauled by the NRAB, shop facilities are needed, such as magnafluxes, drills, presses, lathes, magneto stands, and radio equipment. In fact, an airplane can be completely torn down, inspected and reassembled at a naval reserve base—coming back into operation looking and performing like new. By completely torn down is meant the removal of wings, stripping of fabric, realigning, recovering, doping, and reassembling. Of course, the engine is also completely torn down, inspected and assembled.

You are now a part of a growing, expanding organization that is pinch-hitting for Uncle Sam. Consider that in 1935, when the aviation cadet program began, that there were less than four hundred reserve aviators! That this pitiably small number of pilots is now available to train more pilots! That they are needed badly because the regular navy is no longer in a position to furnish aviators for its airplanes—indeed, if the entire output of the Naval Academy at Annapolis were utilized there would still be a dearth of pilots. As a high-ranking naval officer said recently, "The air arm of the navy is becoming so important that as far as the United States fleet and aviation is concerned, it will soon become a case of the tail wagging the dog."

When training starts, you climb into the back seat (soon to become the rear cockpit!) with a pair of speaking tubes called gosports attached to your helmet. Two brother students wind the inertia starter—you'll do it for them in the afternoon—and the prop spins.

At first, your flying seems strenuous; the reserve instructor, who went through the training just as you go through it, demands accuracy, precision, and aptitude for military flying. You must do things right the first time, or at least profit by your mistakes. If you do not, it is to everyone's interests that training be stopped early in the game before you stop it involuntarily.

Of course, you may not be started on simple maneuvers if you are an advanced student in the C. A. A. pro-

THIS MOTOR WINS PRIZES!

$7.50
Complete
Ready to Run

BROWNIE MODEL "F" $7.50 complete ready to run. Brownie is equipped with the finest ignition unit it has been possible to produce—a *multiple* spring *aviation* timer. The cam is made of coined steel—hardened and tough! The multiple spring is of finest pre-tempered Swedish spring steel—*there is no finer obtainable!* This new timer has been developed exclusively for model aircraft, and operates with equal efficiency whether at 1000 or 10,000 R.P.M.

JUNIOR MOTORS CORP.
2545 N. Broad Street
Philadelphia, Pa.

THIRD SUCCESSFUL YEAR

The Leading Aviation Annual in America

● Particularly designed for students of aviation, those in the industry and everyone interested in aviation.

CONTAINS:
65 SEPARATE AVIATION FEATURES
all prepared by well-known authorities.

8 FULL-COLOR PHOTOGRAPHS (size 8½ x 11½") OF THE LATEST MILITARY AND COMMERCIAL AIRPLANES, printed on a special heavy paper, ready for framing, worth the price of the book many times over.

29 PICTORIAL FEATURES SHOWING HUNDREDS OF EXCLUSIVE PHOTOGRAPHS.

8 ARTICLES ON MODERN AVIATION BY NATIONALLY KNOWN EXPERTS.

10 THREE-VIEW DRAWINGS OF MODERN FIGHTING PLANES LIKE THOSE PUBLISHED IN JANES.

FEATURE ARTICLE ON "AVIATION AND EDUCATION" by JOHN W. STUDEBAKER, U. S. COMMISSIONER OF EDUCATION.

CLOUD CHART, ANATOMY OF A SUMMER STORM AND A CHART ON CLOUD ANATOMY. THESE THREE CHARTS HAVE BEEN CALLED THE MOST ACCURATE IN AMERICA.

DOUBLE PAGE MAP OF U. S. AIRLINES—THE MOST COMPLETE EVER PUBLISHED.

As a technical reference book for schools and library, as well as fascinating, valuable aid for the student, this AIR TRAILS ANNUAL is approved by the nation's leading experts in aviation and educators.

A limited supply has been printed, so if your news dealer cannot supply you, order your copy today (using the coupon at left).

AIR PROGRESS, 79 Seventh Avenue, New York City

Inclosed is 25 cents (30 cents for Canada). Kindly mail me a copy of AIR PROGRESS postage FREE.

NAME..... ADDRESS.....

CITY..... STATE.....

Model Airplane Contests

An Air Youth Guide with Official Rules

WOULD you like to conduct your own model airplane contests, see your plane in competition with the other fellows? Then here is a book you should read, for it covers thoroughly all the information you need; cost, sites, equipment, types of contests, etc. It's the ideal guide for every boy, girl or adult whose hobby is model airplane flying. Foreword by Winthrop Rockefeller. Charts and diagrams. $1.25

At All Booksellers

D. APPLETON-CENTURY CO., 35 W. 32nd St., N. Y.

AVIATION APPRENTICES

Airminded young men interested in technical training for entering the well paid field of aviation as apprentices. Write immediately, enclosing stamp.

MECHANIX UNIVERSAL AVIATION SERVICE CO.
Wayne County Airport, Dept. T., Detroit, Mich.

INTERCEPTORS UP!

by

John R. Hoyt,

in the

January AIR TRAILS

Brings you the thrill of interceptor fighting.

CANADIANS

Send for our latest lists of low priced model airplane supplies, kits, Gas engines, Ships, H. O. gauge Railway equipment. Comet, Megow and Scientific lines.

ST. JOHN MODEL SHOP

649 Portage Ave. Dept. B. Winnipeg, Manitoba

MRL QUALITY
RUBBER AND SUPPLIES

MRL CHAMPION BROWN RUBBER

1/32"—20 ft. 5c—225 ft. 25c	7/64"—10 ft. 5c—225 ft. 60c
3/64"—20 ft. 5c—225 ft. 30c	1/8" —10 ft. 5c—225 ft. 70c
1/16"—15 ft. 5c—225 ft. 35c	5/32"—15 ft. 10c—225 ft. 85c
5/64"—15 ft. 5c—225 ft. 40c	3/16"—15 ft. 10c—225 ft. 95c
3/32"—15 ft. 5c—225 ft. 50c	1/4"—10 ft. 10c—225 ft. 1.20

GAS ENGINES

We carry in stock at all times the latest models of the following makes of motors: Ohlsson, Brown, Dennymite, Atom, Herkimer OK, and Syncro "B30." Prompt Delivery At Standard Prices.

DEALERS

Write on letterhead for confidential price list on GENUINE MRL CHAMPION BROWN RUBBER at regular trade discount. Also all special model supplies.

MODEL RESEARCH LAB
3531-T North Western Ave. Chicago Ill.

gram, but for the most part navy students receive ten hours in fundamentals such as level flight, medium turns, glides, landings, and take-offs. Under present schedules the time required for each student prior to solo is ten hours, and it takes about a month to fly that amount. Before solo the navy's method requires that you pass a flight check with another pilot, also a reserve aviator. The importance of this "check" worries students—maybe you are the type that becomes very nervous on check rides, getting what is called "checkitus," and therefore flying with less skill than you usually fly. But don't worry about it—almost everyone is subject to such nervousness, and almost everyone passes.

During the check you bank, turn, glide, and land. If you held your altitude around the field, seemed to be safe during the simulated engine failure, and made a few good landings, the reserve lieutenant will say, "It's an up," which, translated from navy parlance, means, "The flight test was satisfactory."

Then comes your first solo—you make one trip up and around the field. Be careful of the bombing target on the tip of the island—the SBC's are practicing and at intervals a bomb comes whistling down from a roaring SBC-4! Come in for the landing, banking the yellow wings of the sturdy N3N trainer; the speaking tubes are silent, and the front cockpit is very empty. The ground comes up—and you are on, taxiing to a stop.

First solo? Well then, into the drink with you. The first solo is always honored by a ducking—that's an old navy tradition. Or if there's no [illegible] tossed by your envious classmates will cool your fevered brow!

Next will come your appointment as an aviation cadet, then about nine months at Pensacola. If you graduate, there will be an ensign's commission (corresponding to the army rank of second lieutenant) for you with three to seven years duty to follow. Or perhaps you'll be selected as one of the fortunate officers to be given commissions in the regular navy, which means that you could make the navy your career.

But a great number will return, in normal times, to civil life, and upon request will be assigned to the nearest NRAB. On Saturdays a navy plane will be available, and for two weeks during the summer there will be an active-duty training period. If such is your inclination, you'll report to the NRAB to which you are attached and get back into the swing of things, trying to keep that feel of the air that was so great a part of you during your years with the fleet.

You'll be part of a reserve squadron. In war time a squadron is an operating unit consisting of eighteen planes, a few spares, and a scouting plane (if a fighter squadron), but at present the reserve squadrons are below strength. There will be the commanding officer, known as the "skipper," an executive officer, and other pilot-officers carrying out the duties of gunnery, operations, materiel, communications, and engineering. The crew, consisting of from thirty to eighty men depending upon conditions, will carry out its duties in its respective departments.

In gunnery, these duties are many. The ammunition must be made into belts, and the tips painted so that each pilot may have an identifying color when (and if!) he hits the target. The targets and line (landlubbers call it "rope") must be in order. The planes must be gassed, scrubbed, and hangared before "Secure" is sounded each night.

Because you must navigate if you're a navy pilot, the mornings will be spent in class. You'll take on a few problems, such as:

Given the aircraft carrier *Lexington* on course 90°, speed 25 knots, wind 15 knots from 30° Problem: Scout a relative sector to the *Lexington*, going out on course 180° relative and returning on course 165° relative. Return to ship at end of four hours. Required: Compass course, actual track, actual miles traveled.

After teasing yourself with that for a while the chief radioman comes in and shoots some mixed code groups to you at fifteen words a minute such as: "LKDMA ZXYPO RSUVK L3JRP C5G7X." After a few minutes of intense concentration it all starts to come back, but about that time you receive a message in plain language to which a reply is asked. You reach for the telegraph key in front of you, trying to send the message as your mind forms it. No spoken words are permitted because you are supposed to be actually flying a plane—perhaps spotting shell splashes in the Pacific!

The last class of the morning is really not a class, but a session in the Link Trainer. After your long lay-off you begin with simple instrument flying, such as level flight, timed turns, harder, until at the end of the two-week cruise you will do an actual problem on a radio range and find the cone of silence, provided that rabbit's foot is still working.

In the meantime the crew has gassed the SBC-4s and towed them to the line. In the gun are sixty rounds of .30-caliber ammunition, with your identifying color, red, marking the steel jacket of each round. You climb in after lunch and follow the white cotton sleeve out on the range, high above Lake Erie and outboard from coastwise shipping. The firing runs will consist of every manner of approach that might be used in combat: from above, below, side, and ahead. The only firing position not used is the one from dead astern, because to fire from that position might embarrass the pilot towing the sleeve.

Once in position, you start your dive, watching the airspeed indicator creep toward 200, and trying to get that dot in the telescope sight to stay on the target. But before you can steady the plane you flash by the sleeve without firing a shot—it takes constant practice to get hits in gunnery. *Could we produce 50,000 military pilots overnight?* You wonder.

The next hop is dive bombing, using small, miniature marker bombs that produce a small puff of white smoke to mark the point of impact. From 5,000 feet you look down at the little 200-foot target on the southern tip of Grosse Ile. It is clear, and there seem to be no little yellow trainers hovering around it; switching the

THIS MOTOR WINS PRIZES!

MODEL "D"
$12.50
Complete
Ready to Run

MODEL "D" $12.50 complete ready to run. This new Brown D Motor gives you more value for your money! Precision-made in the world's largest and most completely-equipped plant devoted to the manufacture of model gas motors. The Model D includes the sound engineering advances used in other Junior Motors. New and improved timer! New chrome molybdenum crankshaft! New micrometer needle-valve! New transparent gas tank! Motor shipped ready-to-run, complete with coil and condenser.

JUNIOR MOTORS CORP.
2545 N. Broad Street
Philadelphia, Pa.

FREE
PARA SHOOTER with NOVA KIT. Also plans, parts for launching with any plane.

NEW TIMELY TRADE MARK

Be the first to demonstrate practical PARACHUTE principles with this unique PARA SHOOTER. "TRU-DETAIL" figure gently sails to earth beneath silk parachute—Can be used with or without plane. If purchased at your dealer PARA SHOOTER complete (nothing to build NOT a kit) only..... **10c**
BY MAIL: 15c if ordered in conjunction with other items. Postage additional.

Kit includes Clark 'Y' ribs completely finished and notched. 10" "proper-pitch" Helical type prop. and finished wheels. Free wheeling prop attachment and shaft. Celluloid round bamboo, celluloid tubing steel wire, assorted. Balsa, cement, dope, brush and SILK FOR WINGS AND FUSELAGE .. **$1** WITH PARA SHOOTER
(West of Mississippi add 12c postage)

7 DIFFERENT CUTTING EDGES & KANTSLIP HOLDER, Complete **50c**
OVER 80,000 NOW IN USE!
England's famous "7-in-1" STUDIETTE. Perfect for modeling, Shop and Craft Work, Stencil and Mat Cutting, Photographers! Single operation for: Tongue and Groove; Channel Notching; Ovaling; T, H, & L Shapes; Rounding; Dovetailing, etc. No other like STUDIETTE. Rust resistant. High carbon acid (Sheffield) steel hand ground and sharpened. Extra blades only, 3 for 25c. (Add 5c postage.)
SPECIAL All purpose STUDIETTE Blade with handle. (5c postage)..... **15c**

5 Pc. Heavy Duty KARVER KIT **50c**
The Amateur's BEST AID for professional craft work.
5 popular shaped steel blades easily sharpened. Set in special design E-Z GRIP Handles (non-rolling ends). Complete set of 5 (Type A-illus.)—only 50c. (by mail, add 5c)
KARVER KIT (Type B) with long blades & handles—Set of 5—50c.
Specify type desired.

40 PAGE HOBBY GUIDE

If you build Model Planes, Boats, Trains or Autos you need a copy of our 1940-41 Hobby Guide & Catalog (10c). Profusely illustrated (over 600 items) contains Valuable Hints, Charts, Diagrams.
Contains 10c Cash Value Coupon

INTERNATIONAL MODEL PRODS. 254 W. 55th STREET (DEPT. AT) NEW YORK

OHLSSON "19"

WHEN IT'S GOT TO BE HOT—



Next to POWER, there is nothing so important as dependability in a motor. Used by *five* of the nine winning Class A contestants at the Nationals, Ohlsson 19 gave plenty of evidence that it delivers when the competition is really tough and you can't afford to have a shaky motor.

Interchangeable with Ohlsson 23 for dual purpose flying. An outstanding value at this price, only.... **$14.50**

NATIONAL CHAMPION

Bill Gibson of Hamilton, Ohio, whose feature article appears elsewhere in this issue, shown with his MODELCRAFT CHAMPIONSHIP TROPHY. Gibson not only took the stiffest event—the Open—but also scored the highest time, 47 min. 32 sec., for Class A.

The WINNERS' CIRCLE

ROBERT LIEBER
NATIONAL CHAMPION
CLASS A JUNIOR EVENT
1940 Nationals
Time: 6 min. 23.8 sec.

NOTE to Modelers: We are sorry that lack of space has prevented printing many outstanding Winners' Circle records recently received. We intend to continue this feature regularly, however, as space permits. Keep mailing in your contest records.

Large New Ohlsson Folder
Now Available—Send Coupon

OHLSSON *and* RICE MFG. CO.

"Compare the Engineering"

OHLSSON & RICE MFG. CO.
P. O. Box 2324, Terminal Annex
Los Angeles, Calif.
Please send new Ohlsson Motors folder.
Name.....
Address.....
City and State.....

gas selector valve to reserve, the prop to high pitch, opening the split diving flaps and closing the throttle to 1,000 r.p.m., you roll over into your dive.

A real 70° dive seems very steep—you are out of the seat, almost standing on the rudder pedals. As the speed picks up you must apply more left rudder than usual, and this tends to move the sight off the target. You estimate the wind, trying to figure your lead, and as the target grows larger in the sight you glance at the "ball" in the turn-bank indicator. It is hard to aim and wait, roaring earthward at high speed, but you reach down for the bomb release lever and hold it until you are at 2,000 feet. After the bomb is dropped, you pull out gradually, assuming level flight at 1,000 feet.

For a minute you are busy closing the split flaps, opening the throttle, decreasing the propeller pitch. The plane roars raucously over the target as you bank and turn to get a look at that white puff from the marker: it goes off just outside the circle A miss—try again!

At the end of the day's duty the two-week "cruise" is well begun. Now the planes must be cleaned, serviced, and hangared. The duty section (or guard) must be mustered at 1800 (6:00 p. m.) and if you are so fortunate as to be the O. O. D. (officer of the day) you can get up between midnight and 0300 (3:00 a. m.) to see that all is well. At 0600 you get up, muster the crew at 0755, and see that operations are started promptly at 0800.

The days roll by, with the old feel of the plane coming back slowly. There will be night flying, of which the average pilot does so little, and before taking off you want to check the plane's instrument panel carefully, noting all switches, rheostats and landing lights.

In the darkness you circle Detroit, watching the long line of lights on Michigan Avenue, with the silhouette of the SBC-4 upon it and the blue-white flames spurting from the twin exhausts beneath the cowling. When the turtleback light flickers the signal, you ease from V over to echelon, wondering if the pilot below you is ducking his head!

Coming in to land, you check your landing list carefully: gas, carburetor, prop, wheels, flaps, cowling—and then when you're all through, do it again. Especially the wheels. At five hundred feet the field lights come on, and at three hundred feet you reach down for the switch you memorized prior to take-off and flip your own landing light on.

The two weeks at the naval reserve aviation base rush by. The students are half through now, the base officers working hard to procure another bunch for training, and the reserve squadron holds its formal inspection. During the next year you will attend drills twice a month and try to retain your proficiency, but you wonder when there will be adequately armed planes for reservists to fly—planes with eight machine guns instead of a single .30 caliber. Planes with pilot armor, planes that will fly faster, planes with modern puncture-proof gas tanks, planes with cannon. It takes time and hours in the air to become familiarized with a new airplane—to say nothing of flying gunnery, bombing, night flying and tactics.

As you put your 'chute away and start packing your gear for the trip home, you notice the paper: "Navy to train pilots. Pilots needed. Great expansion." That's all very well, but what are they going to use for planes—bases—mechanics? You ask yourself: Who is going to teach these kids to fly?

The squadron yeoman slips an envelope into your hand and you open it. The paper in it looks official, but that's nothing new. It probably is more routine. You read:

"Upon receipt of these orders you will proceed to NRAB Detroit (Grosse Ile) for duty . . . as instructor."

One of your questions has been answered.

Lanzo Nationals Stick Winner

(Continued from page 39)

fuselage attach just the main spar, leaving the leading edge free to take turn adjustments. After adjusting the model the rudder may be fastened permanently in place.

Although E is given in full size, it may be necessary to make a second one (larger or smaller) to produce the right amount of turn in the glide. E is necessary if the flight-timer idea is not used. The flight timer does, however, tighten up the circle in the glide, enabling the model to stay in the thermals.

ADJUSTING

The best climb and glide is obtained when the ship flies in circles of 400 feet diameter. Before putting the model into the air fully wound be sure the glide is perfect. In preliminary hand glides the leading edge should be at Station 8. A piece of $1/16$" square under the leading edge of the stabilizer will improve the glide.

Side and downthrust may be adjusted temporarily with thin paper matches. The nose block can be cut away or added to later. Wind the ship three quarters of the full amount of turns on hot days, as the ship will hit thermals at low altitudes. It has climbed out of sight on rubber run alone.

The white rubber rope tensioner is used on the motor and the prop should fold back at about forty turns. Use thirty-two strands of $3/16$" flat brown rubber, 40" long.





AT LAST!

AFTER THREE YEARS DEVELOPMENT WORK BY ORIGINATORS OF PREFABRICATED MODEL AIRPLANE CONSTRUCTION SETS:
SEE FEBRUARY 1940 AIR TRAILS, PAGE 31—
PLANE-CRAFT OFFERS HIGH QUALITY, LOW PRICED SEMI-SCALE GAS AND RUBBER POWERED "PREFAB" SETS READY TO ASEMBLE AS SHOWN ABOVE. UP TO THE MINUTE IN DESIGN. 74 COMPLETED PARTS AND FRAMEWORK UNITS IN GAS SET.

THE PLANE-CRAFT SKYLARK IS THE MOST POPULAR PREFAB RUBBER POWERED SET ON THE MARKET, DUE TO ITS LASTING QUALITIES AND LONG FLIGHTS AS DEMONSTRATED BY HUNDREDS OF WASHINGTON D.C. BOYS WHO HAVE BUILT AND FLOWN THIS FINE MODEL.

- PLANE-CRAFT PRODUCTS -

37" CLASS A GAS MODEL SET 2.95. CLASS B 50" $3.95
22" SKYLARK RUBBER POWERED CONSTRUCTION SET- $1.00
22" SKYLARK PART PREFABRICATED " " .50
ALSO COMPLETED READY TO FLY MODELS-LESS MOTOR-CLASS A GAS MODEL- $9.75. CLASS B GAS MODEL- $11.75
SKYLARK RUBBER POWERED MODEL, READY TO FLY- $2.50

PLANE-CRAFT GLIDERS, READY TO ASSEMBLE- 10¢, 25¢.
A NEW PRODUCT—COMPLETED BALSA PROPELLERS WITH METAL TUBE IN HUB, SIZES—8, 10, AND 12 INCH—2¢ PER INCH.
BUILD TODAY — FLY TOMORROW
SEND STAMP FOR LITERATURE
PLANE-CRAFT, 4017 CHESAPEAKE ST. WASHINGTON, D.C.

HODGMAN *Aero* RUBBER

For Power—Speed—Endurance—PROFIT. An extra fine quality backed by over 100 years experience. . . . Used by leading contest flyers and model builders. . . . All standard sizes in skeins or on spools. . . . Sold only to manufacturers and dealers. . . . Send for samples and prices.

HODGMAN RUBBER CO., 261 FIFTH AVE., NEW YORK CITY

Prepare Now for **YOUR LICENSE**

Airplane mechanic's home-study course $1.25. Engine mechanic's course $1.25. Both courses $2.00. Postpaid. Also sent C.O.D. Contains all license questions with answers and accurate diagrams. Helps you tremendously in your mechanic's as well as Pilot's License Exams.

MEYER ENGINEERING, Box 8-J, Hempstead, N.Y.

COLT

45 CAL. Frontier Model

Basswood construction kit with working plans and all necessary hardware. Barrel and cylinder are machined. $1.45

COLT 45 Cal. "FRONTIER" model kit, 5½" barrel.....$1.55
COLT 45 Cal. "FRONTIER" model kit, 7" barrel. 1.70
COLT 45 Automatic Pistol Kit..... 1.00
COLT 25 Cal. automatic pistol kit..... .50
THOMPSON SUB MACHINE GUN model kit.... 3.00
Savage Cal. 32 automatic pistol kit..... .75
LUGER 9 M/M auto. pistol kit w/4" barrel..... 1.75
LUGER 9 M/M auto. pistol kit w/6" barrel..... 1.90
All kits make beautiful full scale models. Postpaid in U. S. A.
GUN MODEL CO., Dept. W-92, 2908 N. Nordica Ave., Chicago, Ill.

DEALERS! **MOTOR $3.95**

Cash in on this— Class "B" Construction Set

Regular profits on this fast seller. Order Now—IMMEDIATE DELIVERY.

Balsa Wood STICKS SHEETS BLOCKS SAW-CUT **Propellers**

MANUFACTURERS! — DEALERS — JOBBERS
CLUBS — SCHOOLS — EXPORT

SELLEY again has perfected an entirely new and fast method of cutting balsa, enabling us to produce in 1 hour what ordinarily would require 6 hours to do. Hence, this saving in labor cost is passed on to you at these NEW SENSATIONALLY LOW PRICES. Our Saw Cut Balsa propellers are the most accurate true pitched props available. We are prepared to furnish sizes from 4" to 18" in any quantity on short notice.

And now, an unfailing, reliable source for the best selected grade of the MOST ACCURATE AND SMOOTH CUT sheets, sticks and saw cut propellers at surprisingly NEW LOW PRICES.

NEW! Confidential NET PRICE LIST

Every dealer will find this the MOST COMPLETE LIST ever compiled for the Model Industry, all basic and Raw Materials, Special Wood Parts, Wheels, Die-cast Airplane and Boat Items, Boxwood Parts, Dope, Rubber, Paper. In fact, hundreds of items that can now be supplied from one source at the Lowest possible Prices.

IMPORTANT —We will mail this list to legitimate dealers only. Use your letter head. Post cards positively will not be acknowledged. Before placing your next order, write for our price list and see our prices before ordering.

SELLEY MANUFACTURING COMPANY, Inc.
Dept. 412, 1377 Gates Avenue, Brooklyn, N. Y.

Air Adventurers

(Continued from page 22)

you want and point your efforts along that line. You want to get into the air corps, but you do not have a couple of years of college. So what? You can still join the air corps as a buck private, take the training course at Chanute Field, which is free; and you have the best training in the world! Then, as you go along, all you have to do is to show interest, let your superior officers know what you want, and then prepare yourself for pilot training. There are hundreds of noncommissioned men getting pilot training and heading for commissioned rank today. Why not you?

So you want to be an air-line pilot, but they won't even let you on the field to watch the mechanics take the engines down. Isn't that too bad! If you want to be an air-line pilot, what are you actually waiting for? A rich uncle to die? An old maiden aunt to get suddenly generous, or are you a real Air Adventurer? If you want to fly a big airliner and you happen to be bumming it along the railroad tracks wondering where your next meal is coming from, you can still fly an airliner. Many a first officer today started from a tougher scratch. If you have all you started with in the way of physical ability and really want to fly an airliner, you know darned well that the law says that you must have so many solo hours to your credit. You know, also, that it costs so much an hour to get the time. You also know that you must spend about two years as a copilot before you can take over.

So what? That's the answer to it all. Go out and get it.

Two hundred and fifty hours at, say, ten bucks an hour is $2,500—and you are ready for a job that pays more than that a year. If you took up the medical or legal profession, you would pay out much more and earn a darn sight less for years! What do you want, gravy? If you can earn fifteen dollars a week, you get $780 a year. In three years you have earned $2,340. You can save some of it unless you must have your movies, your fancy rags and your other luxuries. You can get a lot of training either as a ground man or a pilot for one third of that $2,340, remember. All you have to do after that is to figure out how you can get twenty a week, or even twenty-five. By that time, once you have established yourself as a wage earner who can be trusted, you can borrow money to get what you lack—if you really want to be an air-line pilot and get at least $6,000 a year.

Where else in the world can you do that, and what are you waiting for?

Aviation owes you nothing, but aviation offers more than any other profession. If you want any part of it, the profession is wide open. If you have certain physical defects, quit worrying about them and feeling sorry for yourself and be tickled to death you are not in a wheel chair or on a street corner with a tin cup selling pencils.

There is a man in Britain today who has lost both legs. They gave him the Distinguished Flying Cross recently for shooting down his nineteenth German plane. They tried to steer him out of the game because he had had an accident that took off one leg below the knee and the other just

About the SOLO CLUB and how to become a member

Feeling that there is a definite need for a means of recognizing those pilots who have experienced the supreme thrill of their first adventure alone into the blue on man-made wings, Air Trails has formulated and founded the SOLO CLUB.

This club is open only to those who have actually made a solo flight in heavier-than-air craft, either motorless or powered. It does not matter when or where such flight was made. Applicants must furnish the membership committee with satisfactory proof of their qualification for acceptance. There are no dues. Once a member, always a member.

To obtain your sterling silver SOLO CLUB lapel wings and life membership identification card, comply with any of the following requirements and sign. Send with fifty cents to the SOLO CLUB, Membership Committee, Air Trails, 79 Seventh Ave., New York, N. Y.

Proof of Qualification as a SOLO CLUB Member

1. Dept. of Commerce license and number if held.....
2. F. A. I. license and number if held.....

Or attach any of the following:

3. Evidence of military or naval air-corps service.
4. A letter from your instructor testifying to your solo flight, giving his rating and license number.
5. A notarized statement, preferably with witnesses, giving all details and data of solo flight and plane used.

In submitting the above for membership in the SOLO CLUB, I certify my willingness for the Membership Committee to investigate my application.

Applicant ..... **Age** .....
(please print)

Street ..... **City or Town** ..... **State** .....

HE WAS A SINGLE STEP FROM DEATH!

A true experience of H. J. DE VAUENT, *Scout Leader, Toledo, Ohio*

"AFTER A RAGING CYCLONE had made a shambles of our neighborhood. I grabbed my flashlight and started to round up my Boy Scouts for rescue work," writes Mr. De Vauent. "I had never viewed such a scene of desolation.

"TREES WERE UPROOTED, automobiles overturned, and houses blown from their foundations. Inky darkness complicated rescue work because all power lines were torn down by the force of the storm. One of my Scouts started away from the group on an errand.

"INSTINCTIVELY, I THREW the beam of my light ahead of him, and shouted in horror. A step from the lad, like a deadly snake, lay a 5500 volt power line! Your dependable 'Eveready' *fresh* DATED batteries certainly saved a boy from sudden death *that* night!

(Signed) H. J. DeVauent"

The word "Eveready" is a registered trade-mark of National Carbon Co., Inc.

FRESH BATTERIES LAST LONGER... *Look for the* DATE-LINE

NATIONAL CARBON COMPANY, INC., 30 East 42nd Street, New York, N. Y.
Unit of Union Carbide UCC *and Carbon Corporation*

PARENTS AND MODEL BUILDERS

Get this Gas Model Now for XMAS

THE DICTATOR

RULER OF THE SKIES

38" Class "A" $1.75
50" Class "B" $2.75
M & M Wheels Included
78" Class "C" $4.75
With 4½" Ohlsson Wheels $5.95

No Waiting
Guaranteed In Stock Now

GET YOUR FREE CHRISTMAS GIFT NOW

As an introductory offer for our new line of Solid Models we are offering absolutely FREE one (1) 38" Towline Glider Value 50c with each Solid Model purchased. These Kits contain all parts sawed to outline shape, full sized plans, liquids, wheels, etc. $1.25 Value for only 75c.

16" Bell Pursuit | 13" Messerschmitt | 12" Fokker Tripe | 15" Goshawk
15" Boeing P-12 | 12" Sopwith | 13" Fr. Nieuport | 12" S. E. 5A

75c ea. Postpaid

FEATURING

● Full size blueprints ● All ribs and bulkheads cut to shape ● Sheet covered leading edge ● Cap stripped wing ribs on "B" and "C" models ● Silkspan "GM" covering ● Removable tail unit, wings and landing gear and entire motor unit ● Finished Hi-Fli gas propeller ● Plenty of cement and dope.

X'MAS OFFER
"A" Kit with Motor $8.25
"B" Kit with Motor $9.25
"C" Kit with Motor and 4½" Ohlsson Wheels ... $12.00

Send for Free Catalog of Motors and Supplies

The Class "A" model has ready finished balsa sides, the "B" and "C" models are of the strut and longeron type. Easy construction and accurately ready cut out parts insure contest performance.

"ALL POPULAR MAKE MOTORS ALWAYS IN STOCK"

Mfg. By: TRIANGLE MODEL SUPPLY CO. 31-85A 42nd Street, Long Island City, N.Y.

W. S. 16½"
O. A. 12"

GUARANTEED TO FLY
100-300 FT.

A BIG SUCCESS
When Introduced
at 50c

NOW ONLY
25¢ POSTAGE 10c
AT DEALERS

Non-breakable
Buckram Fuselage

Cambered
Balsa
Wings

READY TO FLY!
—only 4 simple
adjustments!

Ideal's
VICTORY Flyer

LOOK! IDEAL'S 10c 18" FLYING MODELS POSTAGE 10c extra
RYAN STM — BELL AIRACOBRA — CURTISS P40
DOUGLAS DIVE-BOMBER — HAWKER HURRICANE — STINSON 105

LOOK! IDEAL'S 25c 25" FLYING MODELS POSTAGE 10c extra
RYAN STM — PIPER CUB — HAWKER HURRICANE — NORTH AMERICAN TRAINER
STEARMAN TRAINER — BELL AIRACOBRA — Special! 37" TOWLINE GLIDER

LOOK! IDEAL'S 50c 32" FLYING MODELS POSTAGE 10c extra
MONOCOUPE — BELL AIRACOBRA — RYAN STM
HAWKER HURRICANE — REARWIN SPORTSER

BRAND NEW! SUB S-48 — 24"
CARVED PINE HULL
SUPER DETAIL KIT $2.50 Postpaid — makes perfect building easy!

BIG HOBBY CATALOG · 10c
Ideal MODELS IDEAL AEROPLANE & SUPPLY CO., Inc.
24-26 West 19th St., NEW YORK
Pacific Coast: Model Boat & Aircraft Co.
1356 5th Ave., San Diego, Calif.
VISIT Ideal's HOBBY CENTER

[DEALERS: Write today for prices]

MODEL BUILDERS!
You can fill your Xmas needs from our large stock!
Scientific, Berkeley, Comet, Ideal, Capitol, Megow.
Brown Jr., Ohlsson, Denny, Bantam, Atom, Syncro.
TRENTON HOBBY CENTRE
237 East State Street
Trenton, New Jersey

TEX. FOSTER
106-06 Jamaica Ave. Richmond Hill, N. Y.
Hours 10 A. M. to 9 P. M.
*Sail boats — *Gasoline engines
*Plans — *Gas model kits
*Fittings — *Flying model kits
*Sails — *Supplies
A large stock on hand at all times.

DEALERS!
Obtain real profits on gas and rubber powered supplies and kits. Send stamp for complete wholesale prices.
WATERBURY MODEL BUILDERS SUPPLY CO.
118 CHERRY ST., WATERBURY, CONN.

NEW 1941 MODEL POCKET RADIO!
NO TUBES NO BATTERIES PLUG IN
DURABLE PLASTIC CABINETS
DUAL BANDS—MAGICTENNA—MICRODIAL
Fits your pocket or purse—Wt. 6 ozs. Small as cigarette package. Receives stations & some short wave. PATENTED POWER RECTIFIER. No tubes, batteries. Hi-ratio easy tuning slide "MICRODIAL". M. L. OF ILL. SAYS: "MIDGET RADIO WORKS FINE"!
ONE YEAR GUARANTEE!
Sent complete ready to listen with instructions & tiny phone for use in homes, offices, hotels, in bed, etc. SIMPLE TO OPERATE—NO ELECTRICITY NEEDED! SEND NO MONEY! Pay postman only $2.99 plus postage charges on arrival or send $2.99 (Check, M.O., Cash) and yours will be sent postpaid. A MOST UNUSUAL VALUE! ORDER NOW! FREE! PLUG IN "MAGICTENNA"—ELIMINATES OUTSIDE WIRES!
MIDGET RADIO CO. Dept. AT-12 Kearney, Nebr.

METAL COVERED MODELS
KEEP IN STEP WITH MODERN AVIATION
BUILD REAL PLANES IN MINIATURE

Actual photo of BOEING STRATOLINER MODEL

Here it is fellows! A brand new scale model of the beautiful Giant Boeing Stratoliner. The Stratoliner is the last word in airplanes—this kit is the latest in scale models. Imagine this beauty, 21" wingspan, completely covered with aluminum even to reproducing the rivets in the actual plane. Kit is absolutely complete including 1 motors, 1" aluminum cowls, 1 die-cast props, wheels, liquids, etc. All balsa cut to outline shape. Nothing else to buy. You will be proud of this outstanding model and will enjoy building one of these new metal covered planes. PRICE ONLY $3.75 Postpaid

If your dealer can't supply you, send direct and include 15c postage with $1.50 kits and 10c with other kits.

DEALERS: Your customers will be asking for these kits. Write today for prices on your letterhead. Be prepared for the demand.

Actual photo of VULTEE VANGUARD MODEL

It is easy and fascinating to build real planes in miniature with sheet aluminum covering. Your finished job will be a masterpiece with a beautiful lustrous finish that you will be proud of. The kits are complete with everything necessary to make a finished model, with the exception of liquids. The photograph will give you an idea of how the finished model will look.

SELECTION OF FIVE MODELS

13½" VULTEE VANGUARD	$1.50
13¾" CURTISS HAWK 75A	1.50
12" CONSOLIDATED PB2A	.75
10" BELL P-39 PURSUIT	.50
9" NORTHROP A17A	.40

Write for descriptive, illustrated folders.

CZ MODEL AIRPLANE CO. Dept. A-9 3656 W. 65th St., Chicago, Ill.

below the hip. Today, he'll bet you all the tea in China he can get in and out of a Hawker Hurricane quicker than you.

An individual case, we grant you; but yours is an individual case, too, remember. You yourself have certain qualifications no man may take from you. You have certain skills in your hands or fingers. You are adept at something. You can do certain things better than anyone else in your group. Why not capitalize on these things and add to them the other qualifications you have and accomplish that which you have set your heart on? After all, all the money in the world will not *buy* flying ability.

So, there it is in the plainest words we know. Stop grousing that you can't be in aviation. Ask yourself plainly if you have even made a puny effort to get into aviation. Be fair to yourself and take stock of what you have, what you can get and how much work you care to put into this business of getting into the greatest profession the world has ever seen.

It's a very strange thing, but the men we have met who have gone far in aviation are the quietest people in the world. They don't have time for talk or squawk; they are too busy working to get further.

Let's use a little midnight oil and quit spreading the old vocal oil!

Are you with me, Air Adventurers? Let's go—for aviation!

More next month.

Your Flight Commander,
ALBERT J. CARLSON.

It Takes Pull!

(Continued from page 20)

with a ring for a hold-back rope. One end of the hold-back rope is tied to some heavy object, preferably a car, while the other end, after being passed through the ring in the tail, is held by a crew of several men. Another crew takes hold of the loose ends of the V of the shock cord, the number of men depending on the weight of the glider, its distance from the slope and the overspeed required; the usual number is six on each end. One man keeps the wing of the ship level.

All signals are given by the pilot of the glider. When the pilot shouts, "Walk!" the shock-cord crew takes a few paces forward, stretching the cord. On his command, "Run!" they start running, and when the elastic cord is stretched almost to its limit he shouts, "Let go!" At this the tail crew lets go of the tail rope and the ship is catapulted into the air like a stone from a slingshot.

The second method, the auto tow, was introduced in the United States by Hawley Bowlus, builder of the famous Bowlus Albatross and Baby Albatross sailplanes, who is credited with originating it. The gliding fraternity did not take kindly to it at the beginning, and I distinctly remember many of my gliding friends accusing me of foolhardiness and a mild form of insanity when I started the auto tow method here in the East after

"I'm sending your application right in!"

FLY SAFELY

Follow A. M. A. Rules

★ ★ ★

Abide by the common-sense, safety regulations of the Academy of Model Aeronautics.

★ ★ ★

A nationwide safety campaign has been launched to call to the attention of all aeromodelers their responsibilities and the need to "think" before flying model aircraft, especially gas powered models. Aviation leaders, government officials, model club directors, leading contestants and designers, and thousands of licensed Academy flyers have signified their desire to cooperate and conduct their activities with due regard for others.

★ ★ ★

You can help by following the official regulations and having all aeromodelers you know adhere to the rules. You can [illegible] These licenses are good for 12 months and indicate your affiliation with the governing body for model aviation in America . . . they are required for entrance in officially sanctioned competitions. Rubber model flyers receive an official Academy license and lapel emblem pin, registration certificates for their model airplanes, a copy of the official regulations, and official sticker for their automobiles and an Academy emblem decal. Gas model flyers, in addition, receive a set of license numerals for the wings of their gas models.

★ ★ ★

The Academy was established in 1934 to keep model aviation "of, by, and for the model builder" and to advance the activity in every way possible. It is a division of the National Aeronautic Association. It issues manuals and helpful aids for running clubs and conducting meets. A.M.A. Headquarters assists model aviation leaders. For full details concerning the A.M.A. and official sporting licenses, mail the coupon below with a 3c stamp to Academy Headquarters.

★ ★ ★ ★ ★ ★ ★ ★ ★ ★ ★ ★

ATI

ACADEMY of MODEL AERONAUTICS
Willard Hotel . . . Washington, D. C.

Please send me full information concerning the Academy of Model Aeronautics and its sporting licenses.

Name.....

Address.....

City..... State.....

having been given instructions by Hawley. The reason for this antipathy was that many fellows, knowing little not only of stresses imposed on gliders in steep climbs under conditions of excess speeds, but literally knowing nothing of flying, hooked gliders to their cars and proceeded to carom across field and dale with total disregard for the strength of the wind, while the pilot in the ship frantically hauled the stick back as far as he could. Result, the machine got dewinged, as the English call the process of shedding wings. Used sanely, auto tow is the best method of teaching a student to fly gliders when a two-place machine is not available, and at present is the only method used for instruction in the United States. The equipment used for auto tow consists of an automobile, preferably a roadster able to do at least thirty-five to forty miles per hour in second speed, and rope five sixteenths in diameter, the length depending on the size of field available. For instruction purposes about 350 to 400 feet are sufficient; experienced pilots use 1,000 feet or more. It is preferable for the car to be equipped with a seat facing the glider during instructions. Both car and glider should be provided with release hooks so that the rope can be dropped from either end. In towing, strict attention should be paid to the wind conditions, and the combined speed of the tow car and wind should be equal to the flying speed of the glider. That is, if the flying speed of the glider is 35 m.p.h., the wind during the tow 10 m.p.h., the car should not exceed 30 m.p.h., giving the glider [illegible] of 5 m.p.h. being to insure a decent rate of climb.

The glider itself should not be climbed too steeply, as this imposes undue stresses on the wing, the best angle of climb being between twenty and thirty degrees. At the moment of take-off the ship should be climbed gently until approximately 100 feet of altitude is reached, after which a sharper angle can be assumed. As the desired altitude is attained, the ship should be leveled off and the release pulled.

The winch tow is the most popular means of launching gliders and sailplanes. In the United States it was introduced by Gustave Scheurer, one of the pioneers of our gliding and soaring movement and organizer of the Aero Club Albatross of New Jersey. The advantage of a winch tow is that the field from which winch operations are conducted does not have to be as smooth as that required for auto tow, the operations themselves are accelerated as the rope is brought back to the starting point the moment the glider lands, and a take-off can be made almost immediately after landing.

The procedure of piloting the glider from winch tow is similar to the auto-tow method with the difference that the ship gets off the ground much more rapidly. We will not endeavor to describe all the different types of winches in use, as there are quite a number of them and practically every club has its own idea for one. There are some which have a drum attached to the rear wheel of a car, others which use independent power plants for operating the drum. Still others use friction drives consisting of tires mounted on wheels attached to the drum, the whole unit getting its rotation from being lowered onto the wheels of the car, so that the car's tires, being in contact with the tires of the drum's wheels, drive it through friction. The drum has 3,000 to 5,000 feet of rope wound on it and is equipped with a level winder, automatic or hand-operated, which winds the rope evenly on the drum as it is taken in during the tow. A cutting device for the rope, called guillotine, is affixed to the pulleys through which the rope runs to the drum so that it may be cut off in case of failure of the release mechanism on the glider.

Winch driving requires a good deal of skill from the operator, and it's best to have a man who is well acquainted with flying to drive it. Here's how it's done. The winch is put on the far end of the field so that the ship would take off directly into the wind. It is jacked up if it's a friction drive, or the drum is located on one of the rear wheels, and the front wheels are blocked. The free end of the rope which has a ring and is to be attached to the glider is hooked to a car, which proceeds to the take-off point, unreeling the rope from the winch drum. At the take-off site a flagman is located with three flags, red, yellow and green. As soon as the winch operator sees the yellow flag he starts the engine of his winch. At the next signal, the green flag held up straight, he puts the winch in high gear and takes up the slack. As the [illegible] winch and takes the ship into the air. Here he must watch carefully for a signal from the pilot in the glider. If he sees him wigwagging the wings he should accelerate the drum, for the signal means "not enough speed." If the ship fishtails from side to side it means "too much speed," and he should slow up. As the glider gains altitude the speed of the winch should be slackened. As the drum reeling in the rope gets bigger in diameter and the air speed of the glider rises proportionately at the end of the climb, the speed should be diminished by at least thirty percent. If the ship is almost directly above the winch and no visible attempt to release is made, the winch should be thrown into neutral and practically stopped to warn the pilot that it is time to release. If still no attempt to release is made, the guillotine should be put into operation and the ship cut off from the winch. Failure to do so may result in a fatal accident, as the ship will be jerked to a stop stall and spin in. Another method, if the guillotine does not operate or is not present on the winch, is to shift it into reverse and pay out enough rope so that the pilot can make a turn back to the field and attempt a landing. This particular method has been successfully accomplished by myself when a friend of mine whom I was towing failed to release and, not knowing that he was still attached, proceeded to make a turn. The flying speed of the ship increased by better than 20 m.p.h. because of the resultant rope drag, and only because of his skill as a pilot and the fact that enough rope was

New War Thrillers

10¢ 25¢ 50¢

DEVELOPMENTS in aircraft are coming along at racing speed . . . and every month Megow brings out something new! Now it's War Planes . . . to build, to fly and shoot at . . . and interest is at fever-pitch!

This month it's . . .

C31. SPITFIRE. Favorite fighter of the British R.A.F. A type of plane that is in the news every day. A rubber-powered model full of thrills. Full-size plans. Superior materials. 23-inch wingspan. 25c

J17. "STUKA" BOMBER. A big 30-inch rubber-powered flying model of another plane you read about . . . the German Junker's Dive Bomber JU87B. Full-size plans and superior materials that make Megow kits *so different!* 50c

S44. "STUKA" BOMBER. A small solid model of the same plane with 8-inch wingspan. All-Balsawood, exact scale. Plans and all materials 10c

SEND 10c FOR MEGOW'S LARGEST CATALOG . . .

132 pages . . . interesting hobby-craft articles, scores of model airplanes, ships, model railroads, equipment and supplies

NEW MEGOW "199" MOTOR FOR MODEL AIRPLANES

Operates upright or inverted. Chrome-vanadium steel cylinder honed and lapped to .0001". Timer enclosed. Crank case special aluminum alloy, permanently sealed. Extra long bronze bearing. Tungsten points. Bore and stroke, ½" Disp. .199. Weight 3½ oz. Block tested.

$12.50 with coil and condenser

MEGOW

Dept. AT, Howard and Oxford Streets Philadelphia, Pa.
or 217 N. Desplaines St., Chicago, Ill.
or 718 Mission St., San Francisco, Cal.

"G" LINE FLYING

Sensational - New - Thrilling

GAS POWERED SUPER SPEED PLANES FLOWN UNDER FULL CONTROL

NOT RADIO CONTROLLED

Protected By Patent Pend.

BABY SHARK SUPER SPEEDSTER

$1.98 KIT COMPLETE

The new BABY SHARK, Super Streamlined Speed Ship, is designed for all Class A and B motors. This racy little job flies at tremendous speeds of from 50 to 75 M.P.H. It is unusually easy to construct and amazingly stable in flight. COMPLETE KIT, including plenty of balsa, hardwood, plywood, cement, dope, paper, wire, etc., together with detailed plans and instructions, Only $1.08. Postage 25c additional.

TIGER SHARK SPEED DEMON

DELUXE $4.95 KIT COMPLETE

THE SUPER STREAMLINED TIGER SHARK, World's Fastest Gas Model, roars through the air at the unbelievable speed of from 60 to 90 M.P.H. Due to the inherent "G" Line Flying Stability engineered into this design, the Shark is unusually stable and easy to control. May be powered with any 1/5 H.P. Motor.

DELUXE CONSTRUCTION KITS are most complete, including plenty of good quality balsa wood, printed parts, M & M Wheels, prop blank, bamboo paper, spring steel wire, ignition wire, 50 ft. "G" Line, generous supply of cement and dope, etc. Together with detailed plans and instructions for building and flying these new "G" Line Speed Demons. RUSH IN YOUR ORDER TODAY. Or send 5c for illustrated Descriptive Folders.

Dealers Write For Special Discounts.

Victor Stanzel & Co.

Schulenburg. Dept. A. Texas

payed out to him did he land the ship without so much as a scratch.

The final method, airplane tow, is the most fascinating way of launching, but is subject to strict government regulations. The sailplane must be licensed for airplane tow as well as placarded for the maximum permissible speed for towing. The glider pilot must have a commercial glider pilot's certificate, and the tow pilot a power plane commercial license. Both pilots are required to wear parachutes, and even the length of the rope is regulated, the minimum being 300 feet for local tows, 400 feet for cross-country tows. The ship used for towing should have a rearward vision and be supplied with a suitable release for the tow rope. The rope diameter is the same as used for winch and auto tow, although some pilots prefer using one-quarter inch Manila. Once everything is in order, both glider and power plane are wheeled onto the field and pointed upwind. One end of the rope is attached to the glider release hook, the other to the tail-skid release of the power plane. The rope should not have any slack once it is attached to both ships. One of the crew members is stationed near the power plane, another at the wing of the glider. Once everything is in order the sailplane pilot gives the O. K. to his wing man, who waves to the power-plane pilot. The tow-plane pilot guns his ship and the flight starts. The glider will be in the air long before the power plane. As he rises to approximately fifty feet he should dive slightly toward the ground and put slack into the rope; this decreases the drag on the power plane and helps it to get off. In flight the sailplane should always ride slightly above the tow plane. If the pilot gets below he is in danger of getting into the propeller slipstream, receive a bad shaking up and lose control of his ship. The tow-plane pilot should always bear in mind to fly his ship as close to the placarded speed of the glider as possible. Although a slight overspeed is permissible, too much will put severe strain on the glider. This is especially true in bumpy weather where gust loads are apt to strain the ship to a breaking point. Once the glider reaches the desired altitude the pilot releases; a slight jerk on the power plane indicates that the ship is free.

Air Corps Questionnaire

(Continued from page 13)

Question: When most of us hear the words "air corps," we think of the army air corps, but I don't think many of us know exactly what part it plays in our defense. Could you enlighten me a little more on this subject?

Answer: The air corps is the arm that contends with enemy forces of the air, attacks his ground troops from the air, and destroys by bombing his supply depots, his factories where war supplies are made, and his military installations of all kinds. A modern and powerful air arm is one of the main reliances of our army for the defense of the nation. The air units of the United States navy would, in war, co-operate with the fleets of the navy to destroy hostile ships and thus keep an enemy from our shores. The air corps of the army, however, would co-operate and help as needed against an enemy's forces on the seas, though it is organized primarily for operations against the enemy in the air and on the land.

Question: What are some of the different types of planes?

Answer: The air corps has three basic types of combat airplanes: pursuit, bombardment and observation. Pursuit airplanes are of two types: interceptor and fighter. Interceptor airplanes are primarily used for meeting and destroying hostile aircraft attacking objectives in our own territory. Fighter pursuit airplanes accompany bombardment planes and protect them against attack by hostile airplanes. Bombardment airplanes are of three general kinds: light, medium and heavy. Light bombardment airplanes are designed to give fire support to ground troops by machine-gun fire and bombs.

Heavy bombardment airplanes are

The "FLYING CLOUD" FREE

with a year's subscription to AIR TRAILS

- The Flying Cloud 44" wing span, 195 Square Inch wing area, contest endurance model for Wakefield and Moffett international competition.

Designed by HENRY STRUCK . . . America's No. 1 contest model builder.

1940 N. A. A. Gas Model Record Holder
1939 Indoor National Champion
1939 Wakefield Team
1939 N. A. A. Gas Model Record Holder
1938 Flying Scale Model Champion

And more startling is the fact that the Flying Cloud is so easy to build. . . . Build it for your next contest entry; it should bring home the prize with a true champion's performance. The Flying Cloud includes these star features:

- **Propeller retracts flush against fuselage sides.**
- **All propeller parts ready-made.**
- **Rubber tensioner ready-made.**
- **All wire parts ready formed, including landing gear, rubber hooks and tail skid.**

AIR TRAILS MAGAZINE, 79 Seventh Avenue, New York, N. Y. **Dept. D-Q**

I am inclosing $1.50. Kindly send me one FLYING CLOUD KIT and a year's subscription to AIR TRAILS. (This offer is open only to subscribers living in continental United States.)

Name.....

Address.....

City.....**State**.....

designed for long-range bombardment and reconnaissance flights over land and sea. Medium bombardment airplanes are lighter and less expensive, and are designed for bombardment or reconnaissance missions that do not require extreme range. The purpose of observation airplanes is to furnish short-range observation, photographic, command, courier and liaison service to corps and divisions, including their component infantry and artillery units. Observation service includes both visual and photographic reconnaissance and air ground radio communication. All of these combat types of airplanes are armed with machine guns for self-defense against enemy airplanes and have as much speed as their weights and engines will permit.

Question: You say that these are combat planes. What kinds of noncombatant planes are there?

Answer: There are three kinds of basic, noncombatant airplanes: training, cargo and transport, and experimental. The training planes are of various types including primary, basic and obsolescent service types. Transport and cargo airplanes are used to carry both troops and supplies. Experimental airplanes are those under development.

Question: If I am to be a part of all this and decide to join, just what would I expect to learn—i. e., what are some of the different subjects I would have to take up?

Answer: Upon entering, the new flying cadet at once begins his military training and at the end of a few weeks his ground and air training as a flier begins. The ground instruction consists of lectures, demonstrations, laboratory, and class-room work, and includes studies in theory of flight, airplane rigging, and structures. There are courses in airplane engines and trouble shooting; in air navigation, including maps, compasses, radio aids to navigation, and flying instruments; weather; radio code; and airplane weapons. The work at the Air Corps Training Center is divided into three phases, the first being about two months and the other two lasting approximately three months each: primary flight training given at one of the civilian schools selected by the government and basic flight training given at Randolph Field, followed by advanced training at Kelly Field, San Antonio, Texas.

On completing the course, a flying cadet receives his "wings" and the rating of airplane pilot, and soon thereafter a commission as second lieutenant in the air corps reserve.

Question: When I was born my folks had my birth certificate made out Chauncy John Doe. I never liked the name Chauncy and therefore went by the name of John and dropped Chauncy entirely. All through grammar as well as high school I was known as John, but my birth certificate still has my first name as Chauncy. When I turn in my certificate to you, will it make a difference because the name on the school record and the rest of my papers do not have the first name?

Answer: Yes, you will either have to change all your papers around to read like your birth certificate or make out an affidavit stating the facts about the difference in your name. In the case of a man having changed his surname, he must present an affidavit that his name has been officially changed.

Question: In the event I fill out the application, when I sign my name and have my signature notarized, does that obligate me in any way to the government?

Answer: No. When your signature is notarized it just proves that the aforesaid statements are true and correct to the best of your knowledge. You are not obligated in any way to the government until you raise your hand and are sworn in.

Question: May I at any time get married during my period of service?

Answer: No. A flying cadet cannot be married. However, upon being discharged as a flying cadet and appointed second lieutenant in the air corps reserve, he may be married if he so desires. For those who do, Uncle Sam has made pleasant provisions. He is furnished a set of quarters to live in, free gas, electricity and heat, along with free medical and dental care.

Question: I understand that one's eyes play an important part in the physical examination. Suppose a man has almost perfect eyesight, say 20/20 in one eye and just a little over in the other, will they pass him on the strength of one eye being perfect and the other just a fraction off?

Answer: Your eyes are very important, not just alone to you but to the government and its personnel. Faulty eyesight may result in the loss of many lives, especially when and where judgment plays such an important part. Lack of judgment due to faulty eyesight has been the cause of many accidents. Both your eyes must be 20/20 bilateral, without glasses; unimpaired ocular muscle balance; unimpaired optical organism. We are reminded of the experience of an applicant who took the exam and passed everything until he came to the optical part. It seems he was asked to cross his eyes, but try as he would he couldn't make them come to that affectionate stage and had to give up—whereupon he failed the entire examination. Now why, just because he couldn't cross his eyes, didn't they pass him? You have the answer in muscular control. The flight surgeon deemed it inadvisable to pass this man because he didn't have complete control of his eyes. The average person, though, much to his surprise, finds his eyesight is normal. Color blindness is one of the chief causes of disqualification.

Question: I've been told that applicants don't have to be supermen to pass the physical exam, that the requirements are only "normal." Maybe so, but what do you mean by "normal"?

Answer: Well, certain rare individuals are able to read only 10 millimeters high from a distance of

The LOW-PRICED .... HIGH-POWERED MOTOR

That is

Unconditionally Guaranteed

SKY CHIEF

Class "C"—1-5 H.P.

only

$6.95

Complete with Coil & Condenser



Sky Chief "Lightning" 3 ounce Coil
*Bore 7/8", stroke 7/8", displacement .526
*R. P. M. up to 13,000 with 13" propeller
*All bearings are Diamond-bored and Micro-lapped
*Weighs approximately 10 ounces with coil and condenser
*Multiple-finned Cylinder made of Molybdenum Iron
*Piston centerless-ground and Micro-lapped with Perfect Circle Rings for longer motor life
*Heat-treated Crankshaft made of polished-ground steel scientifically balanced.

PRECISION ENGINEERED—BLOCK-TESTED

American Supercraft Corporation
Union and Lake Streets
Chicago, Illinois, U.S.A.

PLANE TALK **SKYWAY** SAVINGS ON ALL SUPPLIES

Make Skyway your regular headquarters for all your model building needs — gas motors — kits — supplies. You want reliability—here it is!

18" BALSA STRIPS Select, Hard Stock
1/16 sq. 60. 5c
1/16x1/2 35 for 5c
1/16x3/16 18. 5c
1/16x1/4 15 for 5c
3/32 sq. 30. 5c
1/8 sq. 30 for 5c
1/4x3/16 12 for 5c
1/4x1/4 10 for 5c
3/16 sq. 8. 5c
1/4 sq. 6 for 5c
1/4x1/2 3 for 5c

18" Balsa Sheets
1/64x2 6 for 10c
1/32x2 9 for 10c
1/16x2 8 for 10c
3/32x2 7 for 10c
1/8x2 6 for 10c
3/16x2 3 for 8c
1/4x2 3 for 9c
1/2x2 2 for 11c
3" & 36" cost twice 18"; 3x36, 3 times.

NOSE BLOCKS
1x2x1 .....1c
2x2x1 .....2c
2x2 1/2x1 .....3c
3x3x1 .....4c
3x3x2 .....7c
3x3x3 .....9c
5x5x2 .....17c

5 FOOT BALSA
1/8x3/16 ..12 20c
1/4x1/4 ....10 20c
3/16 sq. 8 20c
1/4 sq. 6 20c
1/4x1/2 .... 3 20c
3/8 sq. 2 20c
1/2 sq. 2 20c
Sheets, 4 times 18". Double the above price for genuine aircraft SPRUCE

18" Balsa Planks
1/2x1/2 ...2 for 5c
1x1 ....1 for 5c
1x2 ....1 for 9c
2x2 ....1 for 16c
2x3 ....1 for 22c
2x6 ....1 for 38c
3x6 ....1 for 72c

Plastic Balsa
4 oz. 22c, 1 oz. 10c

PROP. BLOCKS
1/2x 3/4x 5 7—5c
1/2x 3/4x 6 6—5c
3/4x1 x 8 3—5c
3/4x1 1/4x10 2—5c
3/4x1 1/4x12 3c ea.
x1 1/2x12 5c ea.
x1 1/2x15 6c ea.

PLYWOOD
1/16, 1/8, 1/4 40c ft.

RUBBER-POWERED ACCESS.
Model Knife, Surgical Steel Bl 10c
Model Pins 1/2 or 1".....100 for 5c
Sheet Celluloid 5x7 4c, 14x17 15c
Ball Bearing Washer 10c val, 5c
Sandpaper, 12 sheets 5x5..... 5c
Lilliput Lights—Dress up display model, 3 lamps, wired, instruc. sheet, each 85c
Insignia 36—American, French, English, Germ., Squadron, in colors, gummed, per sheet..... 5c
Washers, pinhole, 1/8, 1/4, 2 dz. 3c
Prop Shafts, doz. sm. 6c, lge. 10c
Ball Bear: 1/16 15c ea., 1/8 33c
Nose Plugs for 5c: 1/2"—8, 3/4"—6, 1"—4.

MACHINE GUNS
3/4"..2c, 1 1/4"..4c
1 1/4" Lewis 5c
1 5/8" Lewis ...6c
1 1/4" Ring Mt. 10c
1 3/4" Ring Mt. 15c

BOMBS
3/4" ....2 for 5c
1 1/4" ....2 for 11c
3" Torpedo ..10c

Thrust bearings
1/2 doz., Sm. 5c
1/2 doz., Lge. 7c

SKYWAY GAS MOTORS
No premiums or packing charge on motors.
Ohlsson "19" $14.50
Ohlsson "23" 16.50
Ohlsson "60" 21.50
Forster..$17.75 ball bearing.. 19.00
New Forster "29" Class "B" 15.50
"O.K." Special 11.80
"O.K." Twin-Radio Control.. 35.00
Dennymite...$17.85 Unit... 15.85
Brown Jr. "D" $12.50 Brownie 7.50
Mighty Atom 12.50
New Bantam 16.50
Mighty Midget $9.50 Kit 7.85
Gwin Aero..$12.00 Kit.... 9.95
Tiger Aero 16.50
Synero B30..$6.95 Special.. 9.95
Sky Chief 6.95

BIG ALLOWANCE FOR OLD MOTORS

CEMENT
CLEAR DOPE THINNER
Banana Oil
1 oz. 5c, 1/2 pt. 30c
2 oz. 9c, pint 50c

MICROFILM RUBBER LUBE WOOD FILLER
1 oz. 9c, 2 oz. 15c

Colored Dope
1 oz. 6c, 2 oz. 11c
1/2 pt. 35c pt. 60c

MUSIC WIRE
.014 .....6 ft. 2c
.020 .028 6 ft. 3c
.034 .040 6 ft. 6c
.049 .....6 ft. 8c
1/16" ....3 ft. 5c
3/32" ....5 ft. 15c
1/8" .....5 ft. 20c

WHEELS per pr.

Birch	Bisa Celu	A L U
1/2 .01 .03		
3/4 .02 .04 .05		M.
1 .03 .05 .07		.06
1 1/2 .04 .07 .10		.09
1 5/8 .06 .10 .16		.12
2 1/2 .12		
3 .15 .30		

AA TISSUE
All col., doz. 19c
Silver ....ea. 4c
Superslik, wh. 5c

Bamboo Paper
White or Pervel 5c ea.—6 for 25c
Colors ..2 for 15c

GM SILKSPAN
White, Red, Yellow, Orange, Blue 3 for 25c
".00" ..3c a sheet

Gas Model Silk
Il'vy qual. 45c yd.

BROWN RUB.
1/16 sq. 15 ft. 5c
1/8 flat ..15 ft. 5c
3/16 flat 12 ft. 5c
Skein 225 ft. 1/16—50c, 1/8—60c, 3/16—85c

Camel H'r Brush
Med. 5c, Lge. 8c
Sm. 3c, Gas Mod. 15c

Celluloid Radial ENGINES
1 1/2" 8c, 2" 12c
2 1/2" 14c, 3" 17c
4" 50c, 4 1/2" 65c

Wheel Pants, Pr.
1/2" 5c, 3/4" 10c
1" 15c, 1 3/4" 20c

Trexler Wheels
1 1/4, 1 1/2.....40c
1 3/4, 2.....60c
2 1/4, 2 1/2.....60c
Gas Mod. 2 1/2, ..$1
3 1.25 3 1/2...1.50
4 1/4 .....1.75

M&M WHEELS
1 1/4, 1 1/2, 1 3/4 50c
1 3/4, 2, 2 1/2, 60c
Gas Mod. 2 1/2 90c
3 1/2 1.50, 3 1/2 2.75
4 1/2 2.75, 6" 4.00

TAIL-WHEEL
Knee action 75c ea.
1" Do-Nut 10c ea.

PROPELLERS

Balsa	Paulo Ritz Wing	Gas
5" 4c- 7c	Med.	
6" 5c- 9c- 8"35c		
7" 6c-12c- 9"35c		
8" 7c-15c-10"35c		
9" 8c-19c-11"35c		
10" 9c-23c-12"35c		
12"10c-28c-13"35c		
14"12c-35c-14"35c		
15"15c-44c-15" X		
16"16c-50c-16"50c		
18"25c-X-18"1.00		

Ritz-Gumwood
8"9"10"11" 15c ea.
12" 13" 14" 15c ea.
15" 16" ...35c ea.
17" 18" ...50c ea.

COILS
Smith 3V. $2.50
1 1/2 V. 3.00
"Superlite" 1.25
Powerhouse 1.50
Aero-Coil 2.25

TIMERS
Austin $1.00
Dural 1.95
Time-aire .. 1.00

XH'st Manifold
Nickel plated 50c
Str'm lined $1.00

SPRAY GUNS
Small 59c; Large size 2 Jars, 97c

ALUM. BRASS TUB'G per ft.
1/16 ...6c... 8c
3/32, 1/8 7c...10c
3/16, 1/4 9c...12c

Sheet alum.—ft. .003 10c .010 15c

ALUM. LEAF
3 sheets 5c

Dural Angle
1/2x1/2 ....15c ft.
3/4x3/4 ....22c ft.

Wing-Tail L'ght (3 in a set) 5/16 8c, 9/16 10c 11/16 12c per set

GAS MODEL ACCESSORIES
Champion Spark Plugs 3/8 or 1/4 65c
Spark Plug Wrenches, all sizes..25c
Condensers—Metal, 15c Smith 25c
Plugs & Jacks, Set of 2 35c, val 25c
Midget Tip Jacks 20c val, 2—15c
Terminal Clips 5/8" 10c val. 3— 5c
Gas Funnel, Alum. strainer.....25c
Spaghetti Tubing 1/16" 3 ft.—10c
Toggle Switch 50c val. 25c
3 to 1 SAE 70 Oil—1/2 pt.....25c
12" High Tension Leads—Best—14c
Booster Leads—50c val. 35c
Masking Tape 1/4x36"—Instructions 5c
Alligator Clips—5c Solderless 10c

AUTO RACE CARS
Bunch Speed Demon.....$16.50
Synero Rocket 19.00
Dooling—$19.50—"DeLuxe".. 23.50
Speed Chief 12.50
Speed King 15.00

FREE with all purchases over $1.00 your choice of: (1) Model Water Sprayer. (2) Model Builder's Knife. (3) Choice of 3-20" Model Plans—Curtiss, Heathe, Boeing, Driggs, Bellanca. (4) Masking Tape. (5) 6 sheets AA Tissue. (7) Sandpaper, 12 sheets.

FREE POSTAGE ON ALL U.S.A. ORDERS.

SHIPPING INSTRUCTIONS: Packing cost on all orders 10c, 36" or 5 ft. 20c. To packing cost add 15% postage for U.S. possessions, Canada, foreign countries when order is over $1 and 15c if under $1. 5 ft. packages to Canada shipped Express Collect.

For CATALOG Send 3c Stamp

BONA FIDE DEALERS Write for WHOLESALE PRICE LIST.

SKYWAY MODEL AIRCRAFT SUPPLY CO. 426 SIXTH AVE., DEPT. T BROOKLYN, N. Y.

YOUNG AVIATORS

Learn to build motors

We furnish the parts



SYNCRO PC-2 **ONLY $3.95**

Complete motor including spark plug

Now you can build a modern miniature gas engine, 13/16" bore, 9/16" stroke, developing 1/7-1/6 HP. Get the parts from us and complete the job and at the same time save money. Accurately machined parts, supplied in matched assemblies as shown, can be made into a powerful motor in jig time. Have the fun and get a Class B (AMA Rules) motor at an unbelievably low price.

Here's what you get for only $3.95

A. Cylinder assembly, with spark plug, piston and connecting rod.
B. Crankshaft, crankcase and liner assembly.
C. Crankcase cover.
D. Fuel tank and cover complete.
E. Gaskets (cylinder, gas tank, crankcase).
F. Gas line, needle valve and spring.
G. Bolts. H. Front Hub Nuts, together with complete instructions for assembly.

GET IT AT YOUR DEALER'S NOW!



SYNCRO SUPER-LITE COIL

Increases engine speeds; saves on batteries, tested for spark-length, and spark heat. 3 volts. Weighs only 2 oz. Imagine a coil of this capacity, high output, with high tension snap-on leads, for only **$1.50**

Send for complete Syncro catalog L40

SYNCRO DEVICES, INC.

MEMBER MODEL INDUSTRY ASSOCIATION

743 Beaubien – Detroit

N. Y. Sales: 200 Fifth Ave.

20 feet. Flying cadet applicants are required to read letters double that size, 20 millimeters tall, from the 20-foot distance. Twenty millimeters is slightly more than three-fourths of an inch. Try it yourself. "Just normal visual acuity," the flight surgeons declare.

Another test of the eyes is depth perception, ability to judge comparative distances of objects. Two black rods are mounted on a sliding base. Strings are attached to these rods so that the pilot-to-be can move them from a distance. The idea is to adjust the rods so that they will be more or less equidistant from your eyes. An error of 30 millimeters is allowed by the air corps. "Just normal," medicos say, for some persons can adjust the sticks with an error as small as five millimeters.

Still another eye test—color blindness. If the applicant has trouble in distinguishing the "stop" light from the "go" light, he will probably have difficulty in passing this phase. Otherwise his chances are good.

"Perimetric field of vision," is another eye test. Test yourself by holding your head steady while a friend moves a pencil about two feet from your left ear. Have him gradually jiggle it forward, upward, downward. Can you see it in these various positions? If you can, your field of vision is in all probability sufficiently broad.

"My heart's O. K.," all applicants boastfully declare when that portion of the exam starts. Perhaps it is and perhaps it isn't. Blood pressure reclining, pulse rate reclining, both are checked against the same readings taken while standing up and, also, after exercise. A numerical value is given each reading, and all combine to give a final result. An 18 is perfect, the medicos say, but potential pilots need only a plus 8. "Just normal," they reiterate.

Flying cadet applicants are spun round and round in a Barany chair to test the reactions of the middle ear, where the sense of balance is located. A check on the blood pressure is made meanwhile. Occasionally a candidate has difficulty with this phase, but not often.

Can you make your hands and feet behave? Well, let's see. Get into the chair of the Automatic Serial Reaction Machine. Facing the applicant are three double rows of lights. One row is red, the other green. Also in front of the cadet-to-be is a control stick and rudder pedals, similar to the controls of a plane. Instead of controlling a plane they control the lights. The entire machine is automatic from this point on. Three red lights flash on, and you move the controls until the green lights are lighted directly opposite the red ones. When correct, the time to perform this task is registered. Another set of red lights flashes on, and then another and another until the applicant has solved forty settings. This determines his reaction time.

That's about all to the physical examination except the psychological test which consists merely of a chat with a flight surgeon. He probes your mind, seeking for any hidden phobias that may exist, even without your knowledge.

Fine Feathers Make Fine Birds

(Continued from page 17)

Early models, although of sound aërodynamical design, lacked power and consequently were slow, sluggish, and hardly suitable for cross-country flying. Much of the credit for the present perfection of the light plane must be given the engine manufacturers because of the constant improvements made in their efficient little power plants. It was the fifty-horsepower engine appearing on the market only in 1938 that really started the current light-plane boom. With the addition of only ten horsepower to the old forty, the little ships started moving along vigorously even under conditions that had previously kept them hopelessly grounded. From the fifty it was a short step to the sixty-fives, seventy-fives, eighties. Each time a few horsepower were added to an engine, the scope of the light plane became greatly enlarged. More power meant more speed. Engineers had to work overtime making refinements on the old flivver. Drag was being eliminated, cabin space made more spacious, larger gas tanks and more baggage space were added, improvements made in the controls and in the landing gear, and the requirements of comfort for pilot and passenger received increased attention.

A wider market caused competition to mount among the manufacturers to a point where luxuries were being installed. Well-known industrial designers were hired to add eye appeal inside and out. The flivver of today can be had in all kinds of fancy color schemes. A streamlined cowl embraces the powerful little engine and the cylinder openings are hidden behind chromium grille work. Some are equipped with engine mufflers and so well soundproofed inside that a conversation can be carried on easily without raising the voice. Brakes and tail wheels are almost standard equipment, as are wheel pants, propeller spinners, cabin heaters and ventilators. Fancy dashboards are well planned to provide for radio, and any number of desired flight instruments and plenty of baggage space are provided. The three-place light plane has been added to the conventional two-place models. One ship, the Stinson 105, is equipped with flaps; another one, the Culver Cadet, with a retractable gear.

Power has been mentioned as one of the main factors in light-plane progress. From current developments in the engine field it would seem that power will play an equally big part in advancements of the immediate future. The geared engine has been introduced and will no doubt see further development. Fuel injection now being featured by one manufacturer, Continental, will eventually eliminate the grave ever-present danger of carburetor icing. And while this is being written news is received of a new six-cylinder light-plane en-

FOR CANADA ONLY

FREE

Canadian Model that Won Moffett Trophy at the 1940 Chicago Nationals

Roy Nelder of Toronto won the Moffett Trophy using this plane with a three flight total of 289.6 seconds.

Gene Chaille of Miami, Florida won the American Wakefield elimination at the 1939 Detroit Nationals with a duplicate model.

The design of the model that won the 1940 trophy was an improvement over Nelder's 1938 plane which won the Moffett Trophy at the Detroit Nationals.

It's the champion of all champions.

The kit of this nearly 4 foot wing-spread model is ABSOLUTELY FREE to Canadian readers only with a year's subscription to AIR TRAILS.

AIR TRAILS
79 Seventh Ave.
New York, N. Y.

Inclosed is $2.00 in U. S. currency. Kindly send me the Nelder kit and a year's subscription to AIR TRAILS. This offer is for Canadian readers only.

NAME .....

ADDRESS .....

CITY .....

STATE .....

Be an AERONAUTICAL ENGINEER

BIG MONEY PAID
EXCEPTIONAL OPPORTUNITIES

Big demand for Aeronautical Engineers. Lincoln's 2 year course including wide practical experience in Airplane design and construction, prepares you for lifetime career in this fascinating field. Course adjustable to high school or college graduates. Next class starts January. **BE AN AIRLINE MAINTENANCE MECHANIC** Lincoln's Government Approved Mechanics Training prepares for responsible position with Airline or at Airport as Gov't. Rated Airplane and Engine Mechanic. These Graduates taking fine good-pay positions. Jobs for many more.

BE A COMMERCIAL PILOT Lincoln Government Approved Flight Training prepares you for BOTH a Commercial Pilot and Flight Instructor Rating.

ACT NOW Get Lincoln's book "Contact" It tells How Men are Trained for Aviation. **WRITE TODAY** for complete information.

LINCOLN AERONAUTICAL INSTITUTE, INC.
LINCOLN AIRPLANE & FLYING SCHOOL DIVISION
1712 Aircraft Building Lincoln, Nebraska

$2.50 POSTPAID
19 INCH KIT
SCALE MODEL
U. S. SUBMARINE

Water ballast chamber and air control valve for diving. Runs on surface or under water. 54 parts ready to assemble. Die cast conning tower—naval gun—keel parts.
19 inch Model completely assembled.....$3.50 P. P.
13 inch Kit 40 parts ready to assemble.....$1.25 P. P.
18 inch Model completely assembled.....$1.75 P. P.
Send 3c stamp for catalog of other models.
WESTLAKE MODEL CO., DEPT. AT 124, ERIE, PA.

CLASS "A"—*Attention*

Chicago's Foremost Model Shop presents only the latest and the best approved accessories for immediate shipment.

MADEWELL MITE	now only	$ 7.50
Mighty Atom		12.50
Megow "199"		12.50
Ohlsson "19"		14.50
Bantam "Deluxe"		16.50
New Tiny lightweight Austin Timer	only	1.00
NEW Smith Competitor Coil	only	1.75
Pen Cell Battery Box		.35
Champion Spark Plugs	all sizes	.65 ea.
A C Spark Plugs	all sizes	.65 ea.
Blue Crown Spark Plugs	all sizes	.50 ea.

Orders under $2.00 add 15c postage, over $2.00 postpaid.

***Trost* Model Airplane Shop**
3111 WEST 63rd ST., CHICAGO, ILL.

FREE ENLARGEMENT

Just to get acquainted with new customers, we will beautifully enlarge one snapshot print or negative, photo or picture to 8x10 inches—FREE—if you enclose this ad with 10c for handling and return mailing. Information on hand tinting in natural colors sent immediately. Your original returned with your free enlargement. Send it today.

Geppert Studios, Dept. 574, Des Moines, Iowa

NEW BOOKS

AERONAUTICAL TRAINING—Prepares pilots, all grades, for written test.....$2.00
RADIO AND INSTRUMENT FLYING—Prepares pilot for written examination.....$4.00
(Includes Radio-Telephone examination)
FLIGHT INSTRUCTOR MANUAL.....$2.00
(Prepares the pilot for written test)
AIRPLANE & ENGINE MECHANICS quiz text, covering all subjects for mechanics' rating....$3.00
These texts are question and answer form and will be sent C.O.D. or postpaid.

QUIZ SYSTEM Dept. A.T. 1435 Flower Street
Grand Central Air Terminal Glendale, Calif.

---

37 AUTHENTIC DETAILED SKETCHES OF THE LATEST U. S. ARMY, NAVY, AND COMMERCIAL AIRCRAFT, REPRODUCED ON HEAVY WHITE VELLUM PAPER, 9½ BY 12½ INCHES.

SEND TEN CENTS FOR SAMPLE SKETCH AND OUR NEW CATALOG

DEALERS: WRITE FOR PRICES

CRAFT ART COMPANY DEPT. 12T
246 FIFTH AVE. NEW YORK, N. Y.

gine with an output of well over one hundred horsepower.

In addition to all these improvements, one singularly outstanding development has taken concrete shape after years of discussion and spasmodic experiments, and that concerns simplicity and safety in flying. Light planes today seem to have an inherent dislike for anything except conventional and safe flying maneuvers. Although the recklessness and carelessness in human nature can't be erased, one can incorporate features in the machine that will do much toward canceling these faults. Wing slots incorporated in two of the most popular models, Culver and Stinson, are making it difficult to stall these particular ships to a point where they will fall off into a dangerous spin.

But the most significant innovation we've come across personally is a new light plane which is fundamentally designed as a safe flying machine without sacrifice in speed and essential maneuverability. We call it new because production got under way only last fall, although it has been in the making for, believe it or not, a period of ten years, and its prototype was flown and demonstrated more than a year ago. We refer to the Ercoupe, one of which we had the good fortune to pilot recently. That was an enlightening experience!

The Ercoupe is an all-metal, low-wing light plane powered by sixty-five horses and equipped with a tricycle gear. This landing gear in itself offers numerous advantages. It permits the ship to be taxied in level position with lots of visibility from the cockpit over the straight nose. Landing can be made in a straight line with a minimum of "leveling off" and without any danger of the ship going over on its nose once the landing has been accomplished. Once contact has been made with the ground the wheels stay there with a surprising tenacity and there is no tendency to bounce because the center of gravity is well forward in the nose. Any excess speed resulting from a steep approach is quickly and effectively killed by full application of the brakes which act simultaneously on all three wheels of the tricycle gear. No matter how sudden and how hard the application of the brakes, there is no danger of putting her over on the nose due to the little third wheel far out front under the nose.

This wheel is steerable and hooked up to the rudder controls. In the two-control version of the Ercoupe the rudder and aileron controls in turn are actuated simultaneously by turning the control wheel. Hence, taxiing of the ship around the field is little different from driving a car and can be mastered by anybody used to the wheel of the automobile. Even more surprising is the simplicity of handling the ship in the air. In order to make a turn you again simply move that little steering wheel, and ailerons and rudder automatically combine in swinging the ship around in a nicely banked curve in the sky. Co-ordination of controls, the headache of many a fledgling pilot, need not worry him in the Ercoupe, because it is fully automatic. Should he throw the wheel over too hard the aileron will automatically be neutralized and prevent the ship from wheeling into a dangerous vertical bank.

Most astounding feature of all, however, was the absolute and stubborn refusal of the machine to spin after it has been stalled. When you are thumbing through the sad pages of an accident report you will read the same story over and over again; the story of the stall that crept up on the pilot and of the subsequent spin that seized control of the ship from his struggling hands. The Ercoupe, we found, definitely will not spin. Pull its nose up high with full throttle or with power off and she will stall, naturally. That is, she will lose all flying speed, but she will not drop a wing and tear away in a dizzy spin. All that will happen is that the nose will drop to a point where the ship automatically recovers its necessary flying speed. When the ship was being test-flown for licensing by the C.A.B., its best pilots failed either to coax or to force it into a spin, and when tests were completed the Ercoupe was given an official license as an absolutely "spinproof" plane, the first license of its kind ever given to a ship.

So enthusiastic are they about the built-in safety features of the ship that a group of C.A.B. students at College Park, Maryland, was assigned to a flight course in the Ercoupe and the experiments proved that piloting of this type of craft can be mastered in a considerably shorter period of time than in the conventional airplane. Students taking part in this special course were soloed in as little as three hours, and were all prepared for a private pilot's rating in as little as fifteen hours, or about half the time required ordinarily.

The tricycle gear, simplified controls and the spinproof wing are here to stay. The trend has been established and other manufacturers no doubt will follow suit.

From here it may be only a short step to the roadable airplane, discussion of which is already being revived in aviation circles. A few years from now my friend Joe perhaps no longer will have two flivvers, one for the road and one for the sky. Perhaps he will return from a cruise in the sky to his small field in New Jersey some day, set his three wheels down on the runway with perfect ease, fold his wings or store them with the operator, blow the horn and roll home on Route 22 without changing vehicles.

In the next issue read

PILOTLESS PLANES

Latest Developments in Radio Control

Be a Radio Technician

Learn at Home to Make $30, $40, $50 a Week

Radio is a young, growing field with a future offering many good pay spare time and full time job opportunities. And you don't have to leave home to become a Radio Technician. I train you right at home in your spare time.

Why Many Radio Technicians Get Good Jobs at Good Pay

Radio broadcasting stations employ operators, technicians. Radio manufacturers employ testers, inspectors, servicemen, in good-pay jobs. Radio jobbers, dealers, employ installation and servicemen. Many Radio Technicians open their own Radio sales and repair businesses and make $30, $40, $50 a week. Others hold their regular jobs and make $5 to $10 a week fixing Radios in spare time. Automobile, Police, Aviation, Commercial Radio; Loudspeaker Systems, Electronic Devices are other fields of-N.R.I. gives the required knowledge of Radio. Television promises to open good jobs soon.

Chief Operator Broadcasting Station

"Before I completed your lessons, I obtained my Radio Broadcast Operator's license and immediately joined Station WMPC, where I am now Chief Operator." HOLLIS F. HAYES, 327 Madison St., Lapeer, Michigan.

$200 to $300 a Month in Own Business

"For the last two years I have been in business for myself making between $200 and $300 a month. Business has steadily increased. I have N.R.I. to thank for my start in this field." ARLIE J. FROEHNER, 300 W. Texas Ave., Goose Creek, Texas.

$15 a Week Extra in Spare Time

"I am doing spare time Radio work, and I am averaging from $700 to $850 a year. Those extra dollars mean so much — the difference between just barely getting by and living comfortably." JOHN WASHKO, 97 New Cranberry, Hazleton, Penna.

Many Make $5 to $10 a Week Extra in Spare Time While Learning

The day you enroll, I start sending you Extra Money Job Sheets —start showing you how to do Radio repair jobs. Throughout your course I send plans and directions which have helped many make $5 to $10 a week in spare time while learning. I send special Radio equipment to conduct experiments and build circuits. My 50-50 training method makes learning at home interesting, fascinating, practical. YOU ALSO GET A MODERN, PROFESSIONAL, ALL-WAVE, ALL-PURPOSE SET SERVICING INSTRUMENT to help you make money fixing Radios while learning and equip you for full time work after you graduate.

Find Out What Radio And Television Offer You— Mail Coupon

Act TODAY! Mail the coupon for my 64-page Book, "Rich Rewards in Radio." It points out Radio's spare time and full time opportunities and those coming in Television; tells about my course in Radio and Television; shows more than 100 letters from men I have trained, telling what they are doing and earning. Read my money back agreement. MAIL COUPON in an envelope, or paste on a penny postcard—NOW!

J. E. SMITH, President
Dept. OMM
National Radio Institute
Washington, D. C.

Mail this Now FREE
Get 64-page Book

Mr. J. E. Smith, President
Dept. OMM
National Radio Institute
Washington, D. C.

Mail me FREE without obligation, your 64-page book "Rich Rewards in Radio." (No salesman will call. Write Plainly.)

AGE.....
NAME .....
ADDRESS .....
CITY..... STATE.....

CONTEST MODELS THAT HAVE NO EQUAL

HENRY STRUCK'S "AMERICAN ACE"

For "A", "B" or "C" Competition

54 INCH WINGSPAN

WINNER OF 3 OUT OF 10 PLACES AT 1940 NATIONALS

Those who attended the 1940 National went home remembering the standout model, Henry Struck's "New Ruler." Not even introduced in kit form, it was one of the most popular ships on the field. Before the contest, the "American Ace" was designed mainly for competition in Class "B" but also suitable for small Class "C" and large Class "A" engines. The sensational "New Ruler" design in Air Trails was its inspiration. No ship has ever been designed with such painstaking care and precision. A flyer, beyond doubt, the leader in its class for contest competition.

54" Wingspan
Removable Nose & Motor Mount
Ready-Made Landing Gear
Printed Out Wood Parts
Silk for Pylon and Wing Center
Semi-Finished Wood Blocks
Streamlined Rubber Wheels
Carved Propeller

$3.95 P.P.

Plus all the features exclusively in BERKELEY Kits. Complete Hardware and Ignition Equipment. Championship BERKELEY Cement and Dope, Premier Quality Balsa, AND Complete Full Sized Plans.

BUCCANEER "SPECIAL"

THE MYSTERY SHIP OF GAS MODELS

6 FT. WINGSPAN
3 LBS. COMPLETE

$5.95 P.P.

Where does it get its speed? What ship gives performance anything like it? Purposely withheld from the 1940 Nationals, it is setting up records throughout the country. Letters are pouring in, "constructed like a battle cruiser, yet lighter than average models," "BERKELEY has a model to be proud of," "three and one-half minutes on the very first flight with the motor barely turning over."

The kit has the completeness of all BERKELEY Kits, including: Silkspan covering and BERKELEY Time-Air Flight Timer

HENRY STRUCK'S FLYING CLOUD

44 INCH WINGSPAN

$1.00

Winner of four places, more FLYING CLOUDS were lost out-of-sight in the clouds at the Chicago Nationals than any other design. Truly a grand flyer.

Propeller retracts flush into fuselage sides in glide. Kit complete $1. 10c extra by mail.

NEW Class "A"s BUCCANEER "36"

For ATOM Or MADEWELL MOTORS WINGSPAN **36 INCH**

$1.50 P.P.

The newest Buccaneer and really living up to its name. A flyer made especially for the small motor.

AMERICAN ACE "36"

$1.50 P.P.

The sensation caused by the American Ace made us realize that it surely would be popular with builders of small gas models. Faithfully reproduced, the "36" carries the clean lines and perfect stability of the larger ship. It features a removable motor mount allowing for easy access to the motor.

BERKELEY MODELS INC.

230 STEUBEN ST. Dept. AT-12 BROOKLYN, N. Y.

Air Trails Advertisers December 1940

SCHOOLS

Aero Industries Technical Institute . . . . . Back Cover
Aeronautical University 55
California Flyers 7
Curtiss Wright Technical Institute . 5
Lincoln Aeronautical Institute, Inc. . 65
Luscombe School of Aeronautics . . 4
Mechanix Universal Aviation Service . . . . . 54 & 57
Meyer Engineering 58
National Radio Institute 65
Parks Air College 3

MODEL AIRPLANE KITS, MOTORS and SUPPLIES

Academy of Model Aeronautics . . 61
Aircraft . . . . . Third Cover
Aldine Paper Co. 43
American Supercraft Corp. . . . 63
Bay Ridge Model & Supply Co. . . 42
Beebe Products 54
Berkeley Models, Inc. 66
Best by Test Model Co. 55
Bill's Model Hangar 66
Capitol Aircraft & Supply Co. . . 48
Cleveland Model & Supply Co. . . . . Second Cover
C Z Model Airplane Co. 60
Flo-Torque Propellers 53
Tex Foster 60
G. H. Q. Motors 41
Paul K. Guillow 43
Herkimer Tool & Model Works . . 43
H. & F. Model Airplane Co. . . . 55
Hobby-Land 66
Hodgman Rubber Co. 58
Ideal Airplane & Supply Co. . . . 60
Imperial Model Aero Supply . . . 49
International Model Products . . . 57
Junior Motors Corp. . . . . 56 & 57
Lehr-O-Plane Co. 54
Megow's 61
Mercury Model Airplane Co. . . . 50
Microdyne Engines, Inc. 47
Miniature Aircraft Corp. 49
Modelcraft 52
Model Research Labs. 57
Ohlsson & Rice Mfg. Co. 58
Phantom Motors 6
Plane-Craft 58
Scientific Model Airplane & Supply Co. 51
Selley Mfg. Co. . . . . 53 & 58
Skyway Model Aircraft Supply Co. . 63
M. B. Spotts 43
Victor Stanzel & Co. 62
St. John Model Shop 59
Syncro Devices, Inc. . . . . 48 & 64
Testor Cement Co. 46
Trenton Hobby Centre 60
Triangle Model Supply Co. 59
Trost Model Airplane Shop 65
Waterbury Model Builders Supply . 60
Whitfield Paper Co. 54

MISCELLANEOUS

D. Appleton Century Co. 57
Craft Art Co. . . . . 54 & 65
John De Vine 53
Funk & Wagnalls Co. 45
Geppert Studios 65
Gun Model Co. 58
Harley Davidson Motor Co. . . . 54
Jardur Import Co. 50
Lionel Corp. 49
Robert M. McBride & Co. 53
Midget Radio Co. 60
National Carbon Co. 59
Karl Ort . . . . . 44 & 66
Quiz System 65
L. C. Smith & Corona Typewriters . 66
Speedway Mfg. Co. 66
Westlake Model Co. 65

CORONA'S THE BUY THIS CHRISTMAS

Corona offers three Speedline Models to choose from—each equipped with famous Floating Shift. Priced from $49.50 to $64.50. Also two Zephyr Coronas . . . the top values of their price class. Corona Zephyr, $29.75, De Luxe Zephyr, $34.75. Go now to your Corona Dealer. You can buy any Corona on a pay as you type plan.

CORONA

L C SMITH & CORONA TYPEWRITERS INC
Desk 12, 145 Almond Street, Syracuse, New York

This ad is IMPORTANT to YOU!

DON'T hunt around for bargains. Our prices can't be beat. DON'T delay. Send for our FREE complete price list of gas model and rubber powered supplies.

BILL'S MODEL HANGAR
3428 West Belden Ave. Chicago, Ill.

FOR CHRISTMAS $14.95
A COMPLETE AIRPLANE WITH MOTOR!

For class "A" competition

This Sensational Offer Includes:
Megow "199" motor
Aero Champ Gas Model
Pair rubber wheels
Rite Pitch Propeller
Flight timer

BROWN MODEL E in stock $7.50
SYNCRO in stock.....$6.95
Immediate delivery
Anything and everything in model airplanes, boats, etc.

HOBBY-LAND
371-MAIN STREET :: HACKENSACK, N. J.

Be an AERONAUTICAL ENGINEER

BIG MONEY PAID
EXCEPTIONAL OPPORTUNITIES

Big demand for Aeronautical Engineers. Lincoln's 2 year course including wide practical experience in Airplane design and construction, prepares you for lifetime career in this fascinating field. Course adjustable to high school or college graduates. Next class starts January. **BE AN AIRLINE MAINTENANCE MECHANIC** Lincoln's Government Approved Mechanics Training prepares for responsible position with Airline or at Airport as Gov't. Rated Airplane and Engine Mechanic. These Graduates taking fine good-pay positions. Jobs for many more.

BE A COMMERCIAL PILOT Lincoln Government Approved Flight Training prepares you for BOTH a Commercial Pilot and Flight Instructor Rating.

ACT NOW Get Lincoln's book "Contact". It tells How Men are Trained for Aviation. **WRITE TODAY** for complete information.

LINCOLN AERONAUTICAL INSTITUTE, INC.
LINCOLN AIRPLANE & FLYING SCHOOL DIVISION
1712 Aircraft Building — Lincoln, Nebraska

$2.50 POSTPAID
19 INCH KIT
SCALE MODEL
U. S. SUBMARINE



Water ballast chamber and air control valve for diving. Runs on surface or under water. 54 parts ready to assemble. Die cast conning tower—naval gun—keel parts.
19 inch Model completely assembled.....$3.50 P. P.
13 inch Kit 40 parts ready to assemble.....$1.25 P. P.
13 inch Model completely assembled.....$1.75 P. P.
Send 3c stamp for catalog of other models.
WESTLAKE MODEL CO., DEPT. AT 124, ERIE, PA.

CLASS "A"—*Attention*

Chicago's Foremost Model Shop presents only the latest and the best approved accessories for immediate shipment.

MADEWELL MITE	now only	$ 7.50
Mighty Atom		12.50
Megow "199"		12.50
Ohlsson "19"		14.50
Bantam "Deluxe"		16.50
New Tiny lightweight Austin Timer	only	1.00
NEW Smith Competitor Coil	only	1.75
Pen Cell Battery Box		.35
Champion Spark Plugs	all sizes	.65 ea.
A C Spark Plugs	all sizes	.65 ea.
Blue Crown Spark Plugs	all sizes	.50 ea.

Orders under $2.00 add 15c postage, over $2.00 postpaid.

***Trost* Model Airplane Shop**
3111 WEST 63rd ST., CHICAGO, ILL.

FREE ENLARGEMENT

Just to get acquainted with new customers, we will beautifully enlarge one snapshot print or negative, photo or picture to 8x10 inches—FREE—if you enclose this ad with 10c for handling and return mailing. Information on hand tinting in natural colors sent immediately. Your original returned with your free enlargement. Send it today.

Geppert Studios, Dept. 574, Des Moines, Iowa

NEW BOOKS

AERONAUTICAL TRAINING—Prepares pilots, all grades, for written test.....$2.00
RADIO AND INSTRUMENT FLYING—Prepares pilot for written examination.....$4.00
(Includes Radio-Telephone examination)
FLIGHT INSTRUCTOR MANUAL.....$2.00
(Prepares the pilot for written test)
AIRPLANE & ENGINE MECHANICS quiz text, covering all subjects for mechanics' rating....$3.00
These texts are question and answer form and will be sent C.O.D. or postpaid.

QUIZ SYSTEM Dept. A.T. 1435 Flower Street
Grand Central Air Terminal — Glendale, Calif.

---

37 AUTHENTIC DETAILED SKETCHES OF THE LATEST U. S. ARMY, NAVY, AND COMMERCIAL AIRCRAFT, REPRODUCED ON HEAVY WHITE VELLUM PAPER, 9½ BY 12½ INCHES.
SEND TEN CENTS FOR SAMPLE SKETCH AND OUR NEW CATALOG
DEALERS: WRITE FOR PRICES
CRAFT ART COMPANY DEPT. 12T
246 FIFTH AVE. NEW YORK, N. Y.

gine with an output of well over one hundred horsepower.

In addition to all these improvements, one singularly outstanding development has taken concrete shape after years of discussion and spasmodic experiments, and that concerns simplicity and safety in flying. Light planes today seem to have an inherent dislike for anything except conventional and safe flying maneuvers. Although the recklessness and carelessness in human nature can't be erased, one can incorporate features in the machine that will do much toward canceling these faults. Wing slots incorporated in two of the most popular models, Culver and Stinson, are making it difficult to stall these particular ships to a point where they will fall off into a dangerous spin.

But the most significant innovation we've come across personally is a new light plane which is fundamentally designed as a safe flying machine without sacrifice in speed and essential maneuverability. We call it new because production got under way only last fall, although it has been in the making for, believe it or not, a period of ten years, and its prototype was flown and demonstrated more than a year ago. We refer to the Ercoupe, one of which we had the good fortune to pilot recently. That was an enlightening experience!

The Ercoupe is an all-metal, low-wing light plane powered by sixty-five horses and equipped with a tricycle gear. This landing gear in itself offers numerous advantages. It permits the ship to be taxied in level position with lots of visibility from the cockpit over the straight nose. Landing can be made in a straight line with a minimum of leveling off and without any danger of the ship going over on its nose once the landing has been accomplished. Once contact has been made with the ground the wheels stay there with a surprising tenacity and there is no tendency to bounce because the center of gravity is well forward in the nose. Any excess speed resulting from a steep approach is quickly and effectively killed by full application of the brakes which act simultaneously on all three wheels of the tricycle gear. No matter how sudden and how hard the application of the brakes, there is no danger of putting her over on the nose due to the little third wheel far out front under the nose.

This wheel is steerable and hooked up to the rudder controls. In the two-control version of the Ercoupe the rudder and aileron controls in turn are actuated simultaneously by turning the control wheel. Hence, taxiing of the ship around the field is little different from driving a car and can be mastered by anybody used to the wheel of the automobile. Even more surprising is the simplicity of handling the ship in the air. In order to make a turn you again simply move that little steering wheel, and ailerons and rudder automatically combine in swinging the ship around in a nicely banked curve in the sky. Co-ordination of controls, the headache of many a fledgling pilot, need not worry him in the Ercoupe, because it is fully automatic. Should he throw the wheel over too hard the aileron will automatically be neutralized and prevent the ship from wheeling into a dangerous vertical bank.

Most astounding feature of all, however, was the absolute and stubborn refusal of the machine to spin after it has been stalled. When you are thumbing through the sad pages of an accident report you will read the same story over and over again; the story of the stall that crept up on the pilot and of the subsequent spin that seized control of the ship from his struggling hands. The Ercoupe, we found, definitely will not spin. Pull its nose up high with full throttle or with power off and she will stall, naturally. That is, she will lose all flying speed, but she will not drop a wing and tear away in a dizzy spin. All that will happen is that the nose will drop to a point where the ship automatically recovers its necessary flying speed. When the ship was being test-flown for licensing by the C.A.B., its best pilots failed either to coax or to force it into a spin, and when tests were completed the Ercoupe was given an official license as an absolutely "spinproof" plane, the first license of its kind ever given to a ship.

So enthusiastic are they about the built-in safety features of the ship that a group of C.A.B. students at College Park, Maryland, was assigned to a flight course in the Ercoupe and the experiments proved that piloting of this type of craft can be mastered in a considerably shorter period of time than in the conventional airplane. Students taking part in this special course were soloed in as little as three hours, and were all prepared for a private pilot's rating in as little as fifteen hours, or about half the time required ordinarily.

The tricycle gear, simplified controls and the spinproof wing are here to stay. The trend has been established and other manufacturers no doubt will follow suit.

From here it may be only a short step to the roadable airplane, discussion of which is already being revived in aviation circles. A few years from now my friend Joe perhaps no longer will have two flivvers, one for the road and one for the sky. Perhaps he will return from a cruise in the sky to his small field in New Jersey some day, set his three wheels down on the runway with perfect ease, fold his wings or store them with the operator, blow the horn and roll home on Route 22 without changing vehicles.

In the next issue read

PILOTLESS PLANES

Latest Developments in Radio Control

Be a Radio Technician

Learn at Home to Make $30, $40, $50 a Week

Radio is a young, growing field with a future offering many good pay spare time and full time job opportunities. And you don't have to leave home to become a Radio Technician. I train you right at home in your spare time.

Why Many Radio Technicians Get Good Jobs at Good Pay

Radio broadcasting stations employ operators, technicians. Radio manufacturers employ testers, inspectors, servicemen, in good-pay jobs. Radio jobbers, dealers, employ installation and servicemen. Many Radio Technicians open their own Radio sales and repair businesses and make $30, $40, $50 a week. Others hold their regular jobs and make $5 to $10 a week fixing Radios in spare time. Automobile, Police, Aviation, Commercial Radio; Loudspeaker Systems, Electronic Devices are other fields of N.R.I. gives the required knowledge of Radio. Television promises to open good jobs soon.

Chief Operator Broadcasting Station

"Before I completed your lessons, I obtained my Radio Broadcast Operator's license and immediately joined Station WMPC, where I am now Chief Operator." HOLLIS F. HAYES, 327 Madison St., Lapeer, Michigan.

$200 to $300 a Month in Own Business

"For the last two years I have been in business for myself making between $200 and $300 a month. Business has steadily increased. I have N.R.I. to thank for my start in this field." ARLIE J. FROEHNER, 300 W. Texas Ave., Goose Creek, Texas.

$15 a Week Extra in Spare Time

"I am doing spare time Radio work, and I am averaging from $700 to $850 a year. Those extra dollars mean so much — the difference between just barely getting by and living comfortably." JOHN WASHKO, 97 New Cranberry, Hazleton, Penna.

Many Make $5 to $10 a Week Extra in Spare Time While Learning

The day you enroll, I start sending you Extra Money Job Sheets —start showing you how to do Radio repair jobs. Throughout your course I send plans and directions which have helped many make $5 to $10 a week in spare time while learning. I send special Radio equipment to conduct experiments and build circuits. My 50-50 training method makes learning at home interesting, fascinating, practical. YOU ALSO GET A MODERN, PROFESSIONAL, ALL-WAVE, ALL-PURPOSE SET SERVICING INSTRUMENT to help you make money fixing Radios while learning and equip you for full time work after you graduate.

Find Out What Radio And Television Offer You— Mail Coupon

Act TODAY! Mail the coupon for my 64-page Book, "Rich Rewards in Radio." It points out Radio's spare time and full time opportunities and those coming in Television; tells about my course in Radio and Television; shows more than 100 letters from men I have trained, telling what they are doing and earning. Read my money back agreement. MAIL COUPON in an envelope, or paste on a penny postcard—NOW!

J. E. SMITH, President
Dept. OMMI
National Radio Institute
Washington, D. C.

Mail this Now FREE
Get 64-page Book

Mr. J. E. Smith, President
Dept. OMMI
National Radio Institute
Washington, D. C.

Mail me FREE without obligation, your 64-page book "Rich Rewards in Radio." (No salesman will call. Write Plainly.)

AGE.....
NAME .....
ADDRESS .....
CITY..... STATE.....

JUST OUT! SCALE MODELS of WORLD FAMOUS WAR SHIPS!

Complete Kits! Moulded Hull! Easy to Build!

Graf Spee 25c


German Submarine 25c

Exeter 25c

Achilles and The Ajax 25c

Navy Tugboat 25c

Royal Oak 25c

AIRCRAFT OFFERS WORLD'S FINEST LINE OF SOLID MODELS! *JUST LOOK!*

S E 5 Pursuit 25c

Fokker Tripe 25c


Spad 13 25c

Sopwith Camel 25c

Complete List of 25c Kits!

AERONCA	HAWK P6E
ALBATROSS	HEINKEL
BOEING F4B3	MESSERSCHMITT
BOEING F4B4	MONOCOUPE
BOEING P12E	MULLIGAN
BOEING P12F	NIEUPORT
BOEING P26A	NORTHRUP
BREWSTER	LAIRD RACER
CAMEL	REARWIN
FOKKER D7	S E 5
FOKKER D8	SEVERSKY
FOK. TRIPE	SPAD
GOSHAWK	WACO

NO EXTRAS TO BUY!

Aircraft airplane kits contain cut-to-shape wood—wheels—propeller—cast motor and paint! Biggest kit value on market! Enjoy the thrill of building world-famous planes in miniature form!

BUILD THESE SCALE MODELS OF FAMOUS RACE CARS!

Shaw's Masseratti 50c

Miller "23" 50c

Thorne Sparks Special 50c

German Auto Union 50c

Complete Line of New Kits Rushed to Dealers Everywhere!

Step into your Model Dealer and see the new line of Warships, Race Cars and Airplanes! . . . Imagine the thrill of building warships that are making history—planes that are world-famous—and race cars that are record breakers! Say, if you've never built solid models before, you really have a new thrill waiting. And if you are a regular model builder, you'll recognize the super-value in Aircraft kits instantly! So see your dealer today! Get Aircraft—and get more for your money!

If your dealer can't supply you, send the amount shown under model plus 10 cents for postage and packing; or 5 cents per kit when you order two or more. Get started now!

AIRCRAFT, *Dept. A-12, 4024 North Elston Avenue, Chicago, Ill.*

A NEW CEILING
with the Stratoliners

A NEW *Success* CEILING
For the Aero ITI-trained men building these great transports

Like these fellows, how proud YOU would feel to be connected with the famous aircraft builder whose huge Stratoliners have made possible airline flight thousands of feet higher than ever before. But how much MORE pleased you would be to—like these men—have won your start in Aviation with a training that also gives YOU a new "ceiling"... for success!

Aero ITI training does not stop at preparing you to step right into aircraft work. It gives you the broad, diversified aeronautical knowledge and abilities to merit steady advancement... to enjoy security... to *go farther* in Aviation.

Aviation is calling YOU, too. Answer its call with THIS kind of training. Get complete information on Aero ITI's Aeronautical Engineering and Master Aircraft Mechanics courses... which have won for Aero ITI and its graduates a high standing in the great aviation industry. Send the coupon NOW.

AERO INDUSTRIES TECHNICAL INSTITUTE

5257 West San Fernando Road Los Angeles, California

Five Courses In
AIRCRAFT MECHANICS and AERONAUTICAL ENGINEERING
—Including 12 Month Aircraft Mechanics Course Approved by U.S. Civil Aeronautics Board

AERO INDUSTRIES TECHNICAL INSTITUTE
5257 West San Fernando Road, Los Angeles, California

Please send information on Aero ITI training for Aviation careers. I am interested in the following branch of Aviation: ☐ Aircraft Mechanics; ☐ Aeronautical Engineering; ☐ Undecided, please send more information. Years High School: ☐ 1, ☐ 2, ☐ 3, ☐ 4. Years College (Liberal Arts): ☐ 1, ☐ 2, ☐ 3, ☐ 4. Years Engineering College: ☐ 1, ☐ 2, ☐ 3, ☐ 4.

Name_____ Age_____

Address_____

City_____ State_____ a-36-T

EXECUTIVE BOARD

ROBERT E. GROSS
President, Lockheed Aircraft Corporation

JOHN K. NORTHROP
President, Northrop Aircraft, Inc.

C. A. VAN DUSEN
Vice-Pres., Consolidated Aircraft Corporation

These leading Aviation industry executives supervise the policies and operation of Aero Industries Technical Institute.

This Advertisement appears in AIR TRAILS Dec. 1940